

Products						
PlotID	Length	Product	Plies	Net Qty	Fab Type	
FJ1	29-0-6	14" NI-40x	1	8	FF	
FJ2	28-9-6	14" NI-40x	1	2	FF	
FJ3	28-8-7	14" NI-40x	1	4	FF	
FJ4	19-0-9	14" NI-40x	1	1	FF	
FJ5	14-6-9	14" NI-40x	1	4	FF	
FJ6	14-1-14	14" NI-40x	1	1	FF	
FJ7	13-10-8	14" NI-40x	1	3	FF	
FJ8	9-10-2	14" NI-40x	1	2	FF	
FJ9	7-4-5	14" NI-40x	1	3	FF	
FJ10	7-1-14	14" NI-40x	1	1	FF	
FJ11	6-10-2	14" NI-40x	1	1	FF	
BM6	13-0-0	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF	
RPB1	12-0-0	1-3/4"x 9-1/4" LVL Kerto-S	2	4	FF	
DB1	8-0-0	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF	
FB6	7-0-0	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF	
Front GDH	22-0-0	1-3/4"x 11-7/8" LVL Kerto-S	3	3	FF	
FB1	20-0-0	1-3/4"x 14" LVL Kerto-S	2	2	FF	
FB2	16-0-0	1-3/4"x 14" LVL Kerto-S	3	3	FF	
FB3	7-0-0	1-3/4"x 14" LVL Kerto-S	2	2	FF	
FB4	4-0-0	1-3/4"x 14" LVL Kerto-S	1	2	FF	
FB5	22-0-0	1-3/4"x 23-7/8" LVL Kerto-S	3	3	FF	
RIM1	12-0-0	1 1/8" x 14" Rim Board	1	9	FF	
Bk1	2-0-0	14" NI-40x	1	1	FF	

	THD410	USP	4	NA	16d/3-1/2"	10d/3"
	THF25140	USP	24	NA	10d/3"	10d/3"

<u>Truss Placement Plan</u> SCALE: 3/16"=1'

= Indicates Left End of Truss
(Reference Engineered Truss Drawing)
Do NOT Erect Truss Backwards

LOAD CHART FOR JACK STUDS								s
	(BASED ON TABLES R502.5(1) & (b)) NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADER/GIRDER							
	END REACTION (UP TO)	REQ D STUDS FOR (2) PLY HEADER		END REACTION (UP TO)	REQ'D STUDS FOR (3) PLY HEADER		END REACTION (UP TO)	REQ'D STUDS FOR (4) PLY HEADER
	1700	1		2550	1		3400	1
	3400	2		5100	2		6800	2
	5100	3		7650	3		10200	3
	6800	4		10200	4		13600	4
	8500	5		12750	5		17000	5
	10200	6		15300	6			
	11900	7						
	13600	8						
	15300	0						

_		_			
BUILDER	Caviness & Cates Communities	CITY / CO.	Cameron / Harnett	THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.  These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designe is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beam walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSI-B1 and BCSI-B3 provided with the truss delivery packa or online @ sbcindustry.com  Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tab ( derived from the prescriptive Code requirements ) to determine the minimum foundation size and number of wood studs required to support reactions great than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.  MAGNATURE OF THE STATE OF THE S	
JOB NAME	Lot 44 Anderson Creek	ADDRESS	Lot 44 Anderson Creek		
PLAN	CC-2680 / 2ND FLOOR I-JOIST LF2	MODEL	31500		
SEAL DATE	3/30/21	DATE REV.	04/21/22		
QUOTE#	\$2680 I-JFL	DRAWN BY	Marshall Naylor		
JOB#	J0422-2016	SALES REP.	Scot Duncan	Marshall Naylor	



Phone: (910) 864-8787 Fax: (910) 864-4444