Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 195 Rocking Canal PI (US 401) ISSUED TO: JSJ Builders SUBDIVISION Williams Farm REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance: Type of Structure: 37'x52' SFD Proposed Wastewater System Type: 25% reduction Projected Daily Flow: 480 Number of Occupants: 8 Number of bedrooms: 4 Basement Yes May be required based on final location and elevations of facilities Pump Required: Yes No Type of Water Supply: Community Public Well Distance from well feet X Five years Permit valid for: No expiration Permit conditions: Authorized State Agent:: Mac NEHS Date: 07-07-22 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. This Date: 07-07-22 site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. PROPERTY LOCATION: 195 Rocking Canal PI (US 401) ISSUED TO: JSJ Builders SUBDIVISION Williams Farm Facility Type: 37'x52' SFD Expansion X New Basement? Yes Basement Fixtures? Yes 25% reduction (Initial) Wastewater Flow: 480 Type of Wastewater System** (See note below, if applicable) pump to 25% reduction Number of trenches 3 Installation Requirements/Conditions Exact length of each trench 80 Trench Spacing: 9 Feet on Center Septic Tank Size 1000 gallons Soil Cover: 6 Trenches shall be installed on contour at a Pump Tank Size _____ gallons Maximum Trench Depth of: 30-18 (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) inches below pipe Pump Requirements: ft. TDH vs. _ Aggregate Depth: ______ inches above pipe inches total Conditions WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Authorized State Agent: Mal

Date: 07-07-22

Construction Authorization Expiration Date: 07-07-27

Harnett County Department of Public Health Site Sketch

| Property Location: 195 Roc | king Canal PI (US 401) | |
|--|---------------------------|-----------------|
| Issued To: JSJ Builders | Subdivision Williams Farm | Lot # <u>14</u> |
| A Company of the Comp | Man Ch REHS | Date: 07-07-22 |

