

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT ~~18~~ → 14

INITIAL SYSTEM: ^{GRAV} APPROVED 25% REDUCTION

REPAIR ^{GRAV} Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION T.S FC 14/15

NO. BEDROOMS: 5

LTAR 0.6 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH	
I {	1	G	97.25	100
	2	P	97.00	100
	3a	G	96.75	50
			<u>250</u>	
R {	3b	G	96.75	50
	4	P	96.59	100
	5	G	96.33	100
			<u>250</u>	

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-21 LS vfri gran

CUTTING, LOGGING OR OTHER SOIL

21-36 sloom fri gran

DISTURBANCE IN SEPTIC AREA

OR 2 > 39"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

width - as wide as lot
allows
Depth = 60'

Liberty Meadows Lot ~~15~~ & ~~16~~
14 15

