

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT ~~14~~ → 13

^{GRAV}
INITIAL SYSTEM: APPROVED 25% REDUCTION

^{GRAV}
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION To S FC 13/14

NO. BEDROOMS: 4

LTAR 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	B	99.75	40
2	R	99.17	60
3	B	97.59	100
4a	R	97.33	40
			240
R { 4b	R	97.33	65
5	B	97.09	110
6	R	96.83	85
			260 AVAIL

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-21 LS vfri gran

CUTTING, LOGGING OR OTHER SOIL

21-36 LSCL firm SBK

DISTURBANCE IN SEPTIC AREA

CR2 ≥ 30"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

12 + 13 unlimited width
50' depth

Liberty Meadows Lot 13 and 14
12 13

