

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows
GRAV
INITIAL SYSTEM: APPROVED 25% REDUCTION

LOT ~~18~~ → 12
Pump
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION ToS FC 13/14

NO. BEDROOMS: 3

LTAR 0.4 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	G	101.92	40
2	O	101.42	95
3	G	100.92	90
4	O	100.33	90
5a	G	99.75	5
			320 AVAIL

R {

5b	G	99.75	95
6	O	99.33	90
7	G	99.00	60
			225

I {

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-24 LS v fri gran

CUTTING, LOGGING OR OTHER SOIL

24-48 SCL firm SBK

DISTURBANCE IN SEPTIC AREA

OR 3' 9"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

12 + 13

unlimited width
50' depth

Liberty Meadows Lot ~~13~~ and ~~14~~
12 13

