

Liberty Meadow  
Lot 73 & 74

44,45



return 74

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 73 44

<sup>GRAV</sup>  
INITIAL SYSTEM: APPROVED 25% REDUCTION

<sup>GRAV</sup>  
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION T.O.S FC 73/05

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
I {	1	B	98.67
	2	Y	98.42
	3	R	98.25
	4a	W	98.09
			<u>300</u>
R {	4b	W	98.09
	5	B	98.09
	6	R	97.67
	7	Y	97.33
			<u>65</u>
			<u>300</u>

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

0-25 LS vfri gran  
25-36 SCL firm SBK  
m<sub>z</sub> ≥ 29"

HEALTH DEPARTMENT USE ONLY.  
DESIGNS DO NOT GURANTEE FUNCTIONALITY