

Liberty Meadow
Lot 73 & 74

44,45



return 74

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 73 44

^{GRAV}
INITIAL SYSTEM: APPROVED 25% REDUCTION

^{GRAV}
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION To S FC 73/05

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I {	1	B	98.67
	2	Y	98.42
	3	R	98.25
	4a	W	98.09
			300
R {	4b	W	98.09
	5	B	98.09
	6	R	97.67
	7	Y	97.33

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE
0-25 LS vfri gran
25-36 SCL firm SBK
m_z ≥ 28"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.
DESIGNS DO NOT GURANTEE FUNCTIONALITY