

Liberty Meadow
Lot 73 & 74

44,45



revert 74

* Check Soils

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 74

45

INITIAL SYSTEM: ^{Pump} APPROVED 25% REDUCTION

REPAIR ^{Pump} Approved 25% Reduction

DISTRIBUTION: ~~SERIAL~~ Pressure Man

DISTRIBUTION ~~SERIAL~~ SEN inc

BENCHMARK: 100.0

LOCATION T-5 FC 73/05

NO. BEDROOMS: 3

LTAR 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	0	98.67	45
2	G	98.42	60
3	0	98.00	75
			190
4	G	97.93	95
5	0	97.41	105
			200 AVAIL

BY B.C. Raynor

DATE 12/16/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-16 LS vfri gran

CUTTING, LOGGING OR OTHER SOIL

16-36 SCL firm SBK

DISTURBANCE IN SEPTIC AREA

CR2 ≥ 24"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY