

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 2 (New)

Pump  
INITIAL SYSTEM: APPROVED 25% REDUCTION

Pump to  
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION Bc IRON 3/4

NO. BEDROOMS: 3

LTAR 0.45 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH	
I {	1	W	102.42	70
	2	Y	102.25	70
	3	R	101.92	60
			<u>200</u>	
R {	4	B/O	101.75	65
	5	O	101.17	95
	6	W	100.92	95
			<u>255 AVAIL</u>	

BY B.C. Raynor

DATE 12/04/2021

TYPICAL PROFILE

0-33. LS vfri gran (Rock mix)  
33-42 LSCL firm SBK (ns/np)  
CR2 ≥ 36"

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
 Fayetteville, NC 28311  
 Phone/Fax (910) 822-4540  
 Email mike@southeasternsoil.com

ANN L. DIGIORGIO  
 DB 1633, PG 520  
 PB 2002, PG 567

