

Liberty Meadow  
Lot 7 & 8

6 & 7



SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 7

INITIAL SYSTEM: <sup>GRAV</sup> APPROVED 25% REDUCTION

REPAIR <sup>Pump</sup> Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION BC IRON 7/9

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
R {	1	B	102.92
	2	Y	102.93
	3a	B	102.41
			300
I {	3b	B	102.41
	4	Y	102.25
	5	B	101.93
			300

BY B.C. Raynor

DATE 12/04/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-20 LS vfri gran  
20-36 SCL firm SBK  
CR2 ≥ 29"

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY