Harnett County Department of Public Health

Improvement Permit

ISSUED TO: Wellco Contractors

Type of Structure: 44'x61' sfd

Projected Daily Flow: 360 Number of bedrooms: 3

Basement Yes

Permit conditions:

Pump Required: XYes

with the attached system layout.

Basement? Yes

Septic Tank Size 1000

Pump Tank Size 1000

Facility Type: 44'x61' sfd

Type of Wastewater System**

(See note below, if applicable)

Installation Requirements/Conditions

Pump Requirements: ft. TDH vs. _

REPAIR

X No

☐ No

X No

gallons

gallons

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 44 Black Oak PI (SR 1117) SUBDIVISION Rolling Springs EXPANSION Site Improvements required prior to Construction Authorization Issuance: Proposed Wastewater System Type: Pump to 25% reduction Number of Occupants: 6 May be required based on final location and elevations of facilities Type of Water Supply: Community Public Well Distance from well feet X Five years Permit valid for: No expiration Date: 09-13-22 SEE ATTACHED SITE SKETCH The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation of the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance ISSUED TO: Wellco Contractors PROPERTY LOCATION: 44 Black Oak PI (SR 1117) SUBDIVISION Rolling Springs LOT # 112 Expansion ➤ New Basement Fixtures? Yes Pump to 25% reduction (Initial) Wastewater Flow: 360 Pump to 25% reduction Number of trenches 1 Exact length of each trench 225 Trench Spacing: 9 Feet on Center Trenches shall be installed on contour at a Soil Cover: 6 inches

inches

(Maximum soil cover shall not exceed

inches below pipe

inches total

inches above pipe

36" above the trench bottom)

Aggregate Depth:

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

in all directions)

Maximum Trench Depth of: 22

(Trench bottoms shall be level to +/-1/4"

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specified	cations of this permit.
Owner/Legal Representative Signature: Date:	
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This	
Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.	SEE ATTACHED SITE SKETCH
1/1/	

Authorized State Agent: Noh MEHT Date: 09-13-22 Construction Authorization Expiration Date: 09-13-27

Harnett County Department of Public Health Site Sketch

Property Location: 44 Black Oak PI (SR 1117)

Issued To: Wellco Contractors Subdivision Rolling Springs Lot # 112

Authorized State Agent:

Jah U SE/TS Date: 09-13-22

