

# North Carolina 2018 - R402.1.5 Total UA



**Property**

48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing

**Organization**

Southern Energy Manager  
Justin Smith

**Inspection Status**

Results are projected

**Builder**

DreamFinders Homes

DreamFinders Homes - Prelude  
plan slab CZ 4 - ecoSelect  
Prelude plan slab

**This report is based on a proposed design and does not confirm field enforcement of design elements.**

## Building UA

Elements	NC Reference	As Designed
Ceilings	43.4	41.2
Above-Grade Walls	178.9	138.2
Windows, Doors and Skylights	130.3	124.6
Slab Floor:	74.5	96.5
Framed Floors	19.1	20.8
Foundation Walls	0.0	0.0
Rim Joists	8.8	7.1
<b>Overall UA (Design must be equal or lower):</b>	<b>455.0</b>	<b>428.4</b>

## Requirements

✔	R402.1.5	Total UA alternative compliance passes by 5.8%. The proposed home meets the UA requirement by 5.8%
✔	402.3.2	Average SHGC: 0.30 Max SHGC: 0.30 Average SHGC of 0.30 is greater than the maximum of 0.30.
✔	R402.4.2.2	Air Leakage Testing Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✔	R402.5	Area-weighted average fenestration SHGC Area-weighted average fenestration SHGC is 0.3. The maximum allowed value is [No Limit].
✔	R402.5	Area-weighted average fenestration U-Factor
✔	R404.1	Lighting Equipment At least 75.0% of fixtures shall be high-efficacy lamps, currently 100.0% are high-efficacy.
✔	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met. 2015 IECC Mandatory Checklist must be checked as complete.
✔	R403.3.1	Duct Insulation Duct insulation meets the requirements specified in North Carolina 2018 Code Section 403.3.1.
✔	403.3.3	Duct Testing

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 5.8%.**

Name: Justin Smith Signature: Justin Smith  
 Organization: Southern Energy Management Digitally signed: 11/21/22 at 9:48 AM

Ekotrope RATER - Version 4.0.2.3035

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

**Builder**  
DreamFinders Homes

DreamFinders Homes - Prelude plan slab CZ 4 -  
ecoSelect  
Prelude plan slab

## General Building Information

Number Of Bedrooms	4
Number Of Floors	2
Conditioned Floor Area [sq. ft.]	2,435
Has Electric Vehicle Ready Space	No
Unconditioned, attached garage?	Yes
Conditioned Volume [cu. ft.]	21,560
Total Units in Building	1
Residence Type	Single family detached
Number of Floors in Building	-
Floor Number	-
Model	Prelude
Community	Schabert Crossing
RESNET/IECC 2006-2018 Climate Zone	4A
IECC 2021 Climate Zone	3A

## Foundation Wall

None Present

## Foundation Wall Library List

None Present

## Slab

Name	Library Type	Perimeter	Floor Grade	Carpet R	Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	158	On Grade	1	0	1,040.0 ft²	Exposed Exterior	Conditioned Space

## Slab Library List

Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [ft]	Perimeter Insulation Depth [ft]	Perimeter Insulation R Value	Thermal Break	Effective R-value
Uninsulated	Wood Frame / Other	No	0	0	0	No	0.00

# Building Summary



**Property**  
 48 Betty Ann Street  
 Dunn, NC 28334  
 Model: Prelude  
 Community: Schabert Crossing

**Organization**  
 Southern Energy Management  
 Justin Smith

**Inspection Status**  
 Results are projected

**Builder**  
 DreamFinders Homes

DreamFinders Homes - Prelude plan slab CZ 4 -  
 ecoSelect  
 Prelude plan slab

## Framed Floor

Name	Library Type	Carpet R	Floor Grade	Surface Area	Location
over ambient	R 19, 16"OC G1 Hardwood	0	Above Grade	12.0 ft <sup>2</sup>	Exposed Exterior
over garage	R 19, 16"OC G1 Carpet	0	Above Grade	394.0 ft <sup>2</sup>	Unconditioned, attached garage

## Framed Floor Library List

Name	Effective R-value
R 19, 16"OC G1 Carpet	19.566
R 19, 16"OC G1 Hardwood	18.371

## Rim Joist

Name	Library Type	Surface Area	Location
1st floor ambient	R 19 G1, 16"OC	122.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 19 G1, 16"OC	36.0 ft <sup>2</sup>	Unconditioned, attached garage

## Rim Joist Library List

Name	Effective Insulation R-value
R 19 G1, 16"OC	17.30

## Wall

Name	Library Type	Surface Color	Surface Area	Location
1st floor ambient	R 19 FG G1 16" O.C	Medium	1,099.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 19 FG G1 16" O.C	Medium	324.0 ft <sup>2</sup>	Unconditioned, attached garage
2nd floor ambient	R 19 FG G1 16" O.C	Medium	1,272.0 ft <sup>2</sup>	Exposed Exterior

# Building Summary



**Property**  
 48 Betty Ann Street  
 Dunn, NC 28334  
 Model: Prelude  
 Community: Schabert Crossing

**Organization**  
 Southern Energy Management  
 Justin Smith

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

DreamFinders Homes - Prelude plan slab CZ 4 -  
 ecoSelect  
 Prelude plan slab

**Builder**  
 DreamFinders Homes

## Wall Library List

Name	Effective R-value
R 19 FG G1 16" O.C	16.805

## Glazing

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Is Operable	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front 2nd unshaded	35/30	2nd floor ambient		Yes	0	0	0	West	60.0 ft <sup>2</sup>
front unshaded	35/30	1st floor ambient		Yes	0	0	0	West	30.0 ft <sup>2</sup>
left 2nd unshaded	35/30	2nd floor ambient		Yes	0	0	0	North	45.0 ft <sup>2</sup>
left unshaded	35/30	1st floor ambient		Yes	0	0	0	North	15.0 ft <sup>2</sup>
rear 2nd unshaded	35/30	2nd floor ambient		Yes	0	0	0	East	38.0 ft <sup>2</sup>
rear unshaded	35/30	1st floor ambient		Yes	0	0	0	East	100.2 ft <sup>2</sup>
right 2nd unshaded	35/30	2nd floor ambient		Yes	0	0	0	South	46.0 ft <sup>2</sup>

## Glazing Library List

Name	Shgc	U-factor
35/30	0.3	0.350

## Skylight

None Present

## Skylight Library List

None Present

# Building Summary



**Property**  
 48 Betty Ann Street  
 Dunn, NC 28334  
 Model: Prelude  
 Community: Schabert Crossing

**Organization**  
 Southern Energy Management  
 Justin Smith

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

DreamFinders Homes - Prelude plan slab CZ 4 -  
 ecoSelect  
 Prelude plan slab

**Builder**  
 DreamFinders Homes

## Opaque Door

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Emittance	Solar Absorptance	Surface Color	Surface Area	Location
front door	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft²	Exposed Exterior
garage door	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft²	Unconditioned, attached garage

## Opaque Door Library List

Name	Effective U-factor
Fiberglass R-5	0.200

## Roof Insulation

Name	Library Type	Attic Exterior Area [ft²]	Clay or Concrete Roof Tiles	Surface Color	Surface Area	Location
Attic	R 38 Attic BLOWN FG G1 2x10 24"OC NO Radiant Barrier	2,125.62	No	Dark	1,446.0 ft²	Attic

## Roof Insulation Library List

Name	Has Radiant Barrier	Effective R-value
R 38 Attic BLOWN FG G1 2x10 24"OC NO Radiant Barrier	No	35.115

## Whole House Infiltration

Infiltration	Measurement Type	Shelter Class
1724 CFM at 50 Pa	Blower-door tested	4

## Mechanical Ventilation

None Present

# Building Summary



**Property**  
48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing


**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

**Builder**  
DreamFinders Homes

DreamFinders Homes - Prelude plan slab CZ 4 -  
ecoSelect  
Prelude plan slab

## Lighting



## Onsite Generation

None Present

## Onsite Generation Library List

None Present

## Solar Generation

None Present

## Dehumidifier

None Present

## Dehumidifier Library List

None Present

## Whole House Fan

None Present

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

**Builder**  
DreamFinders Homes

DreamFinders Homes - Prelude plan slab CZ 4 -  
ecoSelect  
Prelude plan slab

## Whole House Fan Library List

None Present

## Conditioning Equipment

Name	Library Type	Serial Number	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load	Location
Water Heating	z 50 gal. 0.91 EF Elec		0%	0%	100%	Unspecified
whole house heat pump	z 36k 14 SEER 8.0hspf		100%	100%	0%	Unspecified

### Equipment Type: z 36k 14 SEER 8.0hspf

Equipment Type	Air Source Heat Pump
Fuel Type	Electric
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heating Efficiency	8 HSPF
Heating Capacity [kBtu/h]	36
Backup Fuel Type	Electric
Switchover Temperature [°F]	0
Backup Heating Efficiency	1 COP
Use default Supplemental Heat	Yes
Cooling Efficiency	14 SEER
Cooling Capacity [kBtu/h]	36

### Equipment Type: z 50 gal. 0.91 EF Elec

Equipment Type	Residential Water Heater
Fuel Type	Electric
Distribution Type	Hydronic Delivery (Radiant)
Hot Water Efficiency	0.91 Energy Factor
Tank Capacity (gal.)	50
Hot Water Capacity [kBtu/h]	40
Recovery Efficiency	0.98

# Building Summary



**Property**  
 48 Betty Ann Street  
 Dunn, NC 28334  
 Model: Prelude  
 Community: Schabert Crossing

**Organization**  
 Southern Energy Management  
 Justin Smith

**Inspection Status**  
 Results are projected

DreamFinders Homes - Prelude plan slab CZ 4 -  
 ecoSelect  
 Prelude plan slab

**Builder**  
 DreamFinders Homes

## Distribution System

Distribution Type	Forced Air
Heating Equipment	whole house heat pump
Cooling Equipment	whole house heat pump
Sq. Feet Served	2,435
# Return Grilles	4
Supply Duct R Value	8
Return Duct R Value	8
Supply Duct Area [ft <sup>2</sup> ]	657.45
Return Duct Area [ft <sup>2</sup> ]	487
Leakage to Outdoors	97 CFM @ 25Pa (3.98 / 100 ft <sup>2</sup> )
Total Leakage	97 CFM25
Total Leakage Duct Test Conditions	Post-Construction
Use Default Flow Rate	Yes
Duct 1	
Duct Location	Attic (well vented, radiant barrier)
Percent Supply Area	70
Percent Return Area	70
Duct 2	
Duct Location	Conditioned Space
Percent Supply Area	30
Percent Return Area	30
Duct 3	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 4	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 5	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 6	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0

## HVAC Grading

HVAC Grading Not Conducted

## Ceiling Fan

Has Ceiling Fan	No
Cfm Per Watt	100



# Building Summary



**Property**  
48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

DreamFinders Homes - Prelude plan slab CZ 4 -  
ecoSelect  
Prelude plan slab

**Builder**  
DreamFinders Homes

## Water Distribution

Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	65
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Recirculation System Pipe Loop Length [ft]	10
Drain Water Heat Recovery?	No

## Clothes Dryer

Cef	3.01
Fuel Type	Electric
Field Utilization	Timer Controls
Is Outside Conditioned Space	No
Clothes Dryer Available	Yes
Defaults Type	HERS Reference

## Clothes Washer

Label Energy Rating	153 kWh/Year
Annual Gas Cost	\$12.00
Electric Rate	\$0.11/kWh
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.1547
Defaults Type	Custom
Load Type	Front-load
Loads Per Week	6
Is Outside Conditioned Space	No
Clothes Washer Available	Yes

## Dishwasher

Dishwasher Efficiency	270 kWh
Dishwasher Size	Standard
Annual Gas Cost	\$22.23
Electric Rate	\$0.12/kWh
Gas Rate	\$1.09/Therm
Is Outside Conditioned Space	No

# Building Summary



**Property**  
48 Betty Ann Street  
Dunn, NC 28334  
Model: Prelude  
Community: Schabert Crossing

**Organization**  
Southern Energy Management  
Justin Smith

**Inspection Status**  
Results are projected

DreamFinders Homes - Prelude plan slab CZ 4 -  
ecoSelect  
Prelude plan slab

**Builder**  
DreamFinders Homes

## Appliances and Controls

Thermostat Cooling Setpoint	*** 75.0
Thermostat Heating Setpoint	*** 70.0
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Range/Oven Outside Conditioned Space?	No
Refrigerator Consumption	538 kWh/Year
Refrigerator Outside Conditioned Space?	No

## Notes

- updated JS 11/21/12
- uninsulated slab modeled
- confirm attic insulation and hvac specs
- ventilation modeled as none
- confirm cfl lighting %
- modeled to worst case orientation