

# North Carolina 2018 - R402.1.5 Total UA



**Property**  
 , NC 27546  
 Model: Prelude

**Organization**  
 Southern Energy Manager  
 Sara Caliendo

**Inspection Status**  
 Results are projected

Prelude plan slab  
 Template - H & H Homes - Fayettevil

**Builder**  
 H&H Homes

## Building UA

Elements	NC Reference	As Designed
Ceilings	43.4	38.8
Above-Grade Walls	178.9	156.1
Windows, Doors and Skylights	130.3	124.6
Slab Floor:	74.5	96.5
Framed Floors	19.1	22.3
Foundation Walls	0.0	0.0
Rim Joists	8.8	6.6
<b>Overall UA (Design must be equal or lower):</b>	<b>455.0</b>	<b>444.9</b>

## Requirements

✓	402.1.5	Total UA alternative for insulation and fenestration
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.27; Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3	Duct Insulation
✓	403.3.3	Duct Testing

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 2.2%.**

Name: Sara Caliendo

Signature: *Sara Caliendo*

Organization: Southern Energy Management

Digitally signed: 10/1/19 at 3:08 PM

### Ekotrope RATER - Version 3.1.0.2265

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

# Fuel Summary



**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

Prelude plan slab  
Template - H & H Homes - Fayetteville - I

**Builder**  
H&H Homes

## Annual Energy Cost

Electric	\$1,975
----------	---------

## Annual End-Use Cost

Heating	\$605
Cooling	\$219
Water Heating	\$289
Lights & Appliances	\$693
Onsite Generation	-\$0
Service Charges	\$168
Total	\$1,975

## Annual End-Use Consumption

Heating [Electric kWh]	5,817.3
Cooling [Electric kWh]	2,050.6
Hot Water [Electric kWh]	2,751.3
Lights & Appliances [Electric kWh]	6,575.0
Total [Electric kWh]	17,194.3
Total Onsite Generation kWh	0.0

## Peak Electric Consumption

Peak Winter kW	4.28
Peak Summer kW	2.56

## Utility Rates

Electricity	Duke-Progress 2019
Natural Gas	PSNC - Dominion 2019

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Prelude plan slab  
Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
H&H Homes

## General Building Information

Number Of Bedrooms	4
Number Of Floors	2
Conditioned Floor Area [sq. ft.]	2,435
Unconditioned, attached garage?	No
Conditioned Volume [cu. ft.]	21,560
Total Units in Building	1
Residence Type	Single family detached
Floor Number	-
Model	Prelude
Community	
Climate Zone	4A

## Foundation Wall

None Present

## Foundation Wall Library List

None Present

## Slab

Name	Library Type	Perimeter	Floor Grade	Carpet R	Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	158	On Grade	1	0	1,040.0 ft²	Exposed Exterior	Conditioned Space

## Slab Library List

Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [ft]	Perimeter Insulation Depth [ft]	Perimeter Insulation R Value	Thermal Break	Effective R-value
Uninsulated	Wood Frame / Other	No	0	0	0	No	0.00

# Building Summary



**Property**  
 , NC 27546  
 Model: Prelude

**Organization**  
 Southern Energy Management  
 Sara Callendo

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

Prelude plan slab  
 Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
 H&H Homes

## Framed Floor

Name	Library Type	Carpet R	Floor Grade	Surface Area	Location
over ambient	R-19, 16"OC G3 Hardwood	0	Above Grade	12.0 ft <sup>2</sup>	Exposed Exterior
over garage	R-19, 16"OC G3 Carpet	0	Above Grade	394.0 ft <sup>2</sup>	Unconditioned, attached garage

## Framed Floor Library List

Name	Effective R-value
R-19, 16"OC G3 Carpet	18.202
R-19, 16"OC G3 Hardwood	17.37

## Rim Joist

Name	Library Type	Surface Area	Location
1st floor ambient	R 19.0	122.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 19.0	36.0 ft <sup>2</sup>	Unconditioned, attached garage

## Rim Joist Library List

Name	Effective Insulation R-value
R 19.0	19.00

## Wall

Name	Library Type	Surface Color	Surface Area	Location
1st floor ambient	R 19 FG G3 16" O.C	Medium	1,099.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 19 FG G3 16" O.C	Medium	324.0 ft <sup>2</sup>	Unconditioned, attached garage
2nd floor ambient	R 19 FG G3 16" O.C	Medium	1,272.0 ft <sup>2</sup>	Exposed Exterior

# Building Summary



**Property**  
 , NC 27546  
 Model: Prelude

**Organization**  
 Southern Energy Management  
 Sara Caliendo

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY  
 MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

Prelude plan slab  
 Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
 H&H Homes

## Wall Library List

Name	Effective R-value
R 19 FG G3 16" O.C	14.878

## Glazing

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front 2nd unshaded	35/27	2nd floor ambient		0	0	0	West	60.0 ft²
front unshaded	35/27	1st floor ambient		0	0	0	West	30.0 ft²
left 2nd unshaded	35/27	2nd floor ambient		0	0	0	North	45.0 ft²
left unshaded	35/27	1st floor ambient		0	0	0	North	15.0 ft²
rear 2nd unshaded	35/27	2nd floor ambient		0	0	0	East	38.0 ft²
rear unshaded	35/27	1st floor ambient		0	0	0	East	100.2 ft²
right 2nd unshaded	35/27	2nd floor ambient		0	0	0	South	46.0 ft²

## Glazing Library List

Name	Shgc	U-factor
35/27	0.27	0.350

## Skylight

None Present

## Skylight Library List

None Present

# Building Summary



**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Prelude plan slab  
Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
H&H Homes

## Opaque Door

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Emittance	Solar Absorptance	Surface Color	Surface Area	Location
front door	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft <sup>2</sup>	Exposed Exterior
garage door	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft <sup>2</sup>	Exposed Exterior

## Opaque Door Library List

Name	Effective U-factor
Fiberglass R-5	0.200

## Roof Insulation

Name	Library Type	Attic Exterior Area [s.f.]	Clay or Concrete	Roof Tiles	Surface Color	Surface Area	Location
Attic	R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	1,446		No	Dark	1,446.0 ft <sup>2</sup>	Attic

## Roof Insulation Library List

Name	Has Radiant Barrier	Effective R-value
R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	Yes	37.246

## Whole House Infiltration

Infiltration	Measurement Type	Shelter Class
1724 CFM at 50 Pa	Blower-door tested	4

## Mechanical Ventilation

None Present

# Building Summary



**Property**  
 , NC 27546  
 Model: Prelude

**Organization**  
 Southern Energy Management  
 Sara Caliendo

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY**  
**MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

Prelude plan slab  
 Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
 H&H Homes

## Lighting

% Interior Fluorescent Lighting	% Interior LED Lighting	% Exterior Fluorescent Lighting	% Exterior LED Lighting	% Garage Fluorescent Lighting	% Garage LED Lighting
75	0	0	0	0	0

## Onsite Generation

None Present

## Onsite Generation Library List

None Present

## Solar Generation

None Present

## Solar Generation Library List

None Present

## Conditioning Equipment

Name	Library Type	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load	Location
Water Heating	Z 50 gal. 0.91EF elec	0%	0%	100%	Unspecified
whole house heat pump	z 36k 14 seer 8.0hspf	100%	100%	0%	Unspecified

# Building Summary



**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Prelude plan slab  
Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
H&H Homes

## Equipment Type: Z 50 gal. 0.91EF elec

Fuel Type	Electric
Distribution Type	Hydronic Delivery
Hot Water Efficiency	0.91 Energy Factor
Tank Capacity (gal.)	50
Hot Water Capacity [kBtu/h]	40
Recovery Efficiency	0.98

## Equipment Type: z 36k 14 seer 8.0hspf

Fuel Type	Electric
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heating Efficiency	8 HSPF
Heating Capacity [kBtu/h]	36
Cooling Efficiency	14 SEER
Cooling Capacity [kBtu/h]	36



# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Prelude plan slab  
Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
H&H Homes

## Distribution System

Distribution Type	Forced Air
Heating Equipment	whole house heat pump
Cooling Equipment	whole house heat pump
Sq. Feet Served	2435
# Return Grilles	4
Supply Duct R Value	8
Return Duct R Value	8
Supply Duct Area [ft <sup>2</sup> ]	657.45
Return Duct Area [ft <sup>2</sup> ]	487
Leakage to Outdoors	97 CFM25 (3.98 / 100 s.f.)
Total Leakage	97 CFM25
Total Leakage Duct Test Conditions	Post-Construction
Use Default Flow Rate	Yes
Duct 1	
Duct Location	Attic (well vented, radiant barrier)
Percent Supply Area	70
Percent Return Area	70
Duct 2	
Duct Location	Conditioned Space
Percent Supply Area	30
Percent Return Area	30
Duct 3	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 4	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 5	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 6	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0

## Ceiling Fan

Has Ceiling Fan	Yes
Cfm Per Watt	100

## Water Distribution

Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	65
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Recirculation System Pipe Loop Length [ft]	10
Drain Water Heat Recovery?	No

# Building Summary



**Property**  
NC 27546  
Model: Prelude

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Prelude plan slab  
Template - H & H Homes - Fayetteville - Prelude plan

**Builder**  
H&H Homes

## Clothes Dryer

Fuel Type	Electric
Cef	2.617
Field Utilization	Timer Controls

## Clothes Washer

Label Energy Rating	151 kWh/Year
Electric Rate	\$0.11/kWh
Annual Gas Cost	\$12.00
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.155

## Appliances and Controls

Programmable thermostat?	Yes
Dishwasher Size	Standard
Dishwasher Efficiency	0.65 EF
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Refrigerator Consumption	700 kWh/Year

## Notes

- updated JS 01/29/18
- insulated slab modeled
- wall insulation modeled to Grade 3
- confirm attic insulation and hvac specs
- ventilation modeled as none
- confirm cfl lighting %
- modeled to worst case orientation