

# North Carolina 2018 - R402.1.5 Total UA



**Property**  
 , NC 28390  
 Model: Wayfare

**Organization**  
 Southern Energy Manager  
 Sara Caliendo

**Inspection Status**  
 Results are projected

Wayfare plan slab  
 Template - H & H - Fayetteville - Way

**Builder**  
 H&H Homes

## Building UA

Elements	NC Reference	As Designed
Ceilings	41.5	37.2
Above-Grade Walls	179.5	151.0
Windows, Doors and Skylights	91.4	85.7
Slab Floor:	71.3	92.1
Framed Floors	20.0	23.4
Foundation Walls	0.0	0.0
Rim Joists	8.4	8.3
<b>Overall UA (Design must be equal or lower):</b>	<b>412.1</b>	<b>397.7</b>

## Requirements

✓	402.1.5	Total UA alternative for insulation and fenestration
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.27; Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3	Duct Insulation
✓	403.3.3	Duct Testing

**Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 3.5%.**

Name: Sara Caliendo

Signature: *Sara Caliendo*

Organization: Southern Energy Management

Digitally signed: 10/1/19 at 3:22 PM

### Ekotrope RATER - Version 3.1.0.2265

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

# Fuel Summary



SOUTHERN ENERGY  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
, NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare

**Builder**  
H&H Homes

## Annual Energy Cost

Electric	\$1,892
----------	---------

## Annual End-Use Cost

Heating	\$523
Cooling	\$181
Water Heating	\$247
Lights & Appliances	\$641
Onsite Generation	-\$0
Service Charges	\$300
Total	\$1,892

## Annual End-Use Consumption

Heating [Electric kWh]	5,302.9
Cooling [Electric kWh]	1,668.5
Hot Water [Electric kWh]	2,410.5
Lights & Appliances [Electric kWh]	6,197.4
Total [Electric kWh]	15,579.3
Total Onsite Generation kWh	0.0

## Peak Electric Consumption

Peak Winter kW	3.83
Peak Summer kW	2.28

## Utility Rates

Electricity	SouthRiverEMC 5/14
Natural Gas	PSNC - Dominion 2019

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## General Building Information

Number Of Bedrooms	3
Number Of Floors	2
Conditioned Floor Area [sq. ft.]	2,277
Unconditioned, attached garage?	Yes
Conditioned Volume [cu. ft.]	20,134
Total Units in Building	1
Residence Type	Single family detached
Floor Number	-
Model	Wayfare
Community	
Climate Zone	4A

## Foundation Wall

None Present

## Foundation Wall Library List

None Present

## Slab

Name	Library Type	Perimeter	Floor Grade	Carpet R	Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	152	On Grade	1	0	959.0 ft²	Exposed Exterior	Conditioned Space

## Slab Library List

Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [ft]	Perimeter Insulation Depth [ft]	Perimeter Insulation R Value	Thermal Break	Effective R-value
Uninsulated	Wood Frame / Other	No	0	0	0	No	0.00

# Building Summary



**Property**  
 , NC 28390  
 Model: Wayfare

**Organization**  
 Southern Energy Management  
 Sara Callendo

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY  
 MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

Wayfare plan slab  
 Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
 H&H Homes

## Framed Floor

Name	Library Type	Carpet R	Floor Grade	Surface Area	Location
over ambient	R-19, 16"OC G3 Hardwood	0	Above Grade	12.0 ft <sup>2</sup>	Exposed Exterior
over garage	R-19, 16"OC G3 Carpet	0	Above Grade	413.0 ft <sup>2</sup>	Unconditioned, attached garage

## Framed Floor Library List

Name	Effective R-value
R-19, 16"OC G3 Carpet	18.202
R-19, 16"OC G3 Hardwood	17.37

## Rim Joist

Name	Library Type	Surface Area	Location
1st floor ambient	R-19 G3, 16"OC	111.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R-19 G3, 16"OC	41.0 ft <sup>2</sup>	Unconditioned, attached garage

## Rim Joist Library List

Name	Effective Insulation R-value
R-19 G3, 16"OC	13.20

## Wall

Name	Library Type	Surface Color	Surface Area	Location
1st floor ambient	R 19 Adv. Framing G3 16" O.C	Medium	1,001.0 ft <sup>2</sup>	Exposed Exterior
1st floor garage	R 19 Adv. Framing G3 16" O.C	Medium	367.0 ft <sup>2</sup>	Unconditioned, attached garage
2nd floor ambient	R 19 Adv. Framing G3 16" O.C	Medium	1,224.0 ft <sup>2</sup>	Exposed Exterior

# Building Summary



**Property**  
 , NC 28390  
 Model: Wayfare

**Organization**  
 Southern Energy Management  
 Sara Caliendo

**Inspection Status**  
 Results are projected

**SOUTHERN ENERGY  
 MANAGEMENT**  
 ENERGY EFFICIENCY & SOLAR POWER

Wayfare plan slab  
 Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
 H&H Homes

## Wall Library List

Name	Effective R-value
R 19 Adv. Framing G3 16" O.C	15.433

## Glazing

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front 2nd unshaded	35/27	2nd floor ambient		0	0	0	West	47.0 ft <sup>2</sup>
front shaded	35/27	1st floor ambient		6	1	5	West	8.0 ft <sup>2</sup>
left 2nd unshaded	35/27	2nd floor ambient		0	0	0	North	30.0 ft <sup>2</sup>
rear 2nd unshaded	35/27	2nd floor ambient		0	0	0	East	23.0 ft <sup>2</sup>
rear unshaded	35/27	1st floor ambient		0	0	0	East	55.2 ft <sup>2</sup>
right 2nd unshaded	35/27	2nd floor ambient		0	0	0	South	30.0 ft <sup>2</sup>
right unshaded	35/27	1st floor ambient		0	0	0	South	30.0 ft <sup>2</sup>

## Glazing Library List

Name	Shgc	U-factor
35/27	0.27	0.350

## Skylight

None Present

## Skylight Library List

None Present

# Building Summary



**SOUTHERN ENERGY  
MANAGEMENT**  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## Opaque Door

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Emittance	Solar Absorptance	Surface Color	Surface Area	Location
front door	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft²	Exposed Exterior
garage door	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft²	Exposed Exterior

## Opaque Door Library List

Name	Effective U-factor
Fiberglass R-5	0.200

## Roof Insulation

Name	Library Type	Attic Exterior Area [s.f.]	Clay or Concrete	Roof Tiles	Surface Color	Surface Area	Location
Attic	R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	2,034.48		No	Dark	1,384.0 ft²	Attic

## Roof Insulation Library List

Name	Has Radiant Barrier	Effective R-value
R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	Yes	37.246

## Whole House Infiltration

Infiltration	Measurement Type	Shelter Class
1610 CFM at 50 Pa	Blower-door tested	4

## Mechanical Ventilation

None Present

# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## Lighting

% Interior Fluorescent Lighting	% Interior LED Lighting	% Exterior Fluorescent Lighting	% Exterior LED Lighting	% Garage Fluorescent Lighting	% Garage LED Lighting
75	0	0	0	0	0

## Onsite Generation

None Present

## Onsite Generation Library List

None Present

## Solar Generation

None Present

## Solar Generation Library List

None Present

## Conditioning Equipment

Name	Library Type	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load	Location
Water Heating	Z 50 gal. 0.91EF elec	0%	0%	100%	Unspecified
whole house heat pump	z 36k 14 seer 8.0hspf	100%	100%	0%	Unspecified

# Building Summary



**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## Equipment Type: Z 50 gal. 0.91EF elec

Fuel Type	Electric
Distribution Type	Hydronic Delivery
Hot Water Efficiency	0.91 Energy Factor
Tank Capacity (gal.)	50
Hot Water Capacity [kBtu/h]	40
Recovery Efficiency	0.98

## Equipment Type: z 36k 14 seer 8.0hspf

Fuel Type	Electric
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heating Efficiency	8 HSPF
Heating Capacity [kBtu/h]	36
Cooling Efficiency	14 SEER
Cooling Capacity [kBtu/h]	36



# Building Summary



**SOUTHERN ENERGY**  
MANAGEMENT  
ENERGY EFFICIENCY & SOLAR POWER

**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## Distribution System

Distribution Type	Forced Air
Heating Equipment	whole house heat pump
Cooling Equipment	whole house heat pump
Sq. Feet Served	2277
# Return Grilles	4
Supply Duct R Value	8
Return Duct R Value	8
Supply Duct Area [ft <sup>2</sup> ]	614.79
Return Duct Area [ft <sup>2</sup> ]	455.4
Leakage to Outdoors	91 CFM25 (4 / 100 s.f.)
Total Leakage	91 CFM25
Total Leakage Duct Test Conditions	Post-Construction
Use Default Flow Rate	Yes
Duct 1	
Duct Location	Attic (well vented, radiant barrier)
Percent Supply Area	70
Percent Return Area	70
Duct 2	
Duct Location	Conditioned Space
Percent Supply Area	30
Percent Return Area	30
Duct 3	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 4	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 5	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 6	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0

## Ceiling Fan

Has Ceiling Fan	Yes
Cfm Per Watt	100

## Water Distribution

Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	72
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Recirculation System Pipe Loop Length [ft]	10
Drain Water Heat Recovery?	No

# Building Summary



**Property**  
NC 28390  
Model: Wayfare

**Organization**  
Southern Energy Management  
Sara Caliendo

**Inspection Status**  
Results are projected

Wayfare plan slab  
Template - H & H - Fayetteville - Wayfare plan slab C

**Builder**  
H&H Homes

## Clothes Dryer

Fuel Type	Electric
Cef	2.617
Field Utilization	Timer Controls

## Clothes Washer

Label Energy Rating	151 kWh/Year
Electric Rate	\$0.11/kWh
Annual Gas Cost	\$12.00
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.15474

## Appliances and Controls

Programmable thermostat?	Yes
Dishwasher Size	Standard
Dishwasher Efficiency	0.65 EF
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Refrigerator Consumption	700 kWh/Year

## Notes

- updated JS 11/28/18
- wall insulation modeled to Grade 3
- confirm attic insulation and hvac specs
- ventilation modeled as none
- confirm cfl lighting %
- modeled to worst case orientation