

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows  
GRAV  
 INITIAL SYSTEM: APPROVED 25% REDUCTION

LOT N 10  
GRAV  
 REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION T-5 FC 11/12

NO. BEDROOMS: 5

LTAR <sup>(1)</sup> 0.6 gpd/ft<sup>2</sup> <sup>(2)</sup> 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	G	101.42	60
2	O	101.09	160
3a	G	100.67	30
			250
R { 3b	G	100.67	115
4	O	100.00	145
5	G	99.50	75
6	O	99.00	40
			375

BY B.C. Raynor

DATE \_\_\_\_\_

TYPICAL PROFILE M-L

THERE SHALL BE NO GRADING,

0-21 LS v fri gran

CUTTING, LOGGING OR OTHER SOIL

21-34 SCL firm SBK

DISTURBANCE IN SEPTIC AREA

34-48 Sloam fri gran

HEALTH DEPARTMENT USE ONLY.

CR 2 236" (different bore)

DESIGNS DO NOT GURANTEE FUNCTIONALITY

Liberty Meadow  
Lot ~~11~~ 10

