

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows  
 INITIAL SYSTEM: GRAV APPROVED 25% REDUCTION

LOT 92 53  
 REPAIR: GRAV Low Profile Chamber

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION To S FC 92/05

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
I {	1	W	100.25
	2	B	98.92
	3	W	98.50
	4a	B	97.59
			300
R {	4b	B	97.59
	5	W	97.00
	6	B	96.33
	7	W	95.93
			450 AVAIL

BY B.C. Raynor

DATE 12/05/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,  
 CUTTING, LOGGING OR OTHER SOIL  
 DISTURBANCE IN SEPTIC AREA

Repair {  
 0-18 LS vfri gran  
 18-42 scl firm SBK  
 m<sub>2</sub> ≥ 22"

HEALTH DEPARTMENT USE ONLY.  
 DESIGNS DO NOT GURANTEE FUNCTIONALITY

Ⓡ 0-28 LS vfri gran  
 28+ scl firm SBK  
 m<sub>2</sub> ≥ 29"

Liberty Meadow  
Lot ~~82 & 83~~

83 + 84

