

* No Reduction Repair

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 76 49

INITIAL SYSTEM: ^{GRAV} APPROVED 25% REDUCTION

REPAIR ^{GRAV} Low Profile Chamber

DISTRIBUTION: SEPERAL

DISTRIBUTION SEPERAL

BENCHMARK: 100.0

LOCATION T-5 FC 75/76

NO. BEDROOMS: 4

LTAR 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	R	100.00	40
2	B	99.83	60
3	Y	99.67	75
4a	R	99.25	65
			<u>240</u>

R { 4b	R	99.25	20
5	B	99.00	100
6	Y	98.67	105
7	R	98.33	105
			<u>330 AVAIL</u>

BY B.C. Raynon

DATE 12/04/2021

TYPICAL PROFILE m.c

THERE SHALL BE NO GRADING,

(R) 0-18 LS vfri gran
18-36 SCL firm SBK
CR2 ≥ 22"

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

(I) CR2 ≥ 28"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

Liberty Meadow
Lot ~~75 & 76~~

46 + 47

