

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 43

INITIAL SYSTEM: <sup>pump</sup> APPROVED 25% REDUCTION

REPAIR <sup>pump</sup> Approved 25% Reduction

DISTRIBUTION: SERIAL OR D-BOX

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION <sup>(R)</sup> BC IRON 5/4

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup> <sup>(I)</sup> BC IRON 3/4

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	pu	99.92	90 (75)
2	w	99.75	90 (75)
3	pu	99.09	90 (75)
4	w	98.50	90 (75)
R { 5	w	105.09	95
6	pu	104.59	95
7	w	103.92	70
8	pu	102.92	40
			<u>300</u>

BY B.C. Raynor

DATE 12/04/2021

TYPICAL PROFILE

(I) 0-29 LS vfri gran  
29-36 scl firm SBK  
CR2 ≥ 34"

(R) CR2 ≥ 26"

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY

Liberty Meadow

Lot ~~4 & 5~~ 3+4

