

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 16

INITIAL SYSTEM: ^{GRAV} APPROVED 25% REDUCTION

REPAIR ^{GRAV} Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION T&S FC 17/18

NO. BEDROOMS: 5

LTAR (I) 0.6 gpd/ft² (R) 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I {	1	R	97.25
	2	W	96.92
	3a	G	96.75
			250
R {	3b	G	96.75
	4	Y	96.33
	5	R	96.17
	6	W	96.00
			340 AVAIL

BY B.C. Raynor

DATE 12/04/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

(I) 0-36 LS vfri gran
36-42 Lscl firm SBK
ln 2 ≥ 42"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

(R) 0-31 LS vfri gran
31-42 SCL firm SBK
ln 2 ≥ 42"

width - as wide as lot allows
depth = 50'

Liberty Meadows

Lot 17 & 18

16 + 17

