Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 189 Tarleton Dr

	PROPERTY LOCATION: 103 TATLE			
ISSUED TO: KB Home Raleigh	SUBDIVISION Birchwood Gr	ove	LOT # 189	
NEW REPAIR EXPANSION ■	Site Improvements re	quired prior to Construction Authoriz	zation Issuance:	
Type of Structure: SFD(48'x37')				
Proposed Wastewater System Type: 25% Reduction System	n			
	<u> </u>			
Projected Daily Flow: 480 GPD				
Number of bedrooms: 4 Number of Occupants: 8	max			
Basement Yes X No				
Pump Required: Yes No May be required based on final	I location and elevations of facilities			
	tance from wellfeet	Permit valid for:	▼ Five years	
Permit conditions:			☐ No expiration	
Fernit Conditions.				
News Mills	0/22/22	CFC ATT	CUED CITE CHETCH	
Authorized State Agent::	Date: 9/22/22		ACHED SITE SKETCH	
The issuance of this permit by the Health Department in no way guarantees the issuance of	ther permits. The permit holder is responsible for ch	ecking with appropriate governing bodies in	meeting their requirements. This	
site is subject to revocation if the site plan, plat, or the intended use changes. The Improven	ent Permit shall not be affected by a change in owi	ership of the site. This permit is subject to	compliance with the provisions of	
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.				
Cons	truction Authorization			
	NO. 18 LOCATE HER SECTION TO STATE OF THE SECTION O			
	Required for Building Permit)			
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1	57, .1958. and .1959 are incorporated by reference	into this permit and shall be met. Systems	shall be installed in accordance	
with the attached system layout.				
	100			
ISSUED TO: KB Home Raleigh	PROPERTY LOCATION: 189	Tarleton		
	SUBDIVISION Birchwood	Grove	LOT # 189	
Facility Type: SFD (48'x37')			USAGE INV	
· 110	The second secon			
Basement? Yes No Basement Fixtures? Yes	☐ No			
Type of Wastewater System** 25% Reduction Syste	m	(Initial) Wastewater Flow:	480 GPD	
(See note below, if applicable)		, ,		
25% Reduction Syste	m (Panair)			
Installation Requirements/Conditions Number of tree	enches 4			
Septic Tank Size 1000 gallons Exact length	of each trench 95 feet	Trench Spacing: 9	Feet on Center	
	be installed on contour at a		nches	
	nch Depth of: 18inches	(Maximum soil cover shall r		
(Trench botto	ns shall be level to +/-1/4"	36" above the trench bott	om)	
in all directio	(zn			
Pump Requirements:ft. TDH vsGPM	,		inches below pipe	
rump kequirements:nt. 1DH vsGrri				
		Aggregate Depth:		
Conditions: Permit based on proposal from app	licant.		inches total	
WILTER LINES (INCLUDING IRRIGATION) WILST OF JOST FROM	ANN DARK OF SERVIS SUSTEMA OR	DEDAID ADEA		
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM	ANY PART OF SEPTIC SYSTEM OR	REPAIR AREA.		
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD A	RFA.			
**If applicable: I understand the system type specified is different fro	m the type specified on the application	n. I accept the specifications of t	this permit.	
Owner/Legal Beausementative Signatures		Date:		
Owner/Legal Representative Signature:				
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This				
Construction Authorization is subject to compliance with the provisions of the Laws and Rules	for Sewage Treatment and Disposal and to the cond	tions of this permit.	ATTACHED SITE SKETCH	
			E	
Authorized State Agent: Date: 9/22/22				
Construction Authorization Expiration Date: 9/22/27				
			THE RESERVE OF THE PERSON NAMED IN COLUMN 2 IS NOT THE PERSON NAME	

Harnett County Department of Public Health Site Sketch

Property Location: 189 Tarleton I)r	
Issued To: KB Home Raleigh	Subdivision Birchwood Grove	Lot # 189
Authorized State Agent:	REND COLIVER TOLKSDOTTE)	Date: 9/22/22
0		

