

**NON ITEMIZED QUOTE**



**Carolina Structural Systems**

P.O. Box 157, Ether, NC 27247  
 225 Frame Shop Rd., Star, NC 27356  
 910-491-9004  
**844-767-1926**

**QUOTE # Q2201696**

<b>ORDER DATE</b>	//	<b>CUST PO #</b>	
<b>DELIVERY DATE</b>	//	<b>COUNTY</b>	HARNETT
<b>ORDERED BY</b>	TARYN DONAHUE	<b>TERMS</b>	NET 30 DAYS
<b>SUPERINTENDENT</b>	TARYN DONAHUE	<b>SALES REP</b>	SCOTT LAIL
<b>JOBSITE PHONE #</b>		<b>DESIGNER</b>	JEREMY

<b>SOLD TO</b>	<b>VALUE BUILD HOMES</b> 3015 JEFFERSON DAVIS SANFORD, NC 27332	<b>JOB NAME:</b> WHEELER: 23-53-09	<b>LOT #</b>	<b>SUBDIV:</b>
	<b>SHIP TO</b>	1175 ROUNDABOUT RD. CAMERON, NC 28326	<b>MODEL:</b> PAMLICO- C	<b>OPTIONS:</b>
<b>DELIVERY INSTRUCTIONS:</b>				
		<b>SPECIAL INSTRUCTIONS:</b> Paul McNeil 910-690-4993		

**ROOF TRUSSES**

PROFILE	QTY PLY	PITCH		TYPE ID	BASE SPAN	O/A SPAN	LUMBER		OVERHANG	CANTILEVER		STUB	
							TOP	BOT		LEFT	RIGHT	LEFT	RIGHT
	1	8.00	0.00	COMMON A01	24-07-00	24-07-00	2 X 4	2 X 4	00-11-00	00-11-00			
	5	8.00	0.00	COMMON A02	24-07-00	24-07-00	2 X 4	2 X 4	00-11-00	00-11-00			
	2	8.00	0.00	COMMON A03	24-07-00	24-07-00	2 X 4	2 X 4	00-11-00				
	1 2 Ply	8.00	0.00	COMMON A04	24-07-00	24-07-00	2 X 4	2 X 6	00-11-00				
	14	4.00	0.00	MONOPITCH B01	04-11-08	04-11-08	2 X 4	2 X 4	00-11-00				
	3	4.00	0.00	MONOPITCH B02	04-10-00	04-10-00	2 X 4	2 X 4	00-11-00				
	1 2 Ply	8.00	0.00	COMMON C01	11-11-00	11-11-00	2 X 4	2 X 6		00-11-00			
	2	8.00	0.00	COMMON C02	11-11-00	11-11-00	2 X 4	2 X 4		00-11-00			
	1 2 Ply	8.00	0.00	COMMON C03	11-11-00	11-11-00	2 X 4	2 X 6					
	1	9.00	0.00	ROOF D01	06-05-00	06-05-00	2 X 4	2 X 6					
	1	9.00	0.00	ATTIC E01	33-03-00	26-10-00	2 X 6	2 X 8		00-11-00		06-05-00	
	8	9.00	0.00	ATTIC G01	33-03-00	33-03-00	2 X 6	2 X 8		00-11-00			
	2	4.00	0.00	ATTIC G02	38-03-00	33-03-00	2 X 6	2 X 8		00-11-00		05-00-00	
	4	4.00	0.00	ATTIC G03	38-03-00	33-03-00	2 X 6	2 X 8		00-11-00		05-00-00	
	4 2 Ply	9.00	0.00	ATTIC GIRDER G04	33-03-00	33-03-00	2 X 6	2 X 10		00-11-00			
	6	4.00	0.00	ATTIC G05	38-03-00	33-03-00	2 X 6	2 X 8		00-11-00	04-00-00		05-00-00
	1 2 Ply	4.00	0.00	ATTIC GIRDER G06	38-03-00	33-03-00	2 X 6	2 X 8		00-11-00			05-00-00
	4	9.00	0.00	ATTIC G07	33-03-00	33-03-00	2 X 6	2 X 8		00-11-00			
	1	9.00	0.00	ATTIC G08	33-03-00	33-03-00	2 X 6	2 X 8		00-11-00			
	2	8.00	0.00	COMMON H01	06-09-00	06-09-00	2 X 4	2 X 4	00-11-00	00-11-00			
	10	8.00	0.00	COMMON H02	06-09-00	06-09-00	2 X 4	2 X 4	00-11-00	00-11-00			
	2	8.32	0.00	JACK-OPEN J01	02-01-06	02-01-06	2 X 4	2 X 4	00-11-15				
	1	9.00	0.00	JACK-OPEN J02	02-00-00	02-00-00	2 X 4	2 X 4	00-11-00				

**NON ITEMIZED QUOTE**

**QUOTE # Q2201696**



**Carolina Structural Systems**

P.O. Box 157, Ether, NC 27247  
225 Frame Shop Rd., Star, NC 27356  
910-491-9004

844-767-1926

ORDER DATE	//	CUST PO #	
DELIVERY DATE	//	COUNTY	HARNETT
ORDERED BY	TARYN DONAHUE	TERMS	NET 30 DAYS
SUPERINTENDENT	TARYN DONAHUE	SALES REP	SCOTT LAIL
JOBSITE PHONE #		DESIGNER	JEREMY

SOLD TO	<b>VALUE BUILD HOMES</b> 3015 JEFFERSON DAVIS SANFORD, NC 27332	<b>JOB NAME:</b> WHEELER: 23-53-09 <b>MODEL:</b> PAMLICO- C <b>DELIVERY INSTRUCTIONS:</b>	<b>LOT #</b> <b>SUBDIV:</b>
	<b>SHIPPED TO</b> 1175 ROUNDABOUT RD. CAMERON, NC 28326	<b>OPTIONS:</b> <b>JOB CATEGORY:</b> SINGLE FAMILY <b>SPECIAL INSTRUCTIONS:</b> Paul McNeil 910-690-4993	

**ROOF TRUSSES**

PROFILE	QTY	PITCH		TYPE ID	BASE SPAN	O/A SPAN	LUMBER		OVERHANG	CANTILEVER		STUB	
		PLY					TOP	BOT		LEFT	RIGHT	LEFT	RIGHT
	1	8.00	0.00	MONOPITCH J03	04-00-00	04-00-00	2 X 4	2 X 4	00-11-00				
	3	8.00	0.00	JACK-OPEN J04	04-00-00	04-00-00	2 X 4	2 X 4	00-11-00				
	1	8.00	0.00	VALLEY V01	06-06-08	06-06-08	2 X 4	2 X 4					
	1	8.00	0.00	VALLEY V02	11-00-08	11-00-08	2 X 4	2 X 4					
	1	8.00	0.00	VALLEY V03	15-06-08	15-06-08	2 X 4	2 X 4					
	1	8.00	0.00	VALLEY V04	17-09-11	17-09-11	2 X 4	2 X 4					
	1	8.00	0.00	VALLEY V05	04-08-07	04-08-07	2 X 4	2 X 4					
	1	8.00	0.00	VALLEY V06	08-07-00	08-07-00	2 X 4	2 X 4					
	2	8.00	0.00	VALLEY V07	06-06-09	06-06-09	2 X 4	2 X 4					

**ROOF SUB-TOTAL: \$ 19,140.00**

**ITEMS**

QTY	ITEM TYPE	SIZE	LENGTH FT-IN-16	NOTES
1	JOBSITE PACKAGE			A Jobsite Package is shipped with every project and included in the price of that project. The Jobsite Package includes installation and bracing recommendations, and may include a placement plan (layout) and individual component drawings. Permanent and temporary bracing, including labor, material and locations, are the responsibility of the installing contractor.
2	LP - LVL	1.75" x 9.25"	06-00-00	
1	Hanger	LUS26		
1	Fuel Surcharge	Surcharge		
15	Hanger	THA29		

**ITEMS SUB-TOTAL: \$ 325.00**

<b>QUOTE # Q2201696</b>	<b>DATE QUOTED: 11/30/22</b>	<b>THIS QUOTE EXPIRES ON: 12/07/22</b>						
<b>ACCEPTED BY SELLER</b>  BY: _____ TITLE: _____ DATE OF ACCEPTANCE: _____	<b>ACCEPTED BY BUYER</b> PURCHASER: _____ BY: _____ TITLE: _____ ADDRESS: _____ PHONE: _____ DATE: _____	<table border="1"> <tr> <td><b>SUB-TOTAL</b></td> <td>\$19,465.00</td> </tr> <tr> <td><b>SALES TAX 7.000%</b></td> <td>1,362.55</td> </tr> <tr> <td><b>GRAND TOTAL</b></td> <td><b>\$20,827.55</b></td> </tr> </table>	<b>SUB-TOTAL</b>	\$19,465.00	<b>SALES TAX 7.000%</b>	1,362.55	<b>GRAND TOTAL</b>	<b>\$20,827.55</b>
<b>SUB-TOTAL</b>	\$19,465.00							
<b>SALES TAX 7.000%</b>	1,362.55							
<b>GRAND TOTAL</b>	<b>\$20,827.55</b>							