

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: LIBERTY MEADOWS

LOT 33 (NEW)

INITIAL SYSTEM: LOW PROFILE CHAMBER

REPAIR: LOW PROFILE CHAMBER

DISTRIBUTION: PRESSURE MANIFOLD

DISTRIBUTION PRESSURE MANIFOLD

BENCHMARK: 100.0

LOCATION PC 32/33 (INITIAL)

NO. BEDROOMS: 3

LTAR 0.3 SPD/FT²

SEPTIC TANK SIZE 1000

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
1	R	99.67	60'
2	B	99.25	60'
3	R	98.92	60'
4	B	98.50	60'
5	R	98.08	60'
6	B	97.67	60'
7	R	97.25	60'
			<u>420'</u>
8	B	100.08	48'
9	W	99.75	85'
10	Y	99.58	80'
11	P	99.42	65'
12	B	99.25	60'
13	W	99.08	60'
14	Y	98.84	55'
15	P	98.75	45'

Install
system

BY BC RYAN

DATE 06/14/22

TYPICAL PROFILE (INITIAL)
0-10 US (VF, wgt)
10-36 + 500 (Ri, hll)
1" x 23"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.
DESIGNS DO NOT GUARANTEE FUNCTIONALITY

TRACT 3B OF
 DB 3703, PG 854
 LOT A OF
 PB 2012, PG 549
 FUTURE DEVELOPMENT

