

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: LIBERTY MEADOWS

LOT 33 (New)

INITIAL SYSTEM: LOW PROFILE CHAMBER

REPAIR: LOW PROFILE CHAMBER

DISTRIBUTION: PRESSURE MANIFOLD

DISTRIBUTION PRESSURE MANIFOLD

BENCHMARK: 100.0

LOCATION PC 32/33 (INITIAL)

NO. BEDROOMS: 3

LTAR 0.3 SPD/FTL

SEPTIC TANK SIZE 1000

PUMP TANK SIZE 1000

LINE	FLAG COLOR	ELEVATION	LENGTH
1	R	99.67	60'
2	B	99.25	60'
3	R	98.92	60'
4	B	98.50	60'
5	R	98.08	60'
6	B	97.67	60'
7	R	97.25	60'
			<u>420'</u>
8	B	100.08	48'
9	W	99.75	85'
10	Y	99.58	80'
11	P	99.42	65'
12	B	99.25	60'
13	W	99.08	60'
14	Y	98.84	55'
15	P	98.75	45'
			<u>470' AVAILABLE</u>

Installed system

BY BC Regner

DATE 02/14/22

TYPICAL PROFILE (INITIAL)  
0-10 US (USF, wgs)  
10-36 + 500 (15' / 40')  
1" x 2" x 23"

**THERE SHALL BE NO GRADING,  
 CUTTING, LOGGING OR OTHER SOIL  
 DISTURBANCE IN SEPTIC AREA**

HEALTH DEPARTMENT USE ONLY.  
 DESIGNS DO NOT GUARANTEE FUNCTIONALITY

TRACT 3B OF  
 DB 3703, PG 854  
 LOT A OF  
 PB 2012, PG 549

FUTURE DEVELOPMENT

