

100
73

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadow
Pump to
INITIAL SYSTEM: APPROVED 25% REDUCTION

LOT 28 (New)
Pump to
REPAIR Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION Pol 40 BC 24/25

NO. BEDROOMS: 3

LTAR 0.35 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	O	101.00	55
2	P	100.91	55
3	B	100.75	75
4a	R	100.67	75
			260
4b	R	100.67	10
5	Y	100.17	90
6	Pu	99.93	90
7	O	99.59	95
			295 AVAIL

BY B.C. Raynor

DATE 02/23/2022

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-17 LS vfri gran

CUTTING, LOGGING OR OTHER SOIL

17-36 SCL firm SBK

DISTURBANCE IN SEPTIC AREA

CR2 ≥ 26"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY