




Kempsville Chesapeake Component Plant
 3300 Business Center Drive
 Chesapeake, VA 23323

Phone #: 757-485-8590

Builder: DRB HOMES
Project: LOT 90 FARM AT
NEILLS CREEK
CAMERON 2



THE PLACEMENT PLAN NOTES:


1. The Placement Plan is a diagram for component installation. It is not an engineered drawing and has not been reviewed by an engineer. The Owner/Building Designer is responsible for obtaining an engineer's review if one is required by the local jurisdiction.
2. The responsibilities of the Owner, Contractor, Building Designer, Component Designer and Component Manufacturer shall be as set forth in ANSI/TPI 1. Capitalized terms shall be as defined in ANSI/TP 1 unless otherwise indicated.
3. Each Component is designed as an individual component utilizing information provided by others. The Owner/Building Designer is responsible for reviewing all Component Submittal Packages and individual Component Design Drawings for compliance with the Construction Documents and compatibility with the overall Building design.
4. Contractor will not proceed with component installation until the Owner/Building Designer has reviewed the Component Submittal Package. Questions on the suitability of any Component will be resolved by the Building Designer.
5. The Building Designer and Contractor are responsible for all temporary and permanent bracing.
6. The Placement Plan assumes the building is dimensionally correct, structurally sound, and in a suitable condition to support each Component during installation and thereafter, including but not limited to installation of all bearing points. Proper design and construction of all structural components, including foundations, headers, beams, walls and columns are the responsibility of the Owner, Building Designer and Contractor.
7. Do not cut, drill, or modify any Component without first consulting the Component Manufacturer or Building Designer. Damaged Components shall not be installed unless directed by the Building Designer or approved by the Component Manufacturer.
8. Components must be handled and installed following all applicable safety standards and best practices, including but not limited to BCSI, OSHA, TPI and local codes. Failure to properly handle, brace or otherwise install Component can result in serious injury or death.

General Notes: ** CUTTING OR DRILLING OF COMPONENTS SHOULD NOT BE DONE WITHOUT CONTACTING COMPONENT SUPPLIER FIRST. CUSTOMER TAKES FULL RESPONSIBILITY FOR COMPONENTS IF CUT BEFORE AUTHORIZATION.

** LVL AND JOISTS MUST BE FULLY CONNECTED TOGETHER PRIOR TO ADDING ANY LOADS.

Revisions	
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name
00/00/00	Name

This is an I-Joist Placement Plan Only. All designs of I-joists must follow the IBC/IRC Code Requirements along with Manufacturer's guidelines. This is NOT an engineered plan. This placement plan is created from plans provided by the customer using Manufacturer's guidelines. It is the responsibility of the EOR, or builder, to review and approve all bearing conditions, connections, spans, loading, product usage, and quantities. Do not notch or drill holes in beams or flanges on joists without prior approval from the manufacturing Representative unless following hole guidelines in the installation guide of product. Builder takes full responsibility for doing so and NO Back charge will be accepted.



Products				
PlotID	Length	Product	Plies	Net Qty
J22	22' 0"	14" PJI-40	1	15
J22-2	22' 0"	14" PJI-40	2	4
J20	20' 0"	14" PJI-40	1	11
J18	18' 0"	14" PJI-40	1	11
J16	16' 0"	14" PJI-40	1	2
J4	4' 0"	14" PJI-40	1	3
DB7-2	10' 0"	2.0 RigidLam DF LVL 1-3/4 x 9-1/4	2	2
DB8-2	10' 0"	2.0 RigidLam DF LVL 1-3/4 x 9-1/4	2	2
DB6-2	8' 0"	2.0 RigidLam DF LVL 1-3/4 x 9-1/4	2	2
GDH-3	22' 0"	2.0 RigidLam DF LVL 1-3/4 x 11-7/8	3	3
FB5-3	18' 0"	2.0 RigidLam DF LVL 1-3/4 x 14	3	3
FB2-2	10' 0"	2.0 RigidLam DF LVL 1-3/4 x 14	2	2
FB3-2	10' 0"	2.0 RigidLam DF LVL 1-3/4 x 14	2	2
FB4	4' 0"	2.0 RigidLam DF LVL 1-3/4 x 14	1	1
FB6-2	16' 0"	2.0 RigidLam DF LVL 1-3/4 x 18	2	2
FB1-3	22' 0"	2.0 RigidLam DF LVL 1-3/4 x 24	3	3
RIM	12' 0"	1 1/8" x 14" APA Rim Board	1	11
BP	2' 0"	14" PJI-40	1	4

Accessories				
PlotID	Length	Product	Plies	Net Qty
		3/4" 4x8 OSB	1	35

Connector Summary					
PlotID	Qty	Manuf	Product	Backer Blocks	Web Stiff
H1	1	Simpson	HGUS412	No	No
H2	13	Simpson	IUS2.56/14	No	No
H4	3		SUL2.56/14	No	No

** FRAMER MUST REFER TO PLANS WHILE SETTING COMPONENTS.

** DIMENSIONS ARE READ AS: FOOT-INCH-SIXTEENTH.

** DAMAGED FLOOR JOISTS SHOULD NOT BE INSTALLED UNLESS APPROVED BY COMPONENT PLANT.










DRB HOMES
LOT 90 FARM AT NEILLS CREEK CAMERON 2
FLOOR JOIST LAYOUT

2ND FLOOR LAYOUT

Scale: 1/4" = 1'-0"
 Date: 6/14/23
 Designer: DH
 Project #: 22090049
 Sheet Number:

1 / 1



LABEL LEGEND	
BBO	= Beam by Others
PBO	= Post by Others
GBO	= Girder by Others
J	= I-Joist
FB	= Flush Beam
DB	= Dropped Beam
RB	= Roof Beam
BP	= Blocking Panels
SB	= Squash Blocks

** PLUMBING DROPS NOTED ARE IN APPROXIMATE LOCATIONS PER PLAN. BUILDER MUST VERIFY LOCATIONS BEFORE SETTING JOISTS.

** ALL POINT LOADS FROM ABOVE MUST BE TRANSFERRED TO BEARING FROM UNDER SIDE OF SHEATHING.

** REFER TO INSTALLATION GUIDE FOR PLY TO PLY CONNECTIONS.