


*Keep supply lines >5' from property lines.

*Some lines are flagged longer in the field than lengths indicate.

*No grading septic area.

System: Gravity to D-Box Lines: 1-4, (4x100'x3')Accepted Status System 0.35 Soil LTAR

Repair: Gravity to Serial Dist Lines: 5-8, (385') Accepted Status System 0.35 Soil LTAR





Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout Lot 92, Birchwood Subdivision Harnett County, North Carolina

Job# : 3753 Drawn By : LW Date: 7/20/2022 Revision: