Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 46 Sugarberry PI ISSUED TO: Wellco Contractors SUBDIVISION Rolling Springs REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance: Type of Structure: SFD (44'x31') Proposed Wastewater System Type: 25% Red Sys Projected Daily Flow: 480 GPD Number of Occupants: 8 Number of bedrooms: 4_ Basement Yes ☐ No May be required based on final location and elevations of facilities Pump Required: Yes Type of Water Supply: Community Public Well Distance from well ______feet X Five years Permit valid for: No expiration Permit conditions: REAS SEE ATTACHED SITE SKETCH Authorized State Agent:: The issuance of this permit by the Health Department in no way guarantees the Issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1954, .1955, .1956, .1955, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Wellco Contractors PROPERTY LOCATION: 46 Sugarberry PI SUBDIVISION Rolling Springs Facility Type: SFD (44'x31') Expansion Repair Basement? Yes Basement Fixtures? Yes Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 480 (See note below, if applicable) 25% Red Svs Number of trenches 3 Installation Requirements/Conditions Exact length of each trench 80 Septic Tank Size 1000 gallons Trench Spacing: 9 Feet on Center Pump Tank Size _____gallons Trenches shall be installed on contour at a Soil Cover: 6_____inches Maximum Trench Depth of: 18 (Maximum soil cover shall not exceed inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ft. TDH vs. _____ ____ inches below pipe Aggregate Depth: ______ inches above pipe inches total Conditions: WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: Lunderstand the system type specified is different from the type specified on the application. Laccept the specifications of this permit. Owner/Legal Representative Signature: _ This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Date: 3/2/23 Authorized State Agent: _ Construction Authorization Expiration Date: 3/2/28

Harnett County Department of Public Health Site Sketch

Property Location: 46 Sugarberry Place		
Issued To: Wellco Contractors	Subdivision Rolling Springs	Lot # 134
Authorized State Agent:	REHS (OLIVER TOLKSDOW)	Date: 3/2/23
* CALL WITH ANY QUESTIONS PRIOR TO INSTALLATION	DRAINAGE & DRAINAGE & UTILITY EASCHENT R A A E R A A E (4428) HOUSE (4428) DR 55'	

SUGAR BERRY PL