

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs

LOT 136

INITIAL SYSTEM: <sup>Pump</sup> APPROVED 25% REDUCTION

REPAIR <sup>Pump</sup> Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION WM 136 R side

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	Y	99.67	40
2	w/y	99.41	40
3	P	99.09	70
4	Pu	99.17	90
5a	Y	97.33	60
			300
R { 5b	Y	97.33	30
6	P	96.67	105
7	Pu	96.33	90
9	Y	95.93	75
			300

BY B.C. RAYMOND

DATE 11/11/2022

TYPICAL PROFILE

0-23 ls vfri gran

23-36 sll firm SBK

ca 2 / pm ≥ 36"

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email [mike@southeasternsoil.com](mailto:mike@southeasternsoil.com)

