## Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

Control of Control of the Control of	PROPERTY LOCATION: 95 KINGWO	ood Ct	
ISSUED TO: Dream Finders Homes	subdivision Oakmont		LOT # 319
NEW REPAIR EXPANSION STRUCTURE: SFD (50'x37')	Site Improvements rec	uired prior to Construction Authorizatio	n Issuance:
Proposed Wastewater System Type: 25% Red Sys			
Projected Daily Flow: 600 GPD			
Number of bedrooms: 5 Number of Occupants: 10	max		
Basement Yes No			
	final location and elevations of facilities		
Type of Water Supply: Community Public Well Permit conditions:		-	Five years  No expiration
	2/12/22		
Authorized State Agent::  The issuance of this permit by the Health Department in no way guarantees the issuance site is subject to revocation if the site plan, plat, or the intended use changes. The Imple the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.	of other permits. The permit holder is responsible for che owement Permit shall not be affected by a change in own	cking with appropriate governing bodies in meeti	
Co	nstruction Authorization		
	(Required for Building Permit)		
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956 with the attached system layout.		into this permit and shall be met. Systems shall	be installed in accordance
ISSUED TO: Dream Finders Homes	PROPERTY LOCATION: 95 Ki	nawood Ct	
BJOED TO. DIGGINI MICONO PROMISE	SUBDIVISION Oakmont	Hawood Ot	LOT # 319
(			_ 101 # 319
/ // <u> </u>	New Expansion Repair		
Basement? Yes No Basement Fixtures? Yes			
Type of Wastewater System** 25% Reduction Sys	stem	(Initial) Wastewater Flow: 600	GPD GPD
(See note below, if applicable 🔲)			
25% Red Sys	(Repair)		
Installation Requirements/Conditions Number o	f trenches 1		
Septic Tank Size 1250 gallons Exact leng	th of each trench 200 feet	Trench Spacing: 9 Fee	t on Center
Pump Tank Sizegallons Trenches s	hall be installed on contour at a	Soil Cover: 6inche	
	Trench Depth of: 18inches	(Maximum soil cover shall not	exceed
	ottoms shall be level to +/-1/4"	36" above the trench bottom)	
in all dire		above the trench bottom	
	ctions)		
Pump Requirements:ft. TDH vsGPM			_ inches below pipe
		Aggregate Depth:	inches above pipe
Conditions:			inches total
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FR NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD		REPAIR AREA.	
**If applicable: L understand the system type specified is different	from the type specified on the application	. I accept the specifications of this	permit.
Owner/Legal Representative Signature:		Date:	
Owner/Legal Representative Signature:  This Construction Authorization is subject to revocation if the site plan, plat, or the inten-	ded use changes. The Construction Authorization shall not	be transferred when there is a change in owners	hin of the site This
Construction Authorization is subject to compliance with the provisions of the Laws and F	dules for Sewage Treatment and Disposal and to the condit	ions of this permit.	ACHED SITE SKETCH
			The state of the s
Authorized State Agent:		3/13/23	- 1 1
	Construction Authorization Expiration D	Date: 3/13/28	

## Harnett County Department of Public Health Site Sketch

Property Location: 95 Kingwood	l Ct				
Issued To: Dream Finders Home	S	Subdiv	ision Oakmont		Lot # 319
Authorized State Agent:	Mille	REJES	(OH VERZ TOLKSDORE)	Date: 5	3/13/23

