**ROOF & FLOOR** ComTech TRUSSES & BEAMS Reilly Road Industrial Park P.O. Box 40408 Fayetteville, N.C. 28309 (910) 864-TRUS

		DATE	DZIZ IIZS PAGE I
REQ. QUOTE DATE	11	ORDER#	J0322-1318
ORDER DATE	03/10/22	QUOTE #	
DELIVERY DATE	11	CUSTOMER ACCT#	0000007216
DATE OF INVOICE	11	CUSTOMER PO#	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	Neil Baggett

**Precision Custom Homes** 256 Briar Hill Rd. Raeford, NC 28376

Lot 31 Liberty Meadow

(910) 988-8172

Cameron, NC

SOLD

TO

T

Roof Order

JOB NAME: Lot 31 Liberty Meadow **LOT #** 31 SUBDIV: Liberty Meadow MODEL:Roof TAG: Menger JOB CATEGORY: B & S - Build and Ship

**DELIVERY INSTRUCTIONS:** 

54 miles round trip

**Precision Custom Homes and** 

SPECIAL INSTRUCTIONS:

**PLAN SEAL DATE:** 

DATE BUILDING DEPARTMENT OVERHANG INFO HEEL HEIGHT 00-06-08 REQ. LAYOUTS REQ. ENGINEERING QUOTE LAYOUT NB END CUT RETURN 02/21/23 1 **CUTTING** NB 02/21/23 PLUMB **GABLE STUDS** 24 IN. OC JOBSITE JOBSITE

ROOF T	RUS	SES		DADING FORMATION	TCLL-TCDL-B0		-	RESS INCR.	RO	OF TRUSS S	PACING: 24.0	IN. O.C. (TYP	.)	
PROFILE	QTY PLY	PIT TOP	ВОТ	TYPE ID	BASE O/A	LUM	IBER BOT		HANG RIGHT	REACTIO	NS			
	1	8.25	0.00	GABLE A1-GE	24-09-00 24-09-00			01-02-08		Joint 2 283.0 lbs. -157.9 lbs.	Joint 17 87.9 lbs. -37.4 lbs.	Joint 18 205.6 lbs. -110.3 lbs.	Joint 19 179.9 lbs. -105.4 lbs.	Joint 20 166.5 lbs. -40.4 lbs.
	6	8.25	0.00	COMMON A2	24-09-00 24-09-00	2 X 6	2 X 6	01-02-08		Joint 2 1119.2 lbs. -55.3 lbs.	Joint 11 1265.6 lbs. -65.8 lbs.			
	1	8.25	4.50	ROOF A3	28-03-00 28-03-00	2 X 6	2 X 6	01-02-08		Joint 2 712.9 lbs. -28.2 lbs.	Joint 10 106.9 lbs. -502.0 lbs.	Joint 11 2002.8 lbs. -188.7 lbs.		
	3	8.25	4.50	SCISSORS A4	21-02-08 21-02-08	2 X 6	2 X 6	01-02-08		Joint 2 904.2 lbs. -25.7 lbs.	Joint 8 825.5 lbs. -112.5 lbs.			
	1	8.25	4.50	SCISSORS A4-A	21-02-08 21-02-08	2 X 6	2 X 6			Joint 1 827.7 lbs. -8.0 lbs.	Joint 7 827.7 lbs. -113.1 lbs.			
	2	8.25	4.50	SCISSORS A5	21-06-00 21-06-00	2 X 6	2 X 6			Joint 1 839.4 lbs. -11.2 lbs.	Joint 7 839.4 lbs. -108.9 lbs.			
	1	3.50	4.50	ROOF A6	37-03-00 37-03-00	2 X 6	2 X 6	01-02-08		Joint 2 634.2 lbs. -284.7 lbs.	Joint 10 781.3 lbs. -81.0 lbs.	Joint 12 1590.9 lbs. -141.6 lbs.		
	1	3.50	0.00	ROOF A7	37-03-00 37-03-00	2 X 6	2 X 6	01-02-08		Joint 2 443.4 lbs. -251.3 lbs.	Joint 9 1033.6 lbs. -79.6 lbs.	Joint 12 1744.3 lbs. -157.0 lbs.		
	1	3.50	0.00	ROOF A8	37-03-00 37-03-00	2 X 6	2 X 6	01-02-09		Joint 2 342.0 lbs. -214.3 lbs.	Joint 10 1069.4 lbs. -76.4 lbs.	Joint 14 1805.7 lbs. -182.7 lbs.		
	1	3.50	0.00	ROOF A9	37-03-00 37-03-00	2 X 6	2 X 6	01-02-09		Joint 2 335.3 lbs. -208.1 lbs.	Joint 10 1061.7 lbs. -74.0 lbs.	Joint 14 1816.1 lbs. -190.0 lbs.		
	1	12.00	0.00	GABLE B1-GE	14-03-00 14-03-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 12 251.9 lbs. -142.2 lbs.	Joint 13 245.5 lbs. -239.6 lbs.	Joint 14 172.7 lbs. -167.3 lbs.	Joint 15 276.0 lbs. 36.3 lbs.	Joint 16 279.8 lbs. 23.8 lbs.

**ROOF & FLOOR** ComTech| TRUSSES & BEAMS Reilly Road Industrial Park P.O. Box 40408 Fayetteville, N.C. 28309 (910) 864-TRUS

		DAIL	DEIZ IIZO I AGE Z
REQ. QUOTE DATE	11	ORDER#	J0322-1318
ORDER DATE	03/10/22	QUOTE #	
DELIVERY DATE	11	CUSTOMER ACCT#	0000007216
DATE OF INVOICE	11	CUSTOMER PO#	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	Neil Baggett

**Precision Custom Homes** 256 Briar Hill Rd. Raeford, NC 28376 (910) 988-8172

Lot 31 Liberty Meadow

Cameron, NC

SOLD

T O

T

Roof Order

JOB NAME: Lot 31 Liberty Meadow **LOT #** 31 SUBDIV: Liberty Meadow MODEL:Roof TAG: Menger JOB CATEGORY: B & S - Build and Ship

**DELIVERY INSTRUCTIONS:** 

54 miles round trip

**Precision Custom Homes and** 

SPECIAL INSTRUCTIONS:

**PLAN SEAL DATE:** 

DATE BUILDING DEPARTMENT OVERHANG INFO HEEL HEIGHT 00-06-08 REQ. LAYOUTS REQ. ENGINEERING QUOTE LAYOUT NB END CUT RETURN 02/21/23 1 **CUTTING** NB 02/21/23 PLUMB **GABLE STUDS** 24 IN. OC JOBSITE JOBSITE

ROOF T	RUS	SES		DADING FORMATION	TCLL-TCDL-B0		_	ESS INCR.	RO	OF TRUSS SI	PACING: 24.0	IN. O.C. (TYP	.)	
PROFILE	QTY	PIT		TYPE		LUN	_		HANG	DE 4 07:01				
TROTILL	PLY	TOP	ВОТ	ID	O/A	TOP		LEFT	RIGHT	REACTIO	NS			
	1	12.00	0.00	COMMON B2	14-03-00 14-03-00	2 X 6	2 X 6	01-02-08	01-02-08	Joint 7 635.6 lbs. -28.1 lbs.	Joint 9 635.6 lbs. -28.1 lbs.			
	3	12.00	0.00	COMMON B3	14-03-00 14-03-00	2 X 6	2 X 6			Joint 5 554.7 lbs. -20.2 lbs.	Joint 7 554.7 lbs. -20.2 lbs.			
	1	12.00	0.00	COMMON B4	11-11-00 11-11-00	2 X 6	2 X 6			Joint 5 458.0 lbs. -3.7 lbs.	Joint 7 458.8 lbs. -45.0 lbs.			
1	1	12.00	0.00	GABLE C1-GE	11-03-08 11-02-08	2 X 6	2 X 6	01-03-00	01-03-00	Joint 10 698.4 lbs. -612.8 lbs.	Joint 11 797.7 lbs. -718.2 lbs.	Joint 12 384.7 lbs. 70.8 lbs.	Joint 13 384.6 lbs. 71.7 lbs.	Joint 14 801.3 lbs. -721.5 lbs.
	2	12.00	0.00	COMMON C2	11-03-08 11-02-08	2 X 6	2 X 6	01-03-00	01-03-00	Joint 2 1071.1 lbs. -62.9 lbs.	Joint 6 526.2 lbs. -38.8 lbs.	Joint 8 526.2 lbs. -38.8 lbs.	Joint 10 1154.7 lbs. -44.3 lbs.	
Δ	4	12.00	0.00	COMMON C3	11-03-08 11-02-08	2 X 6	2 X 6			Joint 4 433.3 lbs. -45.0 lbs.	Joint 6 433.3 lbs. -45.0 lbs.			
	1	12.50	7.00	GABLE D1-GE	15-10-00 15-10-00	2 X 6	2 X 6	01-02-08		Joint 2 364.4 lbs. -268.7 lbs.	Joint 10 138.8 lbs. -45.7 lbs.	Joint 11 233.8 lbs. -281.2 lbs.	Joint 12 197.8 lbs. -164.3 lbs.	Joint 13 197.4 lbs. -122.1 lbs.
$\triangle$	7	12.50	7.00	SCISSORS D2	15-10-00 15-10-00	2 X 6	2 X 6	01-02-08		Joint 2 697.6 lbs. -32.5 lbs.	Joint 6 611.4 lbs. -29.1 lbs.			
$\triangle$	4	12.50	0.00	COMMON D3	15-01-08 15-01-08	2 X 6	2 X 6	01-02-08		Joint 2 662.0 lbs. -26.3 lbs.	Joint 7 598.4 lbs. -33.1 lbs.			
$\triangle$	1	12.50	0.00	ATTIC G1-GE	22-00-00 22-00-00	2 X 8	2 X 10	01-02-08	01-02-08	Joint 2 1555.9 lbs. 52.8 lbs.	Joint 10 1555.9 lbs. 52.8 lbs.			
$\triangle$	6	12.50	0.00	ATTIC G2	22-00-00 22-00-00	2 X 8	2 X 10	01-02-08	01-02-08	Joint 2 1562.0 lbs. 174.8 lbs.	Joint 10 1562.0 lbs. 174.8 lbs.			

## **Reaction Summary of Order ROOF & FLOOR** ComTech| TRUSSES & BEAMS

11 **REQ. QUOTE DATE** ORDER# J0322-1318 ORDER DATE 03/10/22 **QUOTE#** 0000007216 **DELIVERY DATE** CUSTOMER ACCT# 11 // DATE OF INVOICE **CUSTOMER PO#** ORDERED BY Shaun Garderner **INVOICE #** COUNTY Harnett **TERMS** Shaun Garderner Neil Baggett **SUPERINTENDANT SALES REP** (910) 988-8172 Neil Baggett **JOBSITE PHONE # SALES AREA** 

Reilly Road Industrial Park P.O. Box 40408 Fayetteville, N.C. 28309 (910) 864-TRUS

**Precision Custom Homes** 256 Briar Hill Rd. Raeford, NC 28376 (910) 988-8172

Lot 31 Liberty Meadow

Cameron, NC

**Precision Custom Homes and** 

SOLD

T O

S H I P

T O

JOB NAME: Lot 31 Liberty Meadow MODEL: Roof TAG: Menger **LOT #** 31 **SUBDIV:**Liberty Meadow JOB CATEGORY: B & S - Build and Ship

**DELIVERY INSTRUCTIONS:** 

54 miles round trip

SPECIAL INSTRUCTIONS:

**PLAN SEAL DATE:** 

DATE BUILDING DEPARTMENT OVERHANG INFO HEEL HEIGHT 00-06-08 REQ. LAYOUTS REQ. ENGINEERING QUOTE LAYOUT NB END CUT RETURN 02/21/23 Roof Order GABLE STUDS CUTTING NB 02/21/23 PLUMB 24 IN. OC JOBSITE JOBSITE

ROOF T	RUS	SES		DADING FORMATION	TCLL-TCDL-B0		_	RESS INCR.	RO	OF TRUSS SPACING: 24.0 IN. O.C. (TYP.)	
PROFILE	QTY PLY	PIT TOP	CH BOT	TYPE ID	BASE O/A	LUN TOP	BER	OVER	HANG RIGHT	REACTIONS	
	6	12.50	0.00	ATTIC	22-00-00 22-00-00				KIGHT	Joint 2 Joint 10 1563.7 lbs. 1517.8 lbs. 174.3 lbs. 177.0 lbs.	
$\triangle$	1	12.50	0.00	ATTIC G5	22-00-00 21-08-08	2 X 8	2 X 10	01-02-08		Joint 2 Joint 11 1565.0 lbs. 1517.7 lbs. 174.4 lbs. 176.9 lbs.	
Â	6	12.50	0.00	ROOF G6	21-08-08 21-08-08	2 X 6	2 X 6	01-02-08		Joint 2 Joint 12 Joint 13 662.6 lbs. 234.1 lbs. 1034.1 lbs. -92.6 lbs144.2 lbs. 3.0 lbs.	
Â	1	12.50	0.00	ROOF G7-GE	21-08-08 21-08-08	2 X 6	2 X 6	01-02-08		Joint 2 Joint 12 Joint 13 668.9 lbs. 658.8 lbs. 1350.1 lbs. -209.4 lbs310.7 lbs168.1 lbs.	
	1	3.50	0.00	HALF HIP H1	16-02-08 16-00-08	2 X 6	2 X 6	01-02-08		Joint 2 Joint 6 1175.0 lbs. 1219.3 lbs. -490.3 lbs512.2 lbs.	
	1 2 Ply	0.00	0.00	FLAT GIRDER K1	24-09-01 24-09-01	2 X 6	2 X 6			Joint 9 Joint 13 3064.2 lbs. 1784.0 lbs. -425.8 lbs597.0 lbs.	
	1	3.50	0.00	ROOF M1	22-09-13 22-09-13	2 X 6	2 X 6	01-02-08		Joint 2 Joint 10 Joint 12 455.0 lbs. 268.1 lbs. 1156.4 lbs. -171.7 lbs46.8 lbs346.9 lbs.	
	1	3.50	0.00	HALF HIP M2	22-09-13 22-09-13	2 X 6	2 X 6	01-02-08		Joint 2 Joint 9 Joint 10 471.0 lbs. 309.3 lbs. 1120.0 lbs. -174.4 lbs14.3 lbs332.6 lbs.	
	1	3.50	0.00	HALF HIP M3	22-09-13 22-09-13	2 X 6	2 X 6	01-02-08		Joint 2 Joint 9 Joint 10 482.4 lbs. 332.1 lbs. 1093.9 lbs. -175.1 lbs17.7 lbs320.6 lbs.	
	4	8.25	0.00	MONOPITCH P1	12-08-00 11-00-08	2 X 6	2 X 6	01-02-08		Joint 2 Joint 7 Joint 9 326.9 lbs. 335.3 lbs. 336.5 lbs42.4 lbs. 52.5 lbs166.7 lbs.	
	1	8.25	0.00	VALLEY VA1	22-03-14 22-03-14	2 X 4	2 X 6				12 .1 lbs. .6 lbs.

			DATE	02/21/23 PAGE 4
Reaction Summary of Order	REQ. QUOTE DATE	11	ORDER #	J0322-1318
	ORDER DATE	03/10/22	QUOTE #	
	DELIVERY DATE	11	CUSTOMER ACCT#	0000007216
ROOF & FLOOR	DATE OF INVOICE	11	CUSTOMER PO#	
ComTech TRUSSES & BEAMS	ORDERED BY	Shaun Garderner	INVOICE #	
Reilly Road Industrial Park P.O. Box 40408	COUNTY	Harnett	TERMS	

Shaun Garderner

(910) 988-8172

Reilly Road Industrial Park P.O. Box 40408 Fayetteville, N.C. 28309 (910) 864-TRUS

**Precision Custom Homes** 256 Briar Hill Rd. Raeford, NC 28376 (910) 988-8172

ТО

MODEL:Roof **DELIVERY INSTRUCTIONS:** 

54 miles round trip

JOB NAME: Lot 31 Liberty Meadow

SUPERINTENDANT

JOBSITE PHONE #

**Precision Custom Homes and** Lot 31 Liberty Meadow Cameron, NC

SPECIAL INSTRUCTIONS:

PLAN SEAL DATE:

SUBDIV: Liberty Meadow

**SALES REP** 

**LOT #** 31

**SALES AREA** 

JOB CATEGORY: B & S - Build and Ship

Neil Baggett

Neil Baggett

<b>BUILDING DEPARTMENT</b>	OVERHANG INFO		HEEL HEIGHT	00-06-08	RE	REQ. LAYOUTS			REQ. ENGINEERING				QUOTE		11
Roof Order	END CUT	RETURN											LAYOUT	NB	02/21/23
	PLUMB		GABLE STUDS	24 IN. OC			JOBSITE	1			JOBSITE	1	CUTTING	NB	02/21/23

TAG: Menger

ROOF T	RUS	SES		DADING FORMATION	TCLL-TCDL-B0		_	ESS INCR.	ROOF TRUSS SPACING: 24.0 IN. O.C. (TYP.)						
PROFILE	QTY PLY	PIT TOP	ВОТ	TYPE ID	BASE O/A		BER BOT	OVER LEFT	HANG RIGHT	REACTIO	NS				
	1	8.25	0.00	VALLEY	19-03-08 19-03-08				rtioiii	Joint 7 90.1 lbs. -39.2 lbs.	Joint 8 271.6 lbs. -78.7 lbs.	Joint 9 463.3 lbs. -109.3 lbs.	Joint 11 461.7 lbs. 83.0 lbs.	Joint 12 461.5 lbs. -107.7 lbs.	
	1	8.25	0.00	VALLEY VA3	14-07-15 14-07-15	2 X 4	2 X 4			Joint 1 116.5 lbs. -11.2 lbs.	Joint 5 103.4 lbs. 9.0 lbs.	Joint 6 350.2 lbs. -103.7 lbs.	Joint 7 254.3 lbs. 53.0 lbs.	Joint 8 350.4 lbs. -103.9 lbs.	
	1	8.25	0.00	VALLEY VA4	08-07-04 08-07-04	2 X 4	2 X 4			Joint 1 169.5 lbs. -26.7 lbs.	Joint 3 169.6 lbs. -32.9 lbs.	Joint 4 279.6 lbs. 21.1 lbs.			
	1	12.00	0.00	VALLEY VB1	04-01-04 04-01-04	2 X 4	2 X 4			Joint 1 84.3 lbs. -15.0 lbs.	Joint 3 84.3 lbs. -15.0 lbs.	Joint 4 108.3 lbs. 14.3 lbs.			
	1	12.00	0.00	VALLEY VC1	02-08-01 02-08-01	2 X 4	2 X 4			Joint 1 81.2 lbs. -2.6 lbs.	Joint 3 81.2 lbs. -2.6 lbs.				
	5	3.50	0.00	JACK-OPEN XH1	06-01-00 06-01-00	2 X 4	2 X 6	01-02-08		Joint 2 324.9 lbs. -135.1 lbs.	Joint 3 167.8 lbs. -68.3 lbs.	Joint 4 117.9 lbs. -30.3 lbs.			
B	2	3.50	0.00	JACK-OPEN YH1	01-11-15 01-11-15	2 X 4	2 X 4	01-02-08		Joint 2 175.6 lbs. -83.9 lbs.	Joint 3 35.4 lbs. -19.8 lbs.	Joint 4 39.1 lbs. -10.1 lbs.			
	2	3.50	0.00	JACK-OPEN YH2	03-11-15 03-11-15	2 X 4	2 X 4	01-02-08		Joint 2 246.3 lbs. -107.6 lbs.	Joint 3 100.2 lbs. -43.8 lbs.	Joint 4 76.1 lbs. -19.6 lbs.			
	1	2.48	0.00	DIAGONAL HIP ZH1	08-05-12 08-05-12	2 X 4	2 X 6	01-08-08		Joint 2 458.3 lbs. -203.3 lbs.	Joint 7 369.6 lbs. -150.3 lbs.				

## **ITEMS**

QTY	ITEM TYPE	SIZE	<b>LENGTH</b> FT-IN-16	PART NUMBER	NOTES
1	Hangers, USP	HJC26			SIMPSON (THJU26)

	ROOF & FLOOR
ComTech	TRUSSES & BEAMS
Reilly Road Industrial	Park P.O. Box 40408
Fayetteville, N.C. 28	3309 (910) 864-TRUS

		DATE	DETENTED THOSE O
REQ. QUOTE DATE	11	ORDER#	J0322-1318
ORDER DATE	03/10/22	QUOTE #	
DELIVERY DATE	11	CUSTOMER ACCT#	0000007216
DATE OF INVOICE	11	CUSTOMER PO#	
ORDERED BY	Shaun Garderner	INVOICE #	
COUNTY	Harnett	TERMS	
SUPERINTENDANT	Shaun Garderner	SALES REP	Neil Baggett
JOBSITE PHONE #	(910) 988-8172	SALES AREA	Neil Baggett

Precision Custom Homes 256 Briar Hill Rd. Raeford, NC 28376 (910) 988-8172 JOB NAME: Lot 31 Liberty Meadow

MODEL: Roof

TAG: Menger

JOB CATEGORY: B & S - Build and Ship

DELIVERY INSTRUCTIONS:

54 miles round trip

Precision Custom Homes and Lot 31 Liberty Meadow Cameron, NC

SPECIAL INSTRUCTIONS:

PLAN SEAL DATE:

<b>BUILDING DEPARTMENT</b>	OVERHANG INFO		HEEL HEIGHT	00-06-08	RI	REQ. LAYOUTS		REQ. ENGINEERING				QUOTE		11	
Roof Order	END CUT	RETURN											LAYOUT	NB	02/21/23
	PLUMB		GABLE STUDS	24 IN. OC			JOBSITE	1			JOBSITE	1	CUTTING	NB	02/21/23

## **ITEMS**

SOLD TO

TEMO					
QTY	ITEM TYPE	SIZE	<b>LENGTH</b> FT-IN-16	PART NUMBER	NOTES
8	Hangers, USP	HUS 26			SIMPSON (HUS26)
3	Hangers, USP	JUS24			SIMPSON (LUS24)
4	Hangers	LSSH210	00-00-00		
					•
2	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	09-00-00		BM1
	, , , ,				•
2	LVL Beams (Sized)	LVL, 1-3/4" x 9-1/4" (S)	08-00-00		BM2
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	22-00-00		GDH
	1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -	, (9)			1
2	LVL Beams (Sized)	LVL, 1-3/4" x 11-7/8" (S)	16-00-00		BM3
	LVL Boarns (Oizea)	[ LVL, 1 0/1 X 11-1/0 (0) ]	10 00-00		Dillo