Harnett County Department of Public Health

Improvement Permit

A building permit can	PROPERTY LOCATION: 1254 Holly Spring Church Rd
ISSUED TO: Jordan Goins	SUBDIVISION LOT #
NEW REPAIR EXPANSION	Site Improvements required prior to Construction Authorization Issuance:
Type of Structure: 80 x 64' SFD	
Proposed Wastewater System Type: Pump To 25 % reduct. Projected Daily Flow: 480 GPD	201
Projected Daily Flow: 480 GPD	
Number of bedrooms: 4 Number of Occupants: 8	max
Basement Yes No	
Pump Required: No	
Type of Water Supply: Community Public Well Dista	nce from wellfeet Permit valid for: 💆 Five years
Permit conditions:	No expiration
Authorized State Agent:: Mach the REHS	Date: 5-22-23 SEE ATTACHED SITE SKETCH
0	er permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This
	Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.	
Consti	ruction Authorization
	guired for Building Permit)
	, 1958, and 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance
with the attached system layout.	
ISSUED TO: Jordan Goins	PROPERTY LOCATION: 1254 Holly Spring Church Rd
Facility Type: 80'x64' SFD New	SUBDIVISION LOT # LOT #
	C Expansion C Repair
Basement? Yes No Basement Fixtures? Yes	(Initial) Wastewater Flow: 480 GPD
	(Initial) Wastewater Flow: 480 GPD
(See note below, if applicable)	—
pump To 25% reduce	(Kepair)
Installation Requirements/Conditions Number of trend	thes9
Septic Tank Size 1000 gallons Exact length of	each trench 300 feet Trench Spacing: 9 Feet on Center
	e installed on contour at a Soil Cover: 6 inches
Maximum Trench	Depth of: 18-24 inches (Maximum soil cover shall not exceed
(Trench bottoms	shall be level to +/-1/4" 36" above the trench bottom)
in all directions	
Pump Requirements:ft. TDH vsGPM	inches below pipe
	Aggregate Depth: inches above pipe
Conditions:	inches total
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM A	NY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD ARE	
**If and in his I understand the system time specified is different from	the time envited on the application I account the restifications of this parmit
applicable: I understand the system type specified is different from	the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature:	Date:
0 1 0	
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH	
1 / M	
Ma/ // 1541	
Authorized State Agent: Meh W REHS Date: 5.22-23	
Authorized State Agent: Meh Chaets Construction Authorization Expiration Date: 5-22-28 Construction Authorization Expiration Date: 5-22-28	

Harnett County Department of Public Health Site Sketch

