

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Liberty Meadows

LOT 9 → 17

INITIAL SYSTEM: <sup>GRAV</sup> APPROVED 25% REDUCTION

REPAIR <sup>GRAV</sup> Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION ToS FC 17/18

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft<sup>2</sup> 120.3

LINE	FLAG COLOR	ELEVATION	LENGTH
1	O	96.75	45
2	B	96.50	65
3	O	96.17	85
4	B	95.33	110
			<u>305'</u>

I {

5b	O	94.93	115
6	B	94.09	115
7	O	93.25	95
8	B	92.75	80
9	O	92.08	100
			<u>465</u>

R {

BY B.C. Raynor

DATE 12/04/2021

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

0-28 LS vfri gran

CUTTING, LOGGING OR OTHER SOIL

28-36 scl firm SBK

DISTURBANCE IN SEPTIC AREA

in 2 ≥ 36"

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GUARANTEE FUNCTIONALITY

width - as wide as lot allows  
depth = 50'

### Liberty Meadows

Lot 17 & 18

16 + 17

