


PLAN:  
Mises



**FRONT ELEVATION**

Scale: 1/4" = 1'0"

9'0" CEILING HEIGHT FIRST FLOOR  
(HEADER HEIGHT 7'6")  
8'0" CEILING HEIGHT SECOND FLOOR  
(HEADER HEIGHT 7')

FRAME WINDOWS TO HEADER HEIGHT

SHEET TITLE:  
**ELEVATIONS**

PROJECT ADDRESS:  
126 Sears Dr. (Lot 25)

DESIGNED BY:  
Precision Custom Homes  
Raeford, NC  
Shaun@PrecisionCustomHomesNC.com

DATE:

4/24/23

SCALE:

1/4" = 1'

SHEET:

**A-1**



**LEFT ELEVATION**

Scale: 1/8" = 1'0"




**RIGHT ELEVATION**

Scale: 1/8" = 1'0"




**REAR ELEVATION**

Scale: 1/8" = 1'0"




AREA SCHEDULE	
1ST FLOOR AREA	1,785 SF
2ND FLOOR AREA	646 SF
<b>TOTAL HEATED AREA</b>	<b>2,431 SF</b>
GARAGE	606 SF
FRONT PORCH	156 SF
REAR PORCH	100 SF
<b>TOTAL AREA UNDER ROOF</b>	<b>3,293 SF</b>


**FOUNDATION PLAN**  
Scale: 1/4" = 1'0"



**MONOLITHIC SLAB**



**LUG FOOTING**



**INTERIOR WALL @ GARAGE STEP DOWN**

**FOUNDATION NOTES:**

ALL FOOTINGS SHALL BEAR ON ORIGINAL UNDISTURBED SOIL  
 THE 28 DAY COMPRESSIVE STRENGTH OF ALL FOOTINGS IS 3000 PSI

PROVIDE WATER PROOFING AND PERIMTER DRAINS AS REQUIRED

FOOTING WIDTHS ARE BASED ON A LOAD BEARING SOIL CAPACITY OF 2000 PSI

PROVIDE 6 MIL POLY VAPOR BARRIER TO COVER GROUND IN CRAWL SPACE AND GROUND UNDER POURED CONCRETE

ALL ANCHOR BOLTS TO BE 1/2" X 12" LONG. ANCHOR BOLTS SHALL BE SPACED AT A MAXIMUM OF 6' ON CENTER AND NO MORE THEN 1' FROM EACH CORNER

**GENERAL FRAMING NOTES:**

ALL LUMBER IN CONTACT WITH CONCRETE OR MASONRY SHALLE BE PRESSURE TREATED

FRAMING LUMBER SHALL BE SYP #2 GRADE AND / OR SPRUCE PINE FIR #1 AND / OR KILN DRIED

WHERE PRE-ENGINEERED JOISTS AND TRUSSES ARE USED, MANUFACTURER SHALL PROVIDE DRAWINGS / SCHEMATICS, WHICH SHALL BEAR OF A N.C. ENGINEER

STUDS AND JOISTS SHALL NOT BE CUT TO INSTALL PLUMBING OR WIRING WITHOUT ADDING METAL OR WOOD SIDE PANELS TO STRENGTHEN MEMBER TO ITS ORIGINAL CAPACITY

NAIL MULTIPLE MEMBERS WITH 2 ROWS OF 16d NAILS STAGGERED 32" O.C. AND USE 3 X 16d NAILS 2" IN AT EACH END.


NAIL FLOOR JOISTS TO SILL PLATE WITH WITH 8d TOE NAILS

ALL EXPOSED FRAMING ON PORCHES OR DECKS SHALL BE PRESSURE TREATED

PROVIDE WATERPROOFING AND DRAINS AS REQUIRED


ALL FRAMING TO BE 16" O.C. WALL FRAMING DIMENSIONS ARE BASED ON 2X4 OR 2X6 EXTERIOR WALLS AND 2X4 INTERIOR WALLS. DOULBE / TRIPLE JACK STUDS AS NECESSARY UNDER HEADERS AS REQUIRED

LVL'S TO BE SIZED BY OTHERS (TRUSS MANUFACTURER)



**EXTERIOR WALL SECTION**

1. 15# FELT UNDERLAYMENT UNDER COMPOSITION SHINGLES.
2. ROOF DECKING.
3. 2 X RAFTERS / ENGINEERED TRUSSES
4. DOUBLE TOP PLATE.
5. 2 X 4 RETURN.
6. 3/4" FASCIA OR PVC TRIM COIL
7. 2 X FASCIA
8. 1/4" PLYWOOD OR VINYL SOFFIT
9. 1 X FREIZE BOARD (TO BE USED WITH BRICK VENEERS)
10. INSULATION BOARD OR HOUSE WRAP
11. AIR SPACE.
12. BRICK WITH BRICK TIES PER MANUFACTURER'S SPECIFICATIONS.
13. 1/2" X 12" ANCHOR BOLTS, 6'-0" O.C., 12" FROM CORNERS.
14. FLASHING WITH WEEP HOLES @ 48" O.C.
15. FINISHED GRADE.
16. FOOTING
17. COMPACTED EARTH FILL.
18. 6 MIL. VAPOR BARRIER
19. 4" CONCRETE SLAB, 3,000 P.S.I. WITH 6" X 6" 10 GA. X 10 GA. WELDED WIRE FABRIC.
20. 1/2" GYPSUM BOARD.



**STAIR DETAIL**

PLAN:  
Mises

SHEET TITLE:  
**DETAIL SHEETS**

PROJECT ADDRESS:  
126 Sears Dr. (Lot 25)


DESIGNED BY:  
Precision Custom Homes  
Rae ford, NC  
Shaun@PrecisionCustomHomesNC.com

DATE:  
4/24/23

SCALE:  
1/4" = 1'

SHEET:  
**A-3**





AREA SCHEDULE	
1ST FLOOR AREA	1,785 SF
2ND FLOOR AREA	646 SF
<b>TOTAL HEATED AREA</b>	<b>2,431 SF</b>
<hr/>	
GARAGE	606 SF
FRONT PORCH	156 SF
REAR PORCH	100 SF
<b>TOTAL AREA UNDER ROOF</b>	<b>3,293 SF</b>

PLAN:  
Mises

SHEET TITLE:  
**2nd FLOOR**

PROJECT ADDRESS:  
126 Sears Dr. (Lot 25)

DESIGNED BY:  
Precision Custom Homes  
Raeferd, NC  
Shaun@PrecisionCustomHomesNC.com

DATE:  
4/24/23

SCALE:  
1/4" = 1'

SHEET:  
**A-5**




ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park  
Fayetteville, N.C. 28309  
Phone: (910) 864-8787  
Fax: (910) 864-4444

**THIS IS A TRUSS PLACEMENT DIAGRAM ONLY.**  
These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. The individual design sheets for each truss design identified on the drawings are the property of the building designer. The building designer is responsible for the design of the roof and floor system and for the overall structure. The design of the truss support system including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding trusses, consult ICC-ES E-1000 and ICC-ES E-1001 provided with the truss delivery package or contact the building designer.

Bearing reactions less than or equal to 3000 lbs are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000 lbs but not greater than 15000 lbs. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000 lbs.

Signature: Neil Baggett



**Dimension Notes**

1. All exterior wall to wall dimensions are to face of stud unless noted otherwise
2. All interior wall dimensions are to face of stud unless noted otherwise
3. All exterior wall to truss dimensions are to face of stud unless noted otherwise

**Hatch Legend**

- Vaulted Ceiling
- Padded HVAC
- Drop Beam

Roof Area = 4152.49 sq.ft.  
Ridge Line = 115.05 ft.  
Hip Line = 0 ft.  
Horiz. OH = 238.68 ft.  
Raked OH = 253.95 ft.  
Decking = 143 sheets

All Walls Shown Are Considered Load Bearing

▲ = Indicates Left End of Truss (Reference Engineered Truss Drawing) Do Not Erect Trusses Backwards

1 Truss Placement Plan Scale: 1/4"=1'

**Products**

PlotID	Length	Product	Plies	Net Qty	Fab Type
BM2	7' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
BM4	7' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
BM1	6' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
BM3	6' 0"	1-3/4"x 9-1/4" LVL Kerto-S	2	2	FF
GDH	24' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2	FF

Connector Information				Nail Information	
Sym	Product	Manuf	Qty	Supported Member	Header Truss
	HUS26	USP	3	Varies	16d/3-1/2" 16d/3-1/2"
	THD26-2	USP	6	Varies	16d/3-1/2" 10d/3"

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.  
○ -- Denotes Reaction Greater than 3,000 lbs. Reaction / # of Studs

COUNTY	ADDRESS	MODEL	DATE REV.	DRAWN BY	SALESMAN
Harnett	Lot 25 Liberty Meadows	Roof	2/28/2023	Neil Baggett	Neil Baggett

BUILDER	JOB NAME	PLAN	SEAL DATE	QUOTE #	JOB #
Precision Custom Homes	Lot 25 Liberty Meadows	Mises 1.0 w/CP	N/A	Quote #	J0722-3740

**LOAD CHART FOR JACK STUDS**

BASED ON TABLES 802.2.5.1 & 802.2.5.2

REQ'D STUDS FOR (1) BY TRUSS	REQ'D STUDS FOR (2) BY BEAM	REQ'D STUDS FOR (3) BY HEADER	REQ'D STUDS FOR (4) BY TRUSS
1700	1	2550	1
3400	2	5100	2
5100	3	7650	3
6800	4	10200	4
8500	5	12750	5
10200	6	15300	6
11900	7		
13600	8		
15300	9		