

# HAL OWEN & ASSOCIATES, INC.

SOIL & ENVIRONMENTAL SCIENTISTS

P.O. Box 400, Lillington NC 27546-0400

Phone (910) 893-8743 / Fax (910) 893-3594

www.halowensoil.com

---

14 July 2023

Paul Lyon  
Lyon Builders  
2139 Barbecue Church Road  
Sanford, NC 27332-1414

Reference: Soil Investigation and Septic System Design  
4071 Barbecue Church Road; PIN 9578-18-2948.000  
Lot #2 Lyon Builders Inc Map#2022-545

Dear Mr. Lyon,

A site investigation was conducted on 6 July 2023 for the above referenced property, which is located on the western side of Barbecue Church Road (SR 1209) in the Barbecue Township in Harnett County, North Carolina. The purpose of the investigation was to determine the ability of this lot to support a subsurface sewage waste disposal system and 100% repair area for a typical three-bedroom home. Public water supplies will be utilized for this lot.

All ratings and determinations were made in accordance with "Laws and Rules for Sewage Treatment and Disposal Systems, 15A NCAC 18A .1900". This report represents my professional opinion but does not guarantee or represent permit approval for any lot by the Local Health Department. The permit you receive from the Local Health Department may contain some modifications or amendments to our submitted design. Please carefully review your permit and adhere to all prescribed requirements.

## SEPTIC SYSTEM DESIGN

The proposed single family residential home will contain three bedrooms and generate a design flow of 360 gallons per day (Figure 2). A 1000 gallon (minimum) septic tank is required with an approved effluent filter. The addition of a 1000-gallon pump tank will be necessary to pump effluent uphill to the proposed drainfield.

The initial septic system is proposed as a pump driven system to 300 linear feet of Infiltrator Quick4 Plus standard chamber drainlines utilizing a 25% reduction in total drainline length (Figure 2). A long-term application rate (LTAR) of 0.3 gal/day/ft<sup>2</sup> was used to design the drainfield. A pressure manifold will be used to deliver effluent in parallel distribution to five 60-ft long drainlines. The drainlines shall be installed on contour with maximum trench bottom depths at 15 inches below surface.

The repair septic system is proposed as a pump driven system to 200 linear feet of Infiltrator Quick4 Plus standard chamber drainlines utilizing a 25% reduction in total drainline length (Figure 2). A long-term application rate (LTAR) of 0.45 gal/day/ft<sup>2</sup> was used to design the drainfield. A pressure manifold will be used to deliver effluent in serial distribution to four unequal-ft long drainlines, connected by overflow pipes. The drainlines shall be installed on contour with maximum trench bottom depths at 15 inches below surface.

All regulatory setbacks for a septic system shall be maintained. Drainlines must be installed at least 9 feet apart on center. The septic system (including tanks) must be at least 10 feet from a property line, 5 feet from a home, 50 feet from a surface water, and 100 feet from an individual well (50ft for repair systems).

Potential septic system drainlines have been demonstrated with various colored pin flags that are located on the lot. It is important to protect the areas designated for installation of the septic system or repair area from all land disturbing activities. It is recommended that a staked line or protective fence be placed around the system prior to construction to eliminate any potential damage to the soil or the layout of the system.

#### **SYSTEM MAINTENANCE**

It is recommended that care be taken to preserve the life of your septic system. The septic tank, pump tank, and distribution boxes should be kept accessible for pumping and adjustment. Your septic system should be inspected periodically and the septic tank pumped out every 2 to 5 years by a professional contractor. Practicing water conservation in the home, such as promptly repairing leaky fixtures and running washing machines and dishwashers only when full, will help to avoid overloading the septic system. Also, disposal of oils, fats, and grease into the septic system should be avoided because they could clog drainlines and conveyance pipes. A list of other useful suggestions can be found at <https://content.ces.ncsu.edu/septic-system-owners-guide>

It is required that the nitrification field and repair area be protected from vehicular traffic or other unauthorized access. Vehicular traffic can damage soils, pipes, and valve boxes. Damage to the nitrification field or repair area could result in the septic permit being revoked.

**CONCLUSION**

This report and the attached septic system design information will need to be submitted to the Local Health Department for review and the permitting process. I appreciate the opportunity to provide this service and hope to be allowed to assist you again in the future. If you have any questions or need additional information, please contact me at your convenience.



Sincerely,

A handwritten signature in black ink that reads "Britt Wilson".

Britt Wilson  
Licensed Soil Scientist, LSS# 1351



A handwritten signature in black ink that reads "Hal Owen".

Hal Owen  
Licensed Soil Scientist

Soil Investigation and Septic System Design  
 4071 Barbecue Church Road; PIN 9578-18-2948.000  
 Lot #2 Lyon Builders Inc Map#2022-545  
 14 July 2023

Figure 2. Septic System Layout

**Repair System**

System Type: Type IIIbg Design LTAR 0.45 gal/day/ft<sup>2</sup>  
 Trenches: Quick4 standard chamber (25% reduction)  
 Total Trench Length (ft): 200 Trench Spacing 9 ft on center  
 Trenches installed on contour at 15 inches  
 Maximum Trench Depth of \_\_\_\_\_ inches (measured on high side)  
 Soil Cover 6 inches (max cover shall not exceed 12 in.)

**SEPTIC SYSTEM DESIGN**

Design Wastewater Flow 360 gpd  
 Septic Tank Size (minimum) 1000 gallons  
 Pump Tank Size (minimum) 1000 gallons

**Initial System** \*See Detailed Design Parameters

System Type: Type IIIbg Design LTAR 0.30 gal/day/ft<sup>2</sup>  
 Trenches: Quick4 standard chamber (25% reduction)  
 Total Trench Length (ft): 300 Trench Spacing 9 ft on center  
 Trenches installed on contour at 12 inches  
 Maximum Trench Depth of 15 inches (measured on high side)  
 Soil Cover 6 inches \*Soil Cover Must Extend 5ft Beyond Drainline\*

Potential Drainlines flagged at site on 9-ft centers.

Line #	Color	Relative Elevation (ft)	Drainline Length(ft)	Field Length(ft)
6	W	98.12	60	74
7	R	97.58	60	62
8	Y	97.15	60	62
9	B	96.46	60	71
10	W	95.83	60	74

<b>Septic Tank:</b>	97.57
<b>Pump Tank:</b>	97.40
<b>Reference Elev</b>	<b>100.00</b>

