


Job 72318352REP1	Truss F21	Truss Type Truss	Qty 1	Ply 1	LGI HOMES/ASHLEY PLAN 2ND FLR Job Reference (optional)
---------------------	--------------	---------------------	----------	----------	---

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Kelly Langley

Run: 8.62 S Sep 22 2022 Print: 8.620 S Sep 22 2022 MiTek Industries, Inc. Thu Jul 20 17:18:30

Page: 1

ID:AaXhHNhwTKP_JQOTwB_5VcyQVUb-YaK9xFXYNiEpa1a_CUV7hr4Tmmhcaw4HLrLnqy71N



Repair for loose plate(s) at joints 1, 2 and 26.

Attach 3/4" Plywood or OSB (23/32" APA Rated Sheathing Exposure 1) as shown to each face of truss with 10d (.131" x 3") nails spaced 3" oc in all members.




Plate Offsets (X, Y): [16.0-2.0,Edge], [25.0-1.8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.95	Vert(LL)	-0.44	22-24	>558	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.73	Vert(CT)	-0.60	22-24	>406	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.58	Horz(CT)	0.08	16	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 120 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied, except end verticals.
BOT CHORD 2x4 SP SS(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 6-0-0 oc bracing: 18-19,17-18,16-17.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	
REACTIONS (lb/size) 16=128/0-3-8, (min. 0-1-8), 19=1057/0-3-8, (min. 0-1-8), 27=881/0-3-8, (min. 0-1-8) Max Grav 16=143 (LC 4), 19=1057 (LC 1), 27=881 (LC 10)	

FORCES	(lb) - Max Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2627/0, 3-4=-4161/0, 4-5=-4161/0, 5-6=-4161/0, 6-7=-3994/0, 7-8=-3191/0, 8-9=-3191/0, 9-10=-1853/0
BOT CHORD	26-27=0/1969, 25-26=0/3266, 24-25=0/4161, 23-24=0/4217, 22-23=0/4217, 21-22=0/3710, 20-21=0/2646, 19-20=0/1087
WEBS	4-25=-279/0, 2-27=-2113/0, 2-26=0/857, 3-26=-831/0, 3-25=0/1127, 10-19=-1353/0, 10-20=0/998, 9-20=-1033/0, 9-21=0/710, 7-21=-676/0, 7-22=0/370, 6-22=-329/0, 6-24=-361/397

NOTES (8)

- Unbalanced floor live loads have been considered for this design.
- All plates are MT20 plates unless otherwise indicated.
- All plates are 1.5x3 MT20 unless otherwise indicated.
- This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
- Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- CAUTION, Do not erect truss backwards.
- Top chord over the bearing at 20-4-4 is required to be field cut at time of installation. No plates are to be damaged or disturbed.
- This repair has been prepared based on information and use conditions supplied by client. Designer has made a good faith effort to outline damage and repair conditions as reported by client. When actual field conditions do not approximate those indicated on this drawing, client shall immediately inform the engineer and refrain from applying the repair.



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

