

**NOTES:**

- ALL WINDOWS @ 7'-0" FROM FINISH FLOOR, UNLESS OTHERWISE NOTED
- 2 x 6 EXTERIOR WALLS INSIDE 6X6 POST, UNLESS OTHERWISE NOTED
- 2 x 4 INTERIOR WALLS, UNLESS OTHERWISE NOTED
- WATER HEATER TO SIZED BY CONTRACTOR, VERIFY WITH GENERAL CONTRACTOR
- 200 AMP ELECTRIC SERVICE

**INTERIOR MATERIALS:**

**-INTERIOR FINISH:**

ALL FINISHED DRYWALL WALLS & CEILINGS TO BE SMOOTH, GARAGE TO BE DRYWALLED TO CODE MIN. COLOR WHITE OR GRAY, CONFIRM WITH OWNER

**-TRIM:**

BASE: 1 x 6 MDF, WALNUT  
CASING: 1 x 4 MDF, WALNUT

**-INTERIOR DOORS:**

SPECIFIED BY OWNER

**-INTERIOR DOOR HARDWARE:**

LEVER STYLE, NICKEL FINISH, CONFIRM W/ OWNER

\*\*EXTERIOR DOOR HARDWARE PER EXTERIOR FINISH SCHEDULE

**-CLOSET SHELVING:**

ALL CLOSETS LABELED 'ROD & SHELF' OR 'R & S' TO HAVE SINGLE 12" DEEP WHITE MELAMINE SHELF AND SINGLE HANGING ROD @ 60" FROM FINISH FLOOR

ALL CLOSETS LABELED 'LIN' OR 'SHELF OR SHV.' TO HAVE 12" DEEP WHITE MELAMINE SHELVES @ 2', 4', & 6' FROM FINISH FLOOR

**-CABINETS:**

WHITE UPPER, WOOD FINISH LOWER WALNUT FINISH OR SIMILAR

**-COUNTERTOPS:**

KITCHEN: WHITE, BACKSPASH, STANDARD EDGE, COLOR SELECTED BY OWNER, SINK, CONFIRM WITH OWNER

BATHROOMS: CULTURED QUARTZ W/ INTEGRATED SINK BOWLS & BACKSPASH CONFIRM WITH OWNER

**-APPLIANCES:**

KITCHEN: STANDARD APPLIANCE PACKAGE INCLUDING REFRIGERATOR, RANGE, MICROWAVE, & DISHWASHER, STAINLESS COLOR, CONFIRM W/ OWNER

**LEGEND:**

- S SWITCH
- OUTLET
- ⊙ CEILING OUTLET
- ⊙ GFCI-OUTLET
- CEILING FIXTURE
- ⊙ RECESSED FIXTURE
- ⊙ PORCELAIN FIXTURE
- WALL ○ WALL FIXTURE
- VENT FAN
- ⊙ FAN/LIGHT
- ⊙ MOTION DETECTOR
- ◀ SPOT SPOT LIGHT

**MAIN LEVEL FLOOR PLAN**  
SCALE: 1/4" = 1'-0"

