Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 942 Hollies Pines Rd (SR 1270) ISSUED TO: HHHunt Homes SUBDIVISION EXPANSION Site Improvements required prior to Construction Authorization Issuance: REPAIR Type of Structure: 35'x38' SFD Proposed Wastewater System Type: Pump to 25% reduction Projected Daily Flow: 360 Number of Occupants: 6 Number of bedrooms: 3 Basement Yes May be required based on final location and elevations of facilities Pump Required: XYes ☐ No Type of Water Supply: Community Public Well Distance from well ______feet X Five years Permit valid for: No expiration Permit conditions: Date: 06-20-23 SEE ATTACHED SITE SKETCH The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. PROPERTY LOCATION: 942 Hollies Pines Rd (SR 1270) ISSUED TO: HHHunt Homes Facility Type: 35'x38' SFD Expansion Basement Fixtures? Yes Basement? Yes X No Type of Wastewater System** Pump to 25% reduction (Initial) Wastewater Flow: 360 (See note below, if applicable) Pump to 25% reduction Number of trenches 4 Installation Requirements/Conditions Trench Spacing: 9 Septic Tank Size 1000 gallons Exact length of each trench 75 Feet on Center Soil Cover: 6 ____inches Trenches shall be installed on contour at a Pump Tank Size _____ Maximum Trench Depth of: 18-24 (Maximum soil cover shall not exceed inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ft. TDH vs. _ inches below pipe inches above pipe Aggregate Depth: inches total Conditions: WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Date: 06-20-23 Authorized State Agent: _ Construction Authorization Expiration Date: 06-20-28

Harnett County Department of Public Health Site Sketch

Property Location: 942 Hollie Issued To: HHHunt Homes	Subdivision	Lot # 2
Authorized State Agent:	Male a REITS	Date: <u>06-20-23</u>
The second second	N23"0'20"E	
	100.26	
	ΔU_{\perp}	
	2 / / / / / / / / / / / / / / / / / /	
	Land St. Taker Contraction of the Contraction of th	
	SE TBACKS	
	Y.0/ / A	
	SEPTIC AREA	
	175.00	
	See. 23.0	
	S66.23.01.E	
	1	
	86 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
	35 438	
	7' 8 3B-	
	36	
	51.0' 518.3 6 11.2'	
	36.0'	
	100.22	
	523°21'08"W	
	- Hollies Pines Rd ->	
	(-) / 10/1	

This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.