

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Rolling Springs

LOT 97

INITIAL SYSTEM: <sup>Pump</sup> APPROVED 25% REDUCTION

REPAIR <sup>Pump</sup> Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION BC IRON Mid 126

NO. BEDROOMS: 4

LTAR 0.5 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
1	R	93.59	45
2	Y	92.33	70
3	B	91.41	95
4a	Pu	90.91	40
			240
4b	Pu	90.91	45
5	W	90.17	95
6	R	89.33	55
7	Y	89.50	55
			240

BY B.C. Raynor

DATE 11/11/2022

TYPICAL PROFILE

- 0-9 LS vfri gran
- 9-16 scl firm SBK
- 16-48 sloam fri gran

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.  
DESIGNS DO NOT GURANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email mike@southeasternsoil.com

