

Job 71030131	Truss F200	Truss Type Truss	Qty 7	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:39

Page: 1

ID:Jv3BhEMefC3hhjpA8mAc6CyyFH-PFDBgBKQGthR1gnKYyYVtskyfU5oh9pJstLyl?yrYIU




Plate Offsets (X, Y): [11:0-1-8,Edge], [13:0-2-0,Edge], [18:0-1-8,Edge], [19:0-1-8,Edge], [21:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.84	Vert(LL)	-0.24	19-20	>692	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.76	Vert(CT)	-0.33	19-20	>503	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.40	Horz(CT)	0.03	13	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 109 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.1(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS (lb/size) 13=329/0-3-8, (min. 0-1-8), 17=1067/0-3-8, (min. 0-1-8), 21=565/0-3-8, (min. 0-1-8)
 Max Grav 13=348 (LC 7), 17=1067 (LC 1), 21=582 (LC 10)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1566/0, 3-4=-1696/0, 4-5=-1696/0, 5-6=-1696/0, 6-7=0/477, 7-8=0/477, 8-9=0/477, 9-10=-663/0, 10-11=-663/0
 BOT CHORD 20-21=0/1231, 19-20=0/1824, 18-19=0/1696, 17-18=0/1108, 16-17=0/513, 15-16=0/513, 14-15=0/663, 13-14=0/663
 WEBS 8-17=-258/0, 9-17=-837/0, 11-13=-705/0, 9-15=0/310, 5-18=-391/0, 2-21=-1319/0, 2-20=0/435, 3-20=-336/0, 3-19=-291/99, 6-17=-1397/0, 6-18=0/849

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



Job 71030131	Truss F201	Truss Type Truss	Qty 1	Ply 1	PBS/PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFPI Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:39

Page: 1

ID:FIAY5vNvBpJPw1zYFBC4BdyymFF-PfIDBgBKQGthR1gnKYoyVtskxRU1Vh7cJstLyl?yrYIU




Plate Offsets (X, Y): [14:0-2-0,Edge], [22:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.92	Vert(LL)	-0.26	22-23	>825	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.97	Vert(CT)	-0.36	22-23	>597	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	0.06	17	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH								Weight: 112 lb FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS	(lb/size)
	14=-72/0-3-8, (min. 0-1-8), 17=1313/0-3-8, (min. 0-1-8), 24=721/0-3-8, (min. 0-1-8)
	Max Uplift 14=-207 (LC 3)
	Max Grav 14=116 (LC 4), 17=1313 (LC 1), 24=724 (LC 10)

FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD	2-3=-2069/0, 3-4=-2870/0, 4-5=-2870/0, 5-6=-2870/0, 6-7=-2382/0, 7-8=-2382/0, 8-9=-1435/0, 9-10=0/1128, 10-11=0/1124, 11-12=-41/493
BOT CHORD	23-24=0/1582, 22-23=0/2506, 21-22=0/2870, 20-21=0/2737, 19-20=0/2031, 18-19=0/799, 17-18=0/799, 16-17=-493/41, 15-16=-493/41, 14-15=-493/41
WEBS	11-17=-893/0, 12-14=-46/615, 5-21=-356/33, 2-24=-1696/0, 2-23=0/634, 3-23=-569/0, 3-22=0/599, 9-17=-1995/0, 9-19=0/836, 8-19=-786/0, 8-20=0/463, 6-20=-472/0, 6-21=-84/555

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 207 lb uplift at joint 14.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard




Job 71030131	Truss F202	Truss Type Truss	Qty 5	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:40

Page: 1

ID:FIAY5vNvBpJPw1zYFBC4BdyymFF-trnZuXK21BpIfqMW6W3kQ3H7OuQTQaOT5X4VgRyRyIT



Scale = 1:41.9

Plate Offsets (X, Y):	[15:0-1-8,Edge]											
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.77	Vert(LL)	-0.28	14-15	>761	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.80	Vert(CT)	-0.39	14-15	>554	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.06	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 89 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-5-7 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	11=788/0-3-8, (min. 0-1-8), 18=788/0-3-8, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-2300/0, 3-4=-3396/0, 4-5=-3396/0, 5-6=-3396/0, 6-7=-3103/0, 7-8=-3103/0, 8-9=-2297/0
BOT CHORD		17-18=0/1742, 16-17=0/2818, 15-16=0/2818, 14-15=0/3396, 13-14=0/3363, 12-13=0/2820, 11-12=0/1740
WEBS		5-14=-275/124, 2-18=-1868/0, 2-17=0/726, 3-17=-675/0, 3-15=0/811, 9-11=-1867/0, 9-12=0/725, 8-12=-680/0, 8-13=0/369, 6-13=-396/0, 6-14=-252/441

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




Job	Truss	Truss Type	Qty	Ply	PBS\PLAN #5 CRAFTSMAN 2F
71030131	F203	Truss	2	1	Job Reference (optional)

UFPP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:40

Page: 1

ID:jUkKJFOXY7RGYAYlpukJryymFE-trnZuXK21BpIfqMW6W3kQ3HA4uRCQaXT5X4VqRyrYIT



Scale = 1:41.5

Plate Offsets (X, Y): [11:0-2-0,Edge], [16:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.60	Vert(LL)	-0.26	15-16	>824	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.75	Vert(CT)	-0.35	15-16	>600	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.50	Horz(CT)	0.06	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 88 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS (lb/size) 11=775/ Mechanical, (min. 0-1-8), 18=775/0-3-8, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2254/0, 3-4=-3293/0, 4-5=-3293/0, 5-6=-3293/0, 6-7=-2700/0, 7-8=-1649/0, 8-9=-1649/0
BOT CHORD 17-18=0/1710, 16-17=0/2756, 15-16=0/3293, 14-15=0/3072, 13-14=0/3072, 12-13=0/2302, 11-12=0/971
WEBS 2-18=-1834/0, 2-17=0/708, 3-17=-654/0, 3-16=0/784, 9-11=-1216/0, 9-12=0/883, 7-12=-850/0, 7-13=0/519, 6-13=-484/0, 6-15=-74/551

- NOTES
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss F204	Truss Type Truss	Qty 3	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:40

Page: 1

ID:jUkKJFOXy7RGYAYlpukJjryymFE-trnZuXK21BplfqMW6W3kQ3HAgU00QahT5X4VqRyrYIT



Scale = 1:41

Plate Offsets (X, Y):	[13:0-1-8,Edge], [14:0-1-8,Edge]											
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.63	Vert(LL)	-0.28	14-15	>752	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.95	Vert(CT)	-0.38	14-15	>556	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.49	Horz(CT)	0.07	10	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 85 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 2-2-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	10=763/ Mechanical, (min. 0-1-8), 16=763/ Mechanical, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-2207/0, 3-4=-3193/0, 4-5=-3193/0, 5-6=-3193/0, 6-7=-2207/0, 7-8=-2207/0
BOT CHORD		15-16=0/1678, 14-15=0/2694, 13-14=0/3193, 12-13=0/2694, 11-12=0/2694, 10-11=0/1678
WEBS		2-16=-1799/0, 2-15=0/689, 3-15=-634/0, 3-14=0/763, 8-10=-1799/0, 8-11=0/689, 6-11=-634/0, 6-13=0/763

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are MT20 plates unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




Job 71030131	Truss F205	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:40

Page: 1

ID:jUkKJFOxy7RGYAYlpukJjryymFE-trnZuXK21BpIfqMW6W3kQ3HAWuP6QaMT5X4VqRyrYIT



Scale = 1:39

Plate Offsets (X, Y): [14:0-1-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.61	Vert(LL)	-0.22	14-15	>869	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.31	14-15	>624	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.45	Horz(CT)	0.05	10	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 80 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS (lb/size) 10=703/0-3-3, (min. 0-1-8), 16=703/ Mechanical, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1995/0, 3-4=-2710/0, 4-5=-2710/0, 5-6=-2710/0, 6-7=-2710/0, 7-8=-1972/0
 BOT CHORD 15-16=0/1531, 14-15=0/2407, 13-14=0/2710, 12-13=0/2392, 11-12=0/2392, 10-11=0/1530
 WEBS 2-16=-1642/0, 2-15=0/604, 3-15=-537/0, 3-14=0/555, 8-10=-1641/0, 8-11=0/576, 7-11=-546/0, 7-13=0/578

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss F206	Truss Type Truss	Qty 6	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:40

Page: 1

ID: jUkKJFOxy7RGYAYlpukJjryymFE-trnZuXK21BplfqMW6W3Q3H9TuP5QbST5X4VqRyrYIT



Scale = 1:38.7

Plate Offsets (X, Y):		[9:Edge,0-1-8], [12:0-1-8,Edge], [14:Edge,0-1-8]										
Loading	(psf)	Spacing	1-7-3	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	0.64	Vert(LL)	-0.22	12-13	>873	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.31	12-13	>626	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.44	Horz(CT)	0.05	9	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 79 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	9=695/0-3-8, (min. 0-1-8), 14=695/ Mechanical, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-1964/0, 3-4=-2642/0, 4-5=-2642/0, 5-6=-2642/0, 6-7=-1939/0
BOT CHORD		13-14=0/1510, 12-13=0/2366, 11-12=0/2642, 10-11=0/2351, 9-10=0/1508
WEBS		2-14=-1619/0, 2-13=0/591, 3-13=-523/0, 3-12=0/528, 7-9=-1618/0, 7-10=0/561, 6-10=-537/0, 6-11=0/559

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Bearing at joint(s) 9 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



Job 71030131	Truss F207	Truss Type Truss	Qty 4	Ply 1	PBS/PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:41

Page: 1

ID:JUKKJFOxy7RGYAYIpuKJjrymFE-L1Lx5tLgoUx9HzjgDbzyHqLrIpD93_cJBq3MtyrYiS




Plate Offsets (X, Y): [8:0-1-8,Edge], [9:0-1-8,Edge], [11:0-1-8,Edge], [18:0-1-8,Edge], [19:0-1-8,Edge], [20:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.60	Vert(LL)	-0.14	19-20	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.63	Vert(CT)	-0.22	19-20	>670	360		
BCLL	0.0	Rep Stress Incr	NO	WB	0.36	Horz(CT)	0.02	16	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 98 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS (lb/size) 13=1069/0-3-8, (min. 0-1-8), 16=898/0-3-8, (min. 0-1-8), 20=489/0-3-8, (min. 0-1-8)
 Max Grav 13=1127 (LC 4), 16=899 (LC 3), 20=497 (LC 14)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1360/0, 3-4=-1360/0, 4-5=-1360/0, 5-6=0/688, 6-7=0/688, 7-8=0/688, 8-9=-111/393, 9-10=0/438, 10-11=0/435
 BOT CHORD 19-20=0/1006, 18-19=0/1360, 17-18=0/711, 16-17=0/711, 15-16=-393/111, 14-15=-393/111, 13-14=-393/111
 WEBS 2-20=-1077/0, 2-19=0/384, 5-16=-1274/0, 5-18=0/757, 9-13=-548/0, 8-16=-554/0, 11-13=-870/0

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Magnitude of user added load(s) on this truss have been applied uniformly across all gravity load cases with no adjustments.
 - 5) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

- 1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (lb/ft)
 Vert: 12-20=-8, 1-11=-80
 Concentrated Loads (lb)
 Vert: 11=-768



Job 71030131	Truss F208	Truss Type Truss	Qty 7	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:41

Page: 1

ID:Jv3BhEMeFC3hhjpA8mAc6CymFH-L1Lx5tLgoUx9HzxjgDbzyHqMplp293GcJbQ3MtyrYIS




Plate Offsets (X, Y): [8:0-1-8,Edge], [10:0-1-8,Edge], [16:0-1-8,Edge], [17:0-1-8,Edge], [18:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.54	Vert(LL)	-0.15	17-18	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.58	Vert(CT)	-0.23	17-18	>658	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.34	Horz(CT)	0.02	14	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 92 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS (lb/size) 10=179/0-3-0, (min. 0-1-8), 14=945/0-3-8, (min. 0-1-8), 18=496/0-3-8, (min. 0-1-8)
 Max Grav 10=224 (LC 7), 14=945 (LC 1), 18=510 (LC 10)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1438/0, 3-4=-1438/0, 4-5=-1438/0, 5-6=0/548, 6-7=0/548, 7-8=0/548, 8-9=-265/54, 9-10=-266/54
 BOT CHORD 17-18=0/1039, 16-17=0/1438, 15-16=0/836, 14-15=0/836, 13-14=-54/265, 12-13=-54/265
 WEBS 2-18=-1113/0, 2-17=0/431, 5-14=-1243/0, 5-16=0/719, 8-14=-702/0, 10-12=-66/325

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 10.
 - 3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 4) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - 5) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
 - 6) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.



Job 71030131	Truss F209	Truss Type Truss	Qty 2	Ply 1	PBS/PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:41

Page: 1

ID:n6dZuZMHQWBYItOMhUhreQyymFG-L1Lx5tLgoUx9HzjgDbzyHqPolv_95LcJBq3MtyrYIS




Plate Offsets (X, Y): [2:0-1-8,Edge], [5:0-1-8,Edge], [7:0-1-8,Edge], [9:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.35	Vert(LL)	-0.02	8-9	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.20	Vert(CT)	-0.03	8-9	>999	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.21	Horz(CT)	0.00	5	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 35 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS (lb/size) 5=262/0-3-0, (min. 0-1-8), 9=257/ Mechanical, (min. 0-1-8)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-412/0, 3-4=-412/0, 4-5=-416/0
 BOT CHORD 8-9=0/412, 7-8=0/412
 WEBS 5-7=0/440, 2-9=-437/0

- NOTES
- Unbalanced floor live loads have been considered for this design.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
 - CAUTION, Do not erect truss backwards.
- LOAD CASE(S) Standard




Job 71030131	Truss F210	Truss Type Truss	Qty 2	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:42

Page: 1

ID:FlAy5vNvBpJPw1zYFBC4BdyymFF-L1Lx5tLgoUx9HzxigDbzyHqPflv995ZcJBq3MtyrYIS



Scale = 1:45.8

Plate Offsets (X, Y): [2:0-1-8,Edge], [6:0-1-8,Edge], [14:0-2-0,Edge], [24:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.36	Vert(LL)	-0.04	17-18	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.25	Vert(CT)	-0.06	17-18	>999	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.20	Horz(CT)	0.01	14	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 105 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS
 All bearings 0-3-8, except 24= Mechanical
 (lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 14
 Max Grav All reactions 250 (lb) or less at joint(s) 14 except 17=631 (LC 14), 21=746 (LC 16), 24=328 (LC 14)

FORCES
 (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-599/0, 3-4=-599/0, 4-5=0/256, 5-6=0/256, 6-7=-558/0, 7-8=-558/0
 BOT CHORD 23-24=0/599, 22-23=0/599, 21-22=0/551, 20-21=0/558, 19-20=0/558, 18-19=0/558, 17-18=0/476
 WEBS 4-21=-690/0, 2-24=-637/0, 8-17=-692/0, 6-21=-716/0, 11-17=-356/0

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 14.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard



Job 71030131	Truss F211	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:42

Page: 1

ID:FlAy5vNvBpJPw1zYFBC4BdyymFF-qEvJJDmJZo30u7VvEx6CVUMaKi90uXxlYrZcuKyrYr




Plate Offsets (X, Y): [7:0-2-0,Edge], [8:0-1-8,Edge], [9:0-1-8,Edge], [10:0-2-0,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.36	Vert(LL)	-0.12	9-10	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.53	Vert(CT)	-0.18	9-10	>799	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.32	Horz(CT)	0.02	7	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 60 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	7=525/0-3-3, (min. 0-1-8), 10=525/0-3-8, (min. 0-1-8)
FORCES	(lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.	
TOP CHORD		2-3=-1537/0, 3-4=-1537/0, 4-5=-1537/0
BOT CHORD		9-10=0/1077, 8-9=0/1537, 7-8=0/1077
WEBS		5-7=-1153/0, 2-10=-1153/0, 5-8=0/571, 2-9=0/571

- NOTES**
- 1) Unbalanced floor live loads have been considered for this design.
 - 2) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 3) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




Job 71030131	Truss F212	Truss Type Truss	Qty 9	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:42

Page: 1

ID:gts4kxPnUkhznUi7wJmnpGyymFC-qEvJJDMJZ030u7VvEx6CVUMV_i2LuSGIYrZcuKyrYiR



Scale = 1:43.4

Plate Offsets (X, Y): [16:0-1-8,Edge], [20:0-3-8,Edge]

Loading	(psf)	Spacing	1-7-3	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.70	Vert(LL)	-0.49	15-16	>513	480	MT18HS	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.96	Vert(CT)	-0.68	15-16	>371	360	MT20	244/190
BCLL	0.0	Rep Stress Incr	YES	WB	0.61	Horz(CT)	0.10	12	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH								
											Weight: 104 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.1(flat)	TOP CHORD	Structural wood sheathing directly applied or 5-0-4 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.1(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS	2x4 SP No.3(flat)		2-2-0 oc bracing: 16-17,15-16.
OTHERS	2x4 SP No.3(flat)		

REACTIONS	(lb/size)	12=919/0-3-8, (min. 0-1-8), 20=914/0-3-8, (min. 0-1-8)
FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.		
TOP CHORD		2-3=-2818/0, 3-4=-3912/0, 4-5=-4622/0, 5-6=-4622/0, 6-7=-4622/0, 7-8=-4622/0, 8-9=-3920/0, 9-10=-2777/0
BOT CHORD		19-20=0/2108, 18-19=0/3489, 17-18=0/4334, 16-17=0/4622, 15-16=0/4335, 14-15=0/3460, 13-14=0/3460, 12-13=0/2067
WEBS		5-17=-286/0, 2-20=-2249/0, 2-19=0/924, 3-19=-873/0, 3-18=0/551, 4-18=-550/0, 4-17=-81/676, 10-12=-2218/0, 10-13=0/924, 9-13=-889/0, 9-15=0/598, 8-15=-541/0, 8-16=-128/688

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are MT20 plates unless otherwise indicated.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Required 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
- LOAD CASE(S)** Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss F213	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:42

Page: 1

ID:oSFIkeObPdvU?xOiAqjnblYymDx-qEvJdJMJz030u7VvEx6CVUMQhi43uU0lYrZcuKyrYIR



Scale = 1:52.9

Plate Offsets (X, Y):	[5:0-3-0,Edge], [11:0-1-8,Edge], [18:0-2-0,Edge], [27:0-1-8,Edge], [28:0-1-8,Edge]
-----------------------	--

Loading	(psf)	Spacing	1-7-3	CSI	DEFLL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.98	Vert(LL)	-0.13	28-29	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.85	Vert(CT)	-0.20	28-29	>760	360		
BCLL	0.0	Rep Stress Incr	NO	WB	0.50	Horz(CT)	0.03	21	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 134 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 3-11-15 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS All bearings 0-3-8.
 (lb) - Max Uplift All uplift 100 (lb) or less at joint(s) 18
 Max Grav All reactions 250 (lb) or less at joint(s) 18 except 21=610 (LC 4), 24=1185 (LC 16), 29=737 (LC 14)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 3-32=-2380/0, 4-32=-2380/0, 4-5=-2380/0, 5-6=-2380/0, 6-7=-2380/0, 7-8=-1425/0, 8-9=0/859, 9-10=0/859, 10-11=0/859, 11-12=-348/315, 12-13=-348/315, 13-14=0/372, 14-15=0/367
 BOT CHORD 28-29=0/1740, 27-28=0/2380, 26-27=0/1882, 25-26=0/955, 24-25=0/955, 23-24=-315/348, 22-23=-315/348, 21-22=-213/338
 WEBS 8-24=-1727/0, 3-29=-1853/0, 8-26=0/648, 3-28=0/734, 7-26=-637/0, 7-27=0/784, 4-28=-258/0, 5-27=-409/0, 13-21=-609/0, 11-24=-926/0, 15-21=-433/0

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 1.5x3 MT20 unless otherwise indicated.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 18.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.
 - Use USP MSH422 (With 10d nails into Girder & 6-10d nails into Truss) or equivalent at 4-7-4 from the left end to connect truss(es) to front face of top chord.
 - Fill all nail holes where hanger is in contact with lumber.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
 Uniform Loads (lb/ft)
 Vert: 18-29=-8, 1-17=-80
 Concentrated Loads (lb)
 Vert: 32=-315 (F)



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss F214	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:43

Page: 1

ID:GrEoEXnEBGba?Fa5FKp2ZoyymEj-IQThWZNxK6BtWH45nedR2ivnO6b1d19vnVJ9RmyrYIQ



Scale = 1:43.1

Plate Offsets (X, Y): [4:0-3-0,Edge], [5:0-2-0,Edge], [8:0-2-0,Edge]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.21	Vert(LL)	0.00	7	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.16	Vert(CT)	-0.01	7	>999	360		
BCLL	0.0	Rep Stress Incr	NO	WB	0.13	Horz(CT)	0.00	5	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-SH							Weight: 28 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 3-10-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS (lb/size) 5=523/0-3-8, (min. 0-1-8), 8=374/ Mechanical, (min. 0-1-8)
Max Grav 5=567 (LC 4), 8=395 (LC 3)

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 5-10=-268/0, 4-10=-268/0, 2-3=-443/0
BOT CHORD 7-8=0/443, 6-7=0/443, 5-6=0/443
WEBS 3-5=-520/0, 2-8=-534/0

- NOTES**
- Unbalanced floor live loads have been considered for this design.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - Use USP MSH422 (With 10d nails into Girder & 6-10d nails into Truss) or equivalent spaced at 1-7-3 oc max. starting at 1-7-12 from the left end to 3-2-15 to connect truss(es) to back face of top chord.
 - Fill all nail holes where hanger is in contact with lumber.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

- LOAD CASE(S)** Standard
- Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (lb/ft)
Vert: 5-8=-10, 1-4=-100
Concentrated Loads (lb)
Vert: 2=-247 (B), 11=-267 (B)



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss L200	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:43

Page: 1

ID:ChIWbP9jRZ79K7xNcFYG2yymFD-IQThWZNxK6BtWH45nedR2ivpY6dRd2evnVJ9RmyrYiQ



Scale = 1:48.5

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.01	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	20	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 94 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS All bearings 22-8-0.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss L202	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:43

Page: 1

ID:ChliWbP9jRZ79K7xNcFYG2yymFD-IQThWZNXK6BtWH45nedR2ivpT6dKd2dvnVJ9RmyrYiQ



Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.02	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	19	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 87 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat) *Except* 19-37:2x4 SP No.2(flat)	

REACTIONS All bearings 20-9-8.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard




Job 71030131	Truss L203	Truss Type Truss	Qty 2	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:43

Page: 1

ID:ChliWbP9jRZ79K7xNcFYG2yymFD-IQThWZNXK6BtWH45nedR2ivp36dDd2avnVJ9RmyrYiQ



Scale = 1:33

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.02	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	11	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 52 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS All bearings 12-4-0.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 11, 12, 13, 14, 15, 16, 17, 18, 19, 20

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss L204	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:43

Page: 1

ID:ChliWbP9jRZ79K7xNcFYG2yymFD-IQThWZNXk6BtWH45nedR2ivpT6dLd2dvnVJ9RmyrYiQ



Scale = 1:25.9

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	40.0	Plate Grip DOL	1.00	TC	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	Horiz(TL)	0.00	8	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R						Weight: 34 lb	FT = 20%F, 11%E

LUMBER		BRACING	
TOP CHORD	2x4 SP No.2(flat)	TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	2x4 SP No.2(flat)	BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	2x4 SP No.3(flat)		
OTHERS	2x4 SP No.3(flat)		

REACTIONS All bearings 7-7-0.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 8, 9, 10, 11, 12, 13, 14

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- 1) All plates are 1.5x3 MT20 unless otherwise indicated.
 - 2) Gable requires continuous bottom chord bearing.
 - 3) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 4) Gable studs spaced at 1-4-0 oc.
 - 5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - 6) Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.




Job 71030131	Truss L206	Truss Type Truss	Qty 1	Ply 1	PBS\PLAN #5 CRAFTSMAN 2F Job Reference (optional)
-----------------	---------------	---------------------	----------	----------	--

UFP Mid Atlantic LLC, 5631 S. NC 62, Burlington, NC, Micah Clayton

Run: 8.43 S Jan 4 2021 Print: 8.430 S Jan 4 2021 MiTek Industries, Inc. Tue Aug 03 13:54:44

Page: 1

ID:ChliWbP9jRZ79K7xNcFYG2yymFD-mc04kvOZ5PJk8RfILM8gavS_CVzaMv12092jzCyrYIP



Scale = 1:38.7

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP	
TCLL	40.0	Plate Grip DOL	1.00	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.02	Vert(TL)	n/a	-	n/a	999		
BCLL	0.0	Rep Stress Incr	YES	WB	0.03	Horiz(TL)	0.00	14	n/a	n/a		
BCDL	5.0	Code	IRC2015/TPI2014	Matrix-R							Weight: 68 lb	FT = 20%F, 11%E

LUMBER	BRACING
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.2(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SP No.3(flat)	
OTHERS 2x4 SP No.3(flat)	

REACTIONS All bearings 16-2-0.
(lb) - Max Grav All reactions 250 (lb) or less at joint(s) 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26

FORCES (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES**
- All plates are 1.5x3 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - Gable studs spaced at 1-4-0 oc.
 - Bearing at joint(s) 26, 14 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
 - This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-00-00 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard



This design is based upon parameters shown, and is for an individual building component to be installed and loaded vertically. Applicability of design parameters and proper incorporation of component is responsibility of the Building Designer. Building Designer shall verify all design information on this sheet for conformance with conditions and requirements of the specific building and governing codes and ordinances. Building Designer accepts responsibility for the correctness or accuracy of the design information as it may relate to a specific building. Certification is valid only when truss is fabricated by a UFPI plant. Bracing shown is for lateral support of truss members only and does not replace erection and permanent bracing. Refer to Building Component Safety Information (BCSI) for general guidance regarding storage, erection and bracing available from SBCA and Truss Plate Institute.

