



TYPICAL GARAGE FLOOR:  
 4" CONCRETE SLAB c/w  
 MESH REINFORCEMENT  
 POLY VAPOR BARRIER  
 COMPACTED GRANULAR FILL  
 SLOPE TO DOORS

TYPICAL PORCH FLOOR:  
 4" CONCRETE SLAB c/w  
 MESH REINFORCEMENT  
 POLY VAPOR BARRIER  
 COMPACTED GRANULAR FILL

Raised Wooden Deck  
 As Specified

3 Ply Beam  
 as Specified

2"x10" Floor Joist  
 16" O.C.

8" Block on 32" x 16" Footer

**FOUNDATION PLAN**  
 SCALE: 1/4" = 1'-0"

SQUARE FOOTAGE	
HEATED 1st Fl.	2414 S.F.
HEATED BONUS	254 S.F.
HEATED TOTAL	2668 S.F.
UNHEATED 1st Fl.	1835 S.F.
UNHEATED BONUS	216 S.F.
UNHEATED TOTAL	2111 S.F.
TOTAL	4779 S.F.