# HAL OWEN & ASSOCIATES, INC.

## SOIL & ENVIRONMENTAL SCIENTISTS

P.O. Box 400, Lillington NC 27546-0400 Phone (910) 893-8743 / Fax (910) 893-3594 www.halowensoil.com

6 September 2023

Asset Development 3900 Dunn Road Roseboro, NC

Reference: Soil Investigation and Septic System Design

165 Cotton Fields Lane, Fuquay Varina, Harnett Co., NC PIN 0643-36-0736.000 Lot 25 Cotton Farms SD

Dear Asset Development,

A site investigation was conducted on 21 August 2023 for the above referenced property, which is located on the northern side of Cotton Fields Lane in Harnett County, North Carolina. The purpose of the investigation was to determine the ability of this lot to support a subsurface sewage waste disposal system and 100% repair area for a typical three-bedroom home. Public water supplies will be utilized for this lot.

All ratings and determinations were made in accordance with "Laws and Rules for Sewage Treatment and Disposal Systems, 15A NCAC 18A .1900". This report represents my professional opinion but does not guarantee or represent permit approval for any lot by the Local Health Department. The permit you receive from the Local Health Department may contain some modifications or amendments to our submitted design. Please carefully review your permit and adhere to all prescribed requirements.

### **SOIL INVESTIGATION**

The soils were evaluated under moist soil conditions through the advancing of auger borings. This evaluation included observations of topography and landscape position, soil morphology (texture, structure, clay mineralogy, organics), soil wetness, soil depth, and restrictive horizons.

Soils in the proposed system area were observed to rate as provisionally suitable for subsurface sewage waste disposal systems (Figure 1). The subsoils were observed to be firm clays and extended to greater than 48 inches below ground surface. No evidence of a soil wetness condition was observed within 48 inches below surface or deeper. These soils appear adequate to support long-term acceptance rates of 0.3 gal/day/ft<sup>2</sup> for chamber drainlines.

#### SEPTIC SYSTEM DESIGN

A 1000 gallon (at minimum) septic tank and an approved septic effluent filter is required. A pump tank (1000 gallon at minimum) is required to lift effluent to the nitrification field.

The initial septic system is proposed as a pump driven system to 300 linear feet of Infiltrator Quick4 Plus standard chamber drainlines utilizing a 25% reduction in total drainline length (Figure 2). A long-term application rate (LTAR) of 0.3 gal/day/ft² was used to design the nitrification field. A pressure manifold will be used to deliver effluent to the drainfield. The last two drainlines are composed of two 28-foot-long runs, on different contours, connected by overflow pipes. The drainlines shall be installed on contour at 24 inches below surface (low side). The maximum trench bottom depth on the high side should not exceed 30 inches.

The repair septic system is proposed as a pump driven system to 300 linear feet of Infiltrator Quick4 Plus standard chamber drainlines utilizing a 25% reduction in total drainline length (Figure 2). A LTAR of 0.3 gal/day/ft<sup>2</sup> was used to design the nitrification field. Effluent will be serially distributed to five unequal length drainlines, connected by overflow pipes. The drainlines shall be installed on contour at 24 inches below surface (low side). The maximum trench bottom depth on the high side should not exceed 30 inches.

It is important that you do not disturb the septic areas during site construction. A staked line or protective fence should be placed around the system areas prior to construction to eliminate any potential damage to the soil or the layout of the system. Septic areas should not be used for staging construction materials or subjected to vehicular traffic. Do not cut, grade, fill, install utilities, or otherwise alter the designated septic areas.

#### **CONCLUSION**

This report and the attached septic system design information will need to be submitted to the Local Health Department for review and the permitting process. I appreciate the opportunity to provide this service and hope to be allowed to assist you again in the future. If you have any questions or need additional information, please contact me at your convenience.


Sincerely,


Britt Wilson


Licensed Soil Scientist

V Wess

Figure 1. Soil Map showing Septic Suitability







DESI	GN FLOW	360	gal/day	5	SOIL LTAR:	0.30	gpd/ft <sup>2</sup>		
TAN	KS (minimu	m) S	Septic Tank:	1000	gallons	oump Tank:	1000	gallons	
TRE	NCHES Dra	ainline Type:	Quick4 stan	dard chamb	er (25% red	uction)			
		ench depth:					3	ft	
		ngth Factor:						ft	
Absorption Area:			900	ft <sup>2</sup> Minimum Linear Length:			300 ft		
PRESSURE MANIFOLD DESIGN CRITERIA									
MANIFOLD # Taps 4 Tap Configuration: 6in. spacing, 1 side of manifold									
							Elevation: 96.11		
TAP	CHART								
Тар	Line		Relative	Run Length	Drainline	Tap Size/	Flow/tap	LTAR	
#	Number	Color	Elevation	(ft)	Length(ft)	Schedule	(gpm)	(gpd/ft <sup>2</sup> )	
1	6	В	95.11	68	68	1/2"sch 40	7.11	0.410	
2	7	Υ	94.02	120	120	3/4"sch 40	12.50	0.409	
3	8	W	91.66	28	56	1/2"sch 80	5.48	0.384	
	9	R	90.43	28					
4	10	В	89.03	28	56	1/2"sch 80	5.48	0.384	
	11	Y	87.54	28					
Total Drainline: 300 Total Flow: 30.57									
						Target LTAR*:	0.40		
PUMP CALCULATIONS						LTAR + 5%:	0.420		
Total Flow: 30.57 gpm Design Head (ft): 2.0									
Daily Pump Run Time: 11.78 min (Daily Flow/Total Flow)									
Dose Volume: 146.93 gallons with Pipe Volume at 75 % (65.3gal/100ft pipe)									
Dose Pump Run 4.81 minutes (Dose Vol/Total Flow)									
* Tar	get LTAR: C	convert LTAR	tor non-cor	nventional dr	ainline types	by dividing	by trench ler	ngth factor	
MAN	NIFOLD DI	IAGRAM:							
Tap #	1	2	3	4					
	4" SCH 80 PVC Manifold								
Тар	1/2"sch 40	3/4"sch 40	1/2"sch 80	1/2"sch 80					
flow (	7.11	12.50	5.48	5.48					
Line Lengi	68 th (ft)	120	56	56					