



- \*Keep tanks and drain lines 10' from property lines.
- \*Not a survey.
- \*Not a guarantee of a septic permit.
- \*Keep supply lines >5' from property lines.
- \*Some lines are flagged longer in the field than lengths indicate.
- \*No grading septic area.

<p>System: Gravity to Serial Dist.          Lines: 4-6, (355')          Accepted Status System          0.275 Soil LTAR          24" Trench Bottom</p>
<p>Repair: Gravity to Serial Dist.          Lines: 1-3,7 (350')          Accepted Status System          0.275 Soil LTAR          24" Trench Bottom</p>

System:
Repair:

GRAPHIC SCALE  
1" = 50'



Central Carolina Soil Consulting, PLLC  
 1900 South Main Street, Suite 110  
 Wake Forest, North Carolina 27587  
 Phone (919)569-6704 Fax (919)569-6703

3-Bedroom Septic Layout  
 Lot 174, Birchwood Subdivision  
 Harnett County, North Carolina

Job# : 3753
Drawn By : LW
Date : 05/9/2023
Revision: