




ALL NON-MASONRY RETURNS TO BE HORIZONTAL SIDING

SEE SHEET D3 OF SDH TYPICAL DETAILS FOR SOFFIT DETAILS PER SOFFIT MATERIAL

# HARRINGTON PLACE LOT 5



FRONT ELEVATION "C"

SCALE: 3/16"=1'-0"

| BY | REVISION | DATE |
|----|----------|------|
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |




ELEVATIONS  
FRONT ELEVATION  
COLEMAN

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.


|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A1.1  |         |

# HARRINGTON PLACE LOT 5




LEFT ELEVATION "C"

SCALE: 1/8" = 1'-0"



RIGHT ELEVATION "C"

SCALE: 1/8" = 1'-0"



REAR ELEVATION "C"

SCALE: 1/8" = 1'-0"

| BY | REVISION | DATE |
|----|----------|------|
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |
| #  | #        | #    |




ELEVATIONS  
SIDES AND REAR  
COLEMAN

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A2.1  |         |

# HARRINGTON PLACE LOT 5



\*RADON VENT PROVIDED  
PER LOCAL CODE

REFER TO DETAIL 3/D1  
FOR BRICK LEDGE  
DETAIL WHEN BRICK  
VENEER IS CHOSEN

| DATE | REVISION | BY |
|------|----------|----|
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |



FOUNDATION PLAN  
SLAB PLAN  
COLEMAN


SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A3.1  |         |



# HARRINGTON PLACE LOT 5



FIRST FLOOR PLAN

SCALE: 1/8" = 1'-0"

\*RADON VENT PROVIDED  
PER LOCAL CODE

| DATE | BY | REVISION |
|------|----|----------|
|      |    |          |
|      |    |          |
|      |    |          |
|      |    |          |
|      |    |          |



FLOOR PLAN  
FIRST FLOOR  
COLEMAN


SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES  
expressly reserves its  
property rights in these  
plans and drawings.  
These plans and related  
drawings are not to be  
reproduced without written  
consent from SMITH  
DOUGLAS HOMES.

|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A5.1  |         |



# HARRINGTON PLACE LOT 5



ROOF LAYOUT "C"

SCALE: 1/8" = 1'-0"

| DATE | REVISION | BY |
|------|----------|----|
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |




ROOF PLAN  
ROOF PLAN  
COLEMAN

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.

|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A6.1  |         |

# HARRINGTON PLACE LOT 5



FIRST FLOOR ELECTRICAL PLAN

SCALE : 1/8" = 1'-0"

| ELECTRICAL LEGEND                                      |                                  |       |                                |
|--|----------------------------------|-------|--------------------------------|
| \$   | SWITCH                           | TV    | TV                             |
| \$3  | 3 WAY SWITCH                     | ⊕     | 120V RECEPTACLE                |
| \$4  | 4 WAY SWITCH                     | ⊕     | 120V SWITCHED RECEPTACLE       |
| ⊗  | CEILING FIXTURE                  | ⊕     | 220V RECEPTACLE                |
| ⊕K   | KEYLESS                          | ⊕GFCI | GFCI OUTLET                    |
| ⊕  | WALL MOUNT FIXTURE               | ⊕AFCI | ARCH FAULT CIRCUIT INTERRUPTER |
| ○  | CEILING FIXTURE                  | †GL   | GAS LINE                       |
| ●  | FLEX CONDUIT                     | †WL   | WATER LINE                     |
| CH   | CHIMES                           | ⊥     | HOSE BIBB                      |
| PH   | TELEPHONE                        | ⊕     | FLOOD LIGHT                    |
| SD/Cc  | SMOKE DETECTOR & CARBON MONOXIDE | ⊕     | 1x4 LUMINOUS FIXTURE           |
| SO   | SECURITY OUTLET                  | ⊕     | CEILING FAN                    |
| □  | GARAGE DOOR OPENER               | —     | ELECTRICAL WIRING              |
| ⊕  | EXHAUST FAN                      | ⊕     | CEILING FIXTURE                |
| ⊕  | FAN/LIGHT                        |       |                                |
| ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES             |                                  |       |                                |
| APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE) |                                  |       |                                |
| BREAKFAST/DINING ROOM                                  | 63" ABOVE FINISHED FLOOR         |       |                                |
| KITCHEN PENDANT LIGHTS                                 | 33" ABOVE COUNTER TOP            |       |                                |
| TWO STORY FOYER FIXTURE                                | 96" ABOVE FINISHED FLOOR         |       |                                |
| CEILING FAN  | 96" ABOVE FINISHED FLOOR         |       |                                |

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER

| DATE | REVISION | BY |
|------|----------|----|
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |
|      |          |    |




ELECTRICAL PLAN  
FIRST FLOOR  
COLEMAN

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.

|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A7.2  |         |

# HARRINGTON PLACE LOT 5



SECOND FLOOR ELECTRICAL PLAN

SCALE: 1/8" = 1'-0"

| ELECTRICAL LEGEND                                      |                                  |    |                                |
|--|----------------------------------|----|--------------------------------|
| \$   | SWITCH                           | TV | TV                             |
| \$3  | 3 WAY SWITCH                     | ⊕  | 120V RECEPTACLE                |
| \$4  | 4 WAY SWITCH                     | ⊕  | 120V SWITCHED RECEPTACLE       |
| ⊗  | CEILING FIXTURE                  | ⊕  | 220V RECEPTACLE                |
| ⊕  | KEYLESS                          | ⊕  | GFCI OUTLET                    |
| ⊕  | WALL MOUNT FIXTURE               | ⊕  | ARCH FAULT CIRCUIT INTERRUPTER |
| ○  | CEILING FIXTURE                  | †  | GAS LINE                       |
| ●  | FLEX CONDUIT                     | †  | WATER LINE                     |
| CH   | CHIMES                           | ⊥  | HOSE BIBB                      |
| PH   | TELEPHONE                        | ⊕  | FLOOD LIGHT                    |
| SD/Co  | SMOKE DETECTOR & CARBON MONOXIDE | ⊕  | 1x4 LUMINOUS FIXTURE           |
| SO   | SECURITY OUTLET                  | ⊕  | CEILING FAN                    |
| □  | GARAGE DOOR OPENER               | —  | ELECTRICAL WIRING              |
| ⊕  | EXHAUST FAN                      | ⊕  | CEILING FIXTURE                |
| ⊕  | FAN/LIGHT                        |    |                                |
| ELECTRICAL PLANS TO FOLLOW ALL LOCAL CODES             |                                  |    |                                |
| APPROX. FIXTURE HGTS (MEASURED FROM BOTTOM OF FIXTURE) |                                  |    |                                |
| BREAKFAST/DINING ROOM                                  | 63" ABOVE FINISHED FLOOR         |    |                                |
| KITCHEN PENDANT LIGHTS                                 | 33" ABOVE COUNTER TOP            |    |                                |
| TWO STORY FOYER FIXTURE                                | 96" ABOVE FINISHED FLOOR         |    |                                |
| CEILING FAN  | 96" ABOVE FINISHED FLOOR         |    |                                |

NOTE: FINAL PLACEMENT OF PHONE/CABLE T.B.D. ON SITE BY THE BUILDER

| DATE | REVISION | BY |
|------|----------|----|
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |
| #    | #        | #  |




ELECTRICAL PLAN  
SECOND FLOOR  
COLEMAN

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 115  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.


|                |         |
|----------------|---------|
| BY: CLJ        | CH: AW  |
| DATE: 08-30-23 |         |
| FACADE OPT: C  |         |
| PLAN ID:       |         |
| FND: ALL       | ELEV: C |
| PAGE NO: A7.3  |         |

REFER TO LOT SPECIFIC PLAN TO DETERMINE WHICH DETAILS APPLY




TYPICAL TWO PIECE CROWN

N.T.S.




SCUTTLE HOLE DETAIL

N.T.S.




PDS TRIM DETAIL

N.T.S.




GAS/ELECTRIC FIREPLACE DETAIL WITH WESCOTT WOOD MANTEL

N.T.S.




LINEAR ELECTRIC FIREPLACE DETAIL

N.T.S.




TYP. KNEEWALL SECTION

N.T.S.




TYP. 2ND FLOOR KNEEWALL STABILITY

N.T.S.




TYP. INTERIOR GARAGE "GOAL POST"

N.T.S.




SECTION VIEW 2X4 PORTAL WALL

N.T.S.




SECTION VIEWS 2X6 PORTAL WALL

N.T.S.




TYP. TV WALL PREP

N.T.S.




CABINET SOFFIT DETAIL ABOVE VENTED MICROWAVE W/CABINET ABOVE RANGE BUMPED UP & OUT

N.T.S.




HANDRAIL/POST DETAIL @ STAIRS

N.T.S.




BOX STEP OVERHANG

N.T.S.




GUARD RAIL DTL. AS REQ'D

N.T.S.




SECTION @ ISLAND KNEEWALL

N.T.S.




TYPICAL CHAIR RAIL & SHADOW BOX DETAIL

N.T.S.




CHAIR RAIL END TRIM DETAIL

N.T.S.



ELECTRICAL PANEL DETAIL


N.T.S.




SIDE ELEVATION

MUD ROOM BENCH SEAT DETAIL

N.T.S.



FRONT ELEVATION



MUD ROOM BENCH SEAT DETAIL WITH BEADED BOARD, HOOKS, & CROWN

N.T.S.

(IF TRIM CHOSEN WITHOUT BENCH CONTINUE TO FLOOR)

© SMITH DOUGLAS HOMES 2023

| BY | REVISION | DATE |
|----|----------|------|
|    |          |      |
|    |          |      |
|    |          |      |
|    |          |      |

**SMITH DOUGLAS HOMES**  
QUALITY | INTEGRITY | VALUE


INTERIOR TRIM  
DETAILS

SMITH DOUGLAS HOMES  
110 VILLAGE TRAIL  
SUITE 215  
WOODSTOCK, GA 30188  
www.smithdouglas.com

SMITH DOUGLAS HOMES expressly reserves its property rights in these plans and drawings. These plans and related drawings are not to be reproduced without written consent from SMITH DOUGLAS HOMES.

|           |         |
|-----------|---------|
| DATE:     | 6/13/23 |
| PLAN ID:  |         |
| PND:      |         |
| ELEV:     |         |
| PAGE NO.: | D1.1    |





**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Boulevard Parkway, Suite 105 - Asheville, NC 28802  
770-777-9974 - mulhern@mulhernkulp.com



Mulhern+Kulp project number:  
**256-2 1006**

project ngr: **SMK**  
drawn by: **MJF**  
issue date: **10-21-2021**

REVISIONS:  
date: **10/21/2021**  
ISSUED BY: **WAS ADP**  
initial: **JFP**

**SMITH DOUGLAS**  
HOMES

**GENERAL STRUCTURAL NOTES**  
**COLEMAN MODEL**  
120 MPH WIND ZONE  
NORTH CAROLINA

Sheet:  
**S0.0**

**Harrington**  
**Lot 5**

**GENERAL STRUCTURAL NOTES**

- DESIGN IS BASED ON 2018 NC59C-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- WOOD FRAME ENGINEERING IS BASED ON NDS, NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION - LATEST EDITION.
- DESIGN LOADS:  
ROOF  
LIVE = 20 PSF  
DEAD = 1 PSF T.C., 10 PSF B.C.  
LOAD DURATION FACTOR = 1.25
- FLOOR  
LIVE = 40 PSF (30 PSF @ SLEEPING AREAS)  
DEAD = 10 PSF (1-1015T5)
- SOIL  
APDL 10 PSF @ CERAMIC TILE IN BATHS & LAUND.  
2,000 PSF ASSIGNED ALLOWABLE BEARING PRESSURE (TO BE VERIFIED BY BUILDER)

**GENERAL FRAMING**

- ALL TYP. NAIL FASTENER REQUIREMENTS ARE NOTED IN STANDARD CONNECTIONS TABLE (IRC TABLE R602.3(1)) OR ON PLANS. ALL NAILS SPECIFIED ARE MIN DIAMETER AND LENGTH REQUIRED FOR CONNECTION. ALL HANGER NAILS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR MAX. CHARTED CAPACITY. NOTE: HANGERS USE COMMON NAIL DIAMETERS NOT TYPICAL FRAMING GAIN NAILS.
- EXT. & INT. BEARING WALLS SHALL BE 2X4 OR 2X6 (AS SHOWN ON PLANS) @ 16" O.C. SPPF59 5/16" GRADE LUMBER OR BETTER, UNO.
- WALLS OVER 12' TALL SHALL BE PER PLAN.
- ALL INTERIOR BEARING WALLS ARE ASSIGNED TO BE SHEATHED w/ 5/8" WALL BOARD (ONE SIDE MIN) OR PROVIDE MID HT. BLOCKING.
- ALL HEADERS, BEAMS & OTHER STRUCTURAL MEMBERS SHALL BE SPRUCE-PINE-FIR #2 (SPF) OR SOUTHERN PINE #2 (SP) LUMBER OR BETTER. SUPPORT ALL HEADERS/ BEAMS w/ (12x) JACK STUD @ (1/2x KING STUD) MINIMUM.
- NUMBER OF STUDS SPECIFIED AT A SUPPORT INDICATES THE NUMBER OF JACK STUDS REQUIRED, UNO.
- ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x STUD GRADE MEMBERS SPACED @ 24" O.C. (MAX, UNO.)
- HEADERS IN NON-LOAD BEARING WALLS SHALL BE: (1/2)x4/6 FLAT @ 4'; (2)x4/6 FLAT UP TO 8'.
- ALL FRAMING LUMBER SHALL BE DRIED TO 19% MC (KD-15).
- ENGINEERED LUMBER BEAMS TO MEET OR EXCEED THE FOLLOWING:  
• LVL - Fb-2600 psi; Fv-285 psi; E=2,000,000 psi  
• LVL - Fb-2400 psi; Fv-2500 psi; E=1,800,000 psi  
FOR 2 & 3 PLY BEAMS OF EQUAL 1 1/2" MAX. WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF 3"x0.120" NAILS @ 8" O.C. OR 2 ROWS USP M855 SCREWS (OR 3"; TRUSSLOK SCREWS) @ 16" O.C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER. APPLY FASTENING AT BOTH FACES FOR 3-PLY CONDITION. LOCATE TOP & BOTTOM NAILS/SCREWS 2" FROM EDGE. SOLID 3 1/2" OR 5 1/2" BEAMS ARE ACCEPTABLE. USE 2 ROWS OF NAILS FOR 2x6 & 2x8 MEMBERS.
- FOR 4 PLY BEAMS OF EQUAL 1 1/2" MAX. WIDTH, FASTEN PLIES TOGETHER WITH 3 ROWS OF USP M86 SCREWS (OR 6 3/4" TRUSSLOK SCREWS) @ 16" O.C. USE A MINIMUM OF 4 ROWS FOR BEAM DEPTHS OF 14" OR GREATER. APPLY FASTENING AT BOTH FACES (ONE SIDE ONLY FOR TRUSSLOK SCREWS). LOCATE TOP AND BOTTOM SCREWS 2" FROM EDGE. A SOLID 1" BEAM IS ACCEPTABLE.
- PROVIDE SOLID BLOCKING IN FLOOR SYSTEM UNDER ALL POSTS CONTIGUOUS TO FRU/BEARING. BLOCKING TO MATCH POST ABOVE.
- ALL EXTERIOR 4x4 WOOD POSTS SHALL HAVE USP BC522-4 CAP & PA44E BASE, UNO.
- CORROSION NOTES:  
• BUILDER RESPONSIBLE TO DETERMINE CORROSION-RESISTANCE REQUIREMENTS AND COMPATIBILITY OF HARDWARE, FASTENERS AND CONNECTORS FOR ENVIRONMENTAL EXPOSURE AND IN CONTACT w/ PRESERVATIVE-TREATED WOOD OF ACTUAL FINAL CONDITIONS AND SOURCED MATERIALS. CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD.
- ALL FASTENERS AND CONNECTORS EXPOSED TO SALT WATER (WITHIN 300' OF SALT WATER SHORELINE, INCLUDING VENTED SPACES) SHALL BE STAINLESS STEEL.

**FLOOR FRAMING**

- I-JOISTS SHALL BE DESIGNED BY MANUF. TO MEET OR EXCEED L/480 LIVE LOAD DEFLECTION CRITERIA. (EXCLUDES STONEMARBLE OR MET BED CONSTRUCTED FLOORS - CONTACT MK FOR EXCLUDED FLOOR DESIGNS)
- PER THE GUIDELINES OF THE TILE COUNCIL OF NORTH AMERICA (TCA HANDBOOK), IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO VERIFY THAT THE FINISHES TO BE INSTALLED MATCH THE DESIGN CRITERIA NOTED ABOVE (UNDER "DESIGN LOADS").
- FLOOR SYSTEMS & SHEATHING HAVE BEEN DESIGNED TO SUPPORT ADDITIONAL DEAD LOAD FROM CERAMIC TILE (EXCLUDING MARBLE OR STONE). HOWEVER, IT SHALL BE THE FLOOR FINISH INSTALLER'S RESPONSIBILITY TO PROVIDE PROPER UNDERLAYMENT, UNDERLAYING MEMBRANE AND PORTLAND CEMENT PER THE MANUFACTURER'S DESIGNATIONS IN THE TCA HANDBOOK (TILE COUNCIL OF NORTH AMERICA).
- AT I-JOIST FLOORS, PROVIDE 1" MIN. OSB RIM BOARD.
- METAL HANGERS SHALL BE SPECIFIED BY MANUFACTURER, UNO.
- I-JOIST SHOP DWGS. SHALL BE SUBMITTED TO ARCH. & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- FLOOR SHEATHING SHALL BE 2392' APA, RATED STURD-I-FLOOR® 24" O.C. EXPOSURE 1 (OR APPROVED EQUAL) WITH TONGUE AND GROOVE EDGES. FASTEN TO FRAMING MEMBERS w/ GLUE AND - 2 1/2" x 0.131" NAILS @ 6" O.C. @ PANEL EDGES & @ 12" O.C. FIELD. - 2 3/8" x 0.120" NAILS @ 4" O.C. @ PANEL EDGES & @ 8" O.C. FIELD. - 2 3/8" x 0.118" NAILS @ 3" O.C. @ PANEL EDGES & @ 6" O.C. IN FIELD.

**ROOF FRAMING**

- ROOF SHEATHING SHALL BE 7/16" APA, RATED SHEATHING 24/16 EXPOSURE 1 (OR APPROVED EQUAL). FASTEN TO FRAMING MEMBERS - w/ 2 1/2" x 0.131" NAILS @ 6" O.C. @ PANEL EDGES & @ 12" O.C. FIELD. - w/ 2 3/8" x 0.120" NAILS @ 4" O.C. @ PANEL EDGES & @ 8" O.C. FIELD. - w/ 2 3/8" x 0.118" NAILS @ 3" O.C. @ PANEL EDGES & @ 6" O.C. FIELD.
- WITHIN 48" OF ALL ROOF EDGES, RIDGES, & HIPs FASTEN ROOF SHEATHING FIELDS PER EDGE NAILING SPEC.
- FASTEN EACH ROOF TRUSS TO TOP PLATE w/ USP RTTA CLIP (OR APPROVED EQUAL) @ ALL BEARING POINTS. PROVIDE (2) RTTA CLIPS AT 2-PLY GIRDER, TRUSSES, @ RTTA CLIPS AT 3-PLY GIRDER TRUSSES & ROOF BEAMS - (3) AT BEARING POINTS.
- METAL HANGERS SHALL BE SPECIFIED BY THE MANUFACTURER, UNO.
- ROOF TRUSS SHOP DWGS. SHALL BE SUBMITTED TO ARCH. & ENG. FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY.
- ERECT AND INSTALL ROOF TRUSSES PER WTC & TP1'S BC51.1 "GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES".
- SUPPORT SHORT SPAN ROOF TRUSSES w/ 2x4 LEDGERS FASTENED TO FRAMING w/ (2) 3" x 0.120" NAILS @ 16" O.C. (IP TO T SPAN).

**MEANS & METHODS NOTES**

THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS FINISHED AND ALL PLAN DETAIL AND NOTE SPECIFICATIONS HAVE BEEN COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUTS, AND TIE-DOWNS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING AND BRACING REQUIRED TO STABILIZE AND PROTECT EXISTING AND ADJACENT STRUCTURES AND SYSTEMS DURING COURSE OF DEMOLITION AND CONSTRUCTION OF THE PROJECT.

STRUCTURAL DESIGN AND SPECIFICATIONS ASSUME THAT ALL SUPPORTING AND NON-SUPPORTING ELEMENTS IN CONTACT WITH FLOOR FRAMING ARE LEVEL, INCLUDING, BUT NOT LIMITED TO; FOUNDATIONS, SLABS ON GRADE, BEAMS, WALLS, AND NON-BEARING ELEMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LEVELNESS AND MAKE ADJUSTMENTS AS NECESSARY, INCLUDING CONSIDERATION OF THOSE AREAS THAT MAY BE WITHIN CONTRACTUAL, INDUSTRY, OR WARRANTY TOLERANCES.

**LATERAL/WALL BRACING & WALL SHEATHING SPECIFICATIONS**

THIS MODEL HAS BEEN DESIGNED TO RESIST LATERAL FORCES RESULTING FROM:  
**20MPH WIND IN 2018 NC59C:RC & 120MPH WIND IN 2018 IRC**  
(120 MPH WIND SPEED IN ASCE 7) WIND MAP, PER IRC R301.2.1.1  
EXP. B, RISK CAT. 2 & SEISMIC CAT. A, B.

THE DESIGN WAS COMPLETED PER 2015 & 2018 IRC SECTION 600.0 & ASCE 7, AS PERMITTED BY R301.1.3 OF THE 2018 NC59C:RC & 2018 IRC. ACCORDINGLY, THIS MODEL, AS DOCUMENTED AND DETAILED HEREWITHIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES.

DESIGN WIND UPLIFT LOADS HAVE BEEN CALCULATED UTILIZING ASCE 7 (ACCEPTED ENGINEERING PRACTICE) AS ALLOWED PER 2018 NC59C:RC & 2018 IRC SECTION R802.1.1.1.1. THIS MODEL HAS BEEN DETAILED WHERE REQUIRED & ENGINEERED TO RESIST THE WIND UPLIFT LOAD PATH PER SECTIONS R602.3.5.4, R802.1.1.

**EXT. WALL SHEATHING SPECIFICATION**

- 7/16" OSB OR 1/2" PLYWOOD:  
FASTEN SHEATHING w/ 2 3/8" x 0.131" NAILS @ 6" O.C. AT EDGES & @ 12" O.C. IN THE PANEL FIELD. (TYP. UNO.)
- ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUDS) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT ALL UNSUPPORTED PANEL EDGES & EDGE FASTENING.
- ALL EXT. WALLS SHALL BE CONTINUOUSLY SHEATHED AND ARE CONSIDERED SHEAR WALLS.
- ALT. STAPLE CONNECTION SPEC: 1 3/4" 16 GA STAPLES (1/2" GROWN) @ 3" O.C. AT EDGES & @ 6" O.C. IN FIELD.

**3" O.C. EDGE NAILING**

- AT DESIGNATED AREAS - FASTEN PANEL EDGES OF WOOD STRUCTURAL WALL SHEATHING TO FRAMING w/ 2 3/8" x 0.131" NAILS @ 3" O.C. AND 12" O.C. IN THE PANEL FIELD. NO STAPLE ALTERNATIVE AVAILABLE
- ALL THIS SPEC. SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUD) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT UNSUPPORTED PANEL EDGES AND 3" O.C. EDGE FASTENING.

**NOTES**

- SEE CONNECTION SPECIFICATIONS CHART FOR STANDARD SHEAR TRANSFER DETAILING. IF ADDITIONAL CAPACITY IS REQUIRED BY DESIGN IT WILL BE SPECIFICALLY NOTED ON PLAN.
- DESIGN ASSUMES 16" O.C. MAX. STUD SPACING, UNO.
- ALL STRUCTURAL PANELS ARE TO BE DIRECTLY APPLIED TO STUD FRAMING.
- PRE-MANUFACTURED PANELIZED WALLS:  
FASTEN TOGETHER END STUDS OF WALL PANELS SHEATHED w/ OSB OR PLYWOOD w/ 3" x 0.120" NAILS @ 4" O.C. (THRU ONE SIDE ONLY)

- INDICATES EXTENT OF INT. OSB SHEARWALL, AND/OR 3" O.C. EDGE NAILING
- INDICATES HOLDOWN

**GENERAL STRUCTURAL NOTES**

**FOUNDATION**

- DESIGN IS BASED ON 2018 NC59C-RESIDENTIAL CODE & 2018 IRC WITH SOUTH CAROLINA AMENDMENTS
- FOOTING DESIGN - 2,000 PSF NET ALLOWABLE SOIL BEARING CAPACITY IS ASSUMED. BUILDER/CONTRACTOR MUST VERIFY.
- FASTEN 2x4/6 SILL PLATES TO CONC FND WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING:  
• 1/2" DIA. ANCHOR BOLTS @ 6'-0" O.C. 1" MIN. EMBEDMENT  
• F44 ANCHOR STRAPS @ 6'-0" O.C.
- FASTEN 2x4 SILL PLATE TO PRECAST BSMT WALLS WITH A MINIMUM OF 2 ANCHORS PER PLATE, 12" MAX. FROM PLATE ENDS - UTILIZING:  
• 1/2" DIA. BOLTS @ 2'-0" O.C.
- ALL LUMBER EXPOSED TO WEATHER OR IN CONTACT w/ PERIMETER FOUNDATION SHALL BE PRESERVATIVE TREATED SOUTHERN PINE #2.
- BUILDER TO VERIFY CORROSION-RESISTANCE COMPATIBILITY OF HARDWARE & FASTENERS IN CONTACT w/ PRESERVATIVE-TREATED WOOD. CONTACT LUMBER & HARDWARE SUPPLIERS TO COORD.
- FOUNDATION WALLS & FOOTINGS SHALL BE PLAIN CONCRETE, UNO.
- CONCRETE DESIGN BASED ON ACI 318. CONCRETE SHALL ATTAIN THE FOLLOWING MIN. COMPRESSIVE STRENGTHS IN 28 DAYS, UNO.:  
Ft - 4,000 psi  
3,000 psi  
3,500 psi  
fy = 60,000 psi
- BASEMENT FOUNDATION WALL DESIGN BASED ON:  
• Ø OR 1" HEIGHT (AS NOTED ON PLANS)  
- TALLER WALLS MUST BE ENGINEERED.
- BASEMENT WALL DESIGN IS BASED ON 30 OR 45 PCF BACKFILL SOIL TYPE CLASSIFICATION:  
45 PCF TYPE (GN, GP, SM, SP)  
• INTERSTANT - IF 60 PCF SOIL TYPE (G, ML, CL, OR CJ) IS UTILIZED FOR BACKFILL, CONTACT MULHERN & KULP FOR FURTHER EVALUATION OF FOUNDATION DESIGN.
- BASEMENT WALLS SHALL BE BRACED PRIOR TO BACKFILLING, BY ADEQUATE TEMPORARY BRACING OR INSTALL 1st FLOOR DECK. THAN 5% OR MORE THAN 18" AIR ENTRAINMENT.
- ALL FOOTINGS SHALL BEAR BELOW FROST LINE (TYP) OR 12" MIN IN REGIONS WHERE CODE FROST DEPTH IS NOT APPLICABLE. CONSULT SOILS REPORT OR BUILDING DEPT. FOR MINIMUM DEPTH BELOW GRADE.
- FOOTINGS AND SLABS ON GRADE SHALL BEAR ON VIRGIN SOIL OR 95% COMPACTED FILL.
- PROVIDE CONTROL JOINTS AT ALL INSIDE CORNERS OF SLAB EDGES, AND OTHER LOCATIONS WHERE SLAB CRACKS ARE LIKELY TO DEVELOP.  
• JOINTS SHALL BE LOCATED @ 10'-0" O.C. (RECOMMENDED) OR 15'-0" O.C. (MAXIMUM)
- JOINT GRID PATTERN SHALL BE AS CLOSE TO SQUARES AS POSSIBLE (1:1 RATIO), WITH A MAXIMUM OF 1:1.5 RATIO
- CONTROL JOINTS SHALL NOT BE INSTALLED IN STRUCTURAL SLABS

- TYPICAL REINFORCEMENT DETAILS: PROVIDE 3" MIN. CLEAR COVER WHERE CAST AGAINST EARTH, 1 1/2" MIN. CLEAR COVER AGAINST FORMS. LAP ALL REBAR 48 BAR DIAMETERS MIN. (24" FOR #4 BARS) & BEND BARS AND LAP AT CORNERS. PROVIDE 6" HOOK INTO SUPPORTING FOOTINGS WHEN FOOTINGS INTERSECT.
- DIMENSIONS BY OTHERS, BUILDER TO VERIFY.

**LEGEND**

- INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANUF. (TYP. UNO)
- INDICATES TRUSS OVERFRAMING @ 24" O.C. (TYP. UNO)
- INDICATES 14" DEEP FLOOR I-JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER
- INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)
- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR APDL 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING WALL
- BEARING WALL ABOVE (BMA)
- BEAM/HEADER
- METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

| DESCRIPTION OF BLDG. ELEMENT                 | 3"x0.131" NAILS   | 3"x0.120" NAILS   |
|--|---|---|
| JOIST TO SOLE PLATE                          | (3) TOENAILS  | (3) TOENAILS*   |
| SOLE PL. TO JOIST/RIM OR BLKG                | NAILS @ 4" O.C.   | NAILS @ 4" O.C.   |
| STUD TO PLATE                                | (4) TOENAILS/ (4) END NAILS   | (4) TOENAILS/ (4) END NAILS*  |
| RIM TO TOP PLATE                             | TOENAILS @ 6" O.C.  | TOENAILS @ 6" O.C.  |
| BLKG: BTRY. JOISTS TO TOP PL.                | (3) TOENAILS EA. END  | (3) TOENAILS EA. END*   |
| DOUBLE 5/16"                                 | NAILS @ 16" O.C.  | NAILS @ 16" O.C.  |
| DOUBLE TOP PLATE                             | NAILS @ 12" O.C.  | NAILS @ 8" O.C.   |
| DOUBLE TOP PLATE LAP SPLICE                  | (2) NAILS IN LAPPED AREA (24" MIN)  | (2) NAILS IN LAPPED AREA (24" MIN)  |
| TOP PLATE LAP @ CORNERS & INTERSECTING WALLS | (3) NAILS   | (3) NAILS   |
| RAFTER/TRUSSES TO TOP PLATE                  | (4) TOENAILS + (1) SIMPSON H25T   | (4) TOENAILS + (1) SIMPSON H25T   |
| GAB. END TRUSSES TO DBL. TOP PL.             | TOENAILS @ 8" O.C.  | TOENAILS @ 8" O.C.  |
| R.T. w/ HEEL HT. 9 1/4" TO 12"               | 2X10 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C.   | 2X10 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C.   |
| R.T. w/ HEEL HT. 12" TO 16"                  | 2X12 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C.   | 2X12 BLK EVERY 3RD BAY FASTENED TO DBL. TOP PLATE w/ TOENAILS @ 4" O.C.   |
| R.T. w/ HEEL HT. IP TO 24"                   | LAP WALL SHG. w/ DBL. TOP PL. & INSTALL ON TRUSSES VERT. - FASTEN w/ NAILS @ 6" O.C.*   | LAP WALL SHG. w/ DBL. TOP PL. & INSTALL ON TRUSSES VERT. - FASTEN w/ NAILS @ 6" O.C.*   |
| R.T. w/ HEEL HT. 24" TO 48"                  | LAP WALL SHG. w/ DBL. TOP PL. & INSTALL ON TRUSSES VERT. - FASTEN w/ NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL* | LAP WALL SHG. w/ DBL. TOP PL. & INSTALL ON TRUSSES VERT. - FASTEN w/ NAILS @ 6" O.C. PROVIDE 2x BLK @ EA. BAY AT TOP OF HEEL* |
| WALL TO FOUNDATION                           | WALL SHG. LAP w/ SILL PL. & FASTENED PER SHEAR WALL FASTENING SPEC.   | WALL SHG. LAP w/ SILL PL. & FASTENED PER SHEAR WALL FASTENING SPEC.   |

\* 2 1/2"x0.131 IS AN ACCEPTABLE ALTERNATIVE TO A 3"x0.120, SAME SPACING OR NUMBER OF NAILS. (ONLY ACCEPTABLE WHERE \* ARE SHOWN)

**ADDITIONAL NOTES FOR TRUSS & I-JOIST MANUFACTURER**

ROOF TRUSS AND ENGINEERED JOISTS SHALL BE DESIGNED TO MEET THE DEFLECTION CRITERIA BELOW UNLESS NOTED OTHERWISE ON PLAN. MULHERN & KULP CANNOT BE HELD RESPONSIBLE FOR ANY STRUCTURAL ISSUES RELATED TO ANY BUILDING COMPONENT IF COMPONENT SHOP DRAWINGS ARE NOT SUBMITTED TO MK FOR REVIEW PRIOR TO FABRICATION, DELIVERY, OR INSTALLATION.

TRUSSES/IJOISTS SHALL BE DESIGNED SO THAT DIFFERENTIAL DEFLECTION BETWEEN ADJACENT PARALLEL TRUSSES/IJOISTS OR GIRDER TRUSSES/FISH BEAMS DO NOT EXCEED THE FOLLOWING:


- ROOF TRUSSES:  
1/4" DEAD LOAD
- ATTIC TRUSSES/ I-JOISTS:  
1/8" DEAD LOAD

ABSOLUTE DEAD LOAD DEFLECTION OF ATTIC TRUSSES WHEN ADJACENT TO FLOOR FRAMING BY OTHERS SHALL BE LIMITED TO 3/16". (NOT DIFFERENTIAL DEFLECTION)

**VENEER LINTEL SCHEDULE**

| SPAN (MAX) | HEIGHT OF VENEER ABOVE LINTEL | STEEL ANGLE SIZE |
|------------|-------------------------------|------------------|
| 3'-0"      | 20 FT. MAX                    | 1 1/2"x3"x1/2"   |
| 6'-0"      | 3 FT. MAX                     | 1 1/2"x3"x1/2"   |
| 6'-0"      | 12 FT. MAX                    | 1 1/2"x3"x1/2"   |
| 6'-0"      | 20 FT. MAX                    | 1 1/2"x3"x1/2"   |
| 6'-0"      | 3 FT. MAX                     | 1 1/2"x3"x1/2"   |
| 6'-0"      | 12 FT. MAX                    | 1 1/2"x3"x1/2"   |
| 6'-0"      | 16 FT. MAX                    | 1 1/2"x3"x1/2"   |
| 6'-0"      | 12 FT. MAX                    | 1 1/2"x3"x1/2"   |

ALL LINTELS:  
- SHALL SUPPORT 2 1/2" x 3 1/2" VENEER w/ 40 PSI MAXIMUM HEIGHT.  
- SHALL BE INSTALLED OVER A MINIMUM OF 2" CONCRETE OR 4" CMU BEARING.  
- 6" SHALL NOT BE FASTENED BACK TO BEARER.  
- 6" SHALL HAVE 8" MIN. BEARING.  
- 6" SHALL HAVE 8" MIN. BEARING.  
- LONG LAG SCREWS IN 2" LONG VERTICALLY SLOTTED NAILS.  
- MAX. VENEER HT. APPLIES TO ANY PORTION OF BRACK OVER THE OPENING.  
- WHEN SUPPORTING VENEER, 3" MADE THE EXTERIOR TOE OF THE HORIZONTAL LEG MAY BE CUT IN THE FIELD TO BE 3/4" WIDE OVER THE BEARING LENGTH ONLY. THIS SHALL BE NOTED ON THE PLAN.  
- SEE STRUCTURAL PLANS FOR ANY LINTEL CONDITION NOT ENCOMPASSED BY THE ABOVE PARAMETERS.  
- FOR GREEN VENEER USE LAGS/MK.



MULHERN+KULP  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Southside Parkway, Suite 105 - Durham, NC 27702  
919-777-0874 - mulhern+kulp.com  
NC License # C-3825



Mulhern+Kulp project number:  
**256-21006**  
Project Ngr: **SMK**  
Drawn by: **MJF**  
Issue date: **10-21-2021**

REVISIONS:  
date: **12/10/21**  
initial: **JFP**  
description: **REVISIONS ADDED**


SMITH DOUGLAS  
HOMES

MONO-SLAB FOUNDATION  
COLEMAN MODEL  
120 MPH WIND ZONE  
NORTH CAROLINA

Sheet:  
**S1.0**


**3 PARTIAL MONO-SLAB FOUNDATION PLAN**  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT

OPT. COVERED PORCH




**4 PARTIAL MONO-SLAB FOUNDATION PLAN**  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT

OPT. LARGE COVERED PORCH



**1 MONO-SLAB FOUNDATION PLAN**  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT

ALL ELEV. SIM.



**Harrington Lot 5**


REFER TO S0.0 FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

**LEGEND**


- RT. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANIF. (TYP. UNO.)
- O.F. INDICATES TRUSSES OVERFRAMING @ 24" O.C. (TYP. UNO.)
- F.J. INDICATES 14" DEEP FLOOR JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER.
- D.J. INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX).
- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL. 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING WALL
- BEARING WALL ABOVE (B.W.A.)
- BEAM/HEADER
- METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

**2 PARTIAL MONO-SLAB FOUNDATION PLAN**  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT

OPT. SIDE ENTRY GARAGE







MULHERN+KULP  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Bousharts Parkway, Suite 105 - Ahlsville, GA 30022  
478-777-0074 - mulhern@mulhernkulp.com




Mulhern+Kulp project number:  
256-21006  
project mgr: SMK  
drawn by: MJF  
issue date: 10-21-2021

REVISIONS:  
date: 10/21/21  
initial: JFP  
description: REVISIONS HAS ADDED

SMITH DOUGLAS  
HOMES

1ST FLOOR FRAMING PLAN  
COLEMAN MODEL  
120 MPH WIND ZONE  
NORTH CAROLINA

Sheet:  
**S2.0**



**3 PARTIAL 1ST FLOOR FRAMING PLAN**

SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT  
OPT. EXT. DECK  
OPT. LARGE  
COVERED DECK SIM.


**Harrington  
Lot 5**

THIS LEVEL HAS BEEN DESIGNED FOR 9'-1" PLATE HEIGHT  
REFER TO S.O.D FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

**LEGEND**

- RT. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF MANIF. (TYP. UNO.)
- O.F. INDICATES TRUSSES OVERFRAMING @ 24" O.C. (TYP. UNO.)
- F.J. INDICATES 14" DEEP FLOOR JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER.
- P.J. INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX).
- INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.
- INTERIOR BEARING MALL
- BEARING WALL ABOVE (B.W.A.)
- BEAM/HEADER
- METAL HANGER
- INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
- \*

**1 1ST FLOOR FRAMING PLAN**  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON LIMIT  
ALL ELEV. SIM.



MULHERN+KULP  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Southside Parkway, Suite 105 - Durham, NC 27702  
919-777-0014 - mulhern@mk.com

NC License # C-3825



Project number: 256-21006  
Project mgr: SMK  
Drawn by: MJF  
Issue date: 10-21-2021


REVISIONS:  
date: 10/21/2021  
initial: JFP

SMITH DOUGLAS  
HOMES


2ND FLOOR FRAMING PLAN  
COLEMAN MODEL  
NORTH CAROLINA  
120 MPH WIND ZONE

Sheet: **S3.0**


**3** PARTIAL 2ND FLOOR FRAMING PLAN  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON I/JIT




**4** PARTIAL 2ND FLOOR FRAMING PLAN  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON I/JIT



**1** 2ND FLOOR FRAMING PLAN  
ELEV. A, C, D, F, G, H  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON I/JIT



**2** PARTIAL 2ND FLOOR FRAMING PLAN  
ELEV. B, E, & H  
SCALE: 1/4"=1'-0" ON 22x34  
1/8"=1'-0" ON I/JIT




Harrington  
Lot 5

THIS LEVEL HAS BEEN DESIGNED FOR 9'-1" PLATE HEIGHT

REFER TO 50.0 FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

- LEGEND**
- RT. INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF. MANIF. (TYP. UNO.)
  - O.F. INDICATES TRUSSES OVERFRAMING @ 24" O.C. (TYP. UNO.)
  - F.J. INDICATES 14" DEEP FLOOR JOISTS (24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER.
  - D.J. INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX).
  - INDICATES LOCATIONS OF POTENTIAL TILE FLOOR. JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADDL. 10 PSF DEAD LOAD AT THESE LOCATIONS.
  - INTERIOR BEARING WALL
  - BEARING WALL ABOVE (B.W.A.)
  - BEAM/HEADER
  - METAL HANGER
  - INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
  - \*



**1** ROOF FRAMING PLAN  
 SCALE: 1/4"=1'-0" ON 22x34  
 1/8"=1'-0" ON 11x7  
 ELEV. C, F & I

- LEGEND**
- INDICATES ROOF TRUSSES @ 24" O.C. PER ROOF MANUF. (TYP. UNO.)
  - INDICATES TRUSSES OVERFRAMING @ 24" O.C. (TYP. UNO.)
  - INDICATES 14" DEEP FLOOR I-JOISTS @ 24" O.C. MAX SPACING). JOIST SERIES AND SPACING SHALL BE THE RESPONSIBILITY OF THE JOIST MANUFACTURER
  - INDICATES 2x8 P.T. DECK JOISTS @ 16" O.C. (MAX)
  - INDICATES LOCATIONS OF POTENTIAL TILE FLOOR JOIST MANUFACTURER SHALL DESIGN FLOOR SYSTEM FOR ADD'L 10 PSF DEAD LOAD AT THESE LOCATIONS.
  - INTERIOR BEARING WALL
  - BEARING WALL ABOVE (B.W.A.)
  - BEAM/HEADER
  - METAL HANGER
  - INDICATES POST ABOVE (P.A.) PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.

THIS LEVEL HAS BEEN DESIGNED FOR 9'-1" PLATE HEIGHT

REFER TO SOI FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

Harrington  
Lot 5

ROOF FRAMING PLAN

COLEMAN MODEL

120 MPH WIND ZONE  
NORTH CAROLINA

SMITH DOUGLAS  
HOMES

REVISIONS:

|            |                     |          |     |
|------------|---------------------|----------|-----|
| date:      | 12/10/21            | initial: | JFP |
| REVISIONS: | REVISIONS WAS ADDED |          |     |

project mgr: SMK  
drawn by: MJF  
issue date: 10-21-2021


Mulhern+Kulp project number:  
256-21006

**MULHERN+KULP**  
 RESIDENTIAL STRUCTURAL ENGINEERING  
 3025 Shawsboro Parkway, Suite 105 - Ahoskie, VA 24502  
 #770-777-0074 - mulhern+kulp.com  
 NC License # C-3825

8/11/23  
 © copyright: MULHERN & KULP  
 Structural Engineering, Inc.







**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING

3625 Brookside Parkway, Suite 165, Alpharetta, GA 30022 ▶ p 770-777-0074 ▶ mulhernkulp.com

August 18, 2023


Jody Hunt  
Director of Product Development  
**SMITH DOUGLAS HOMES**  
110 Village Trail, Suite 215  
Woodstock, GA 30188

**ALTERNATE GARAGE CURB DETAIL**  
Smith Douglas Homes

*Reference*  
Current Structural Plans prepared by Mulhern & Kulp

Jody:

Pursuant to your request, we have prepared this letter to address the “*Alternate Garage Curb Details*”, prepared by Mulhern & Kulp for Smith Douglas Homes shown below. The foundation details shown below call for a 4” wide curb with a maximum of 8” stem wall height; these are an acceptable alternative to the 6” wide curb at the garage per M&K foundation details 3 & 4 on sheet SD-1.0 at 2x4 garage wall locations.




Please feel free to call if you have any questions.

Respectfully,  
**MULHERN & KULP STRUCTURAL ENGINEERING, INC.**  
NC License # C-3825  
Shaun M. Kreidel, P.E. *Project Manager + Atlanta Office Director*



Signature + Seal 08/18/2023



© copyright: MULHERN + KULP  
Structural Engineering, Inc.

**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Southside Parkway, Suite 105 - Ahlsville, VA 20022  
703-777-0074 - mulhern@mk.com



Mulhern+Kulp project number:  
**256-21006**

project mgr: **SMK**  
drawn by: **MJF**  
issue date: **10-21-2021**



REVISIONS:  
date: **12/10/21** initial: **JFP**  
REVISIONS: **ISSUES HAS ADDED**


SMITH DOUGLAS  
HOMES

FOUNDATION DETAILS  
COLEMAN MODEL  
120 MPH WIND ZONE  
NORTH CAROLINA

Harrington  
Lot 5

Sheet:  
**SD1.4**





**MULHERN+KULP**  
 #ESSENTIAL STRUCTURAL ENGINEERING  
 2025 Southside Parkway, Suite 105 - Alhambra, GA 30022  
 404-770-7774 - mulhern@mulhernkulp.com  
 NC License # C-3825

Mulhern+Kulp project number: 256-21006


|                 |            |
|-----------------|------------|
| project mgr:    | SMK        |
| drawn by:       | MJF        |
| issue date:     | 10-21-2021 |
| REVISIONS:      |            |
| date:           | initial    |
| 12/10/21        | JFP        |
| REVISIONS ADDED |            |

SMITH DOUGLAS  
 HOMES


FOUNDATION DETAILS  
 COLEMAN MODEL  
 120 MPH WIND ZONE  
 NORTH CAROLINA

Sheet: **SD1.5**


Harrington  
 Lot 5




**4** TYPICAL CONCRETE GRADE BEAM @ GARAGE FDN.  
 SCALE: 3/4"=1'-0"




**3** TYPICAL PERIMETER FOOTING @ GARAGE - BASEMENT FOUNDATION (BRICK)  
 SCALE: 3/4"=1'-0"




**2** TYPICAL PERIMETER FOOTING @ GARAGE - BASEMENT FOUNDATION  
 SCALE: 3/4"=1'-0"




**1** GENERIC FOUNDATION PLAN KEY @ GARAGE  
 SCALE: 1/4"=1'-0"




**7** SECTION  
 SCALE: 3/4"=1'-0"



**6** SECTION  
 SCALE: 3/4"=1'-0"



**5** CONCRETE BSMT. FDN. WALL @ GARAGE  
 SCALE: 3/4"=1'-0"



**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Beavertail Parkway, Suite 105 - Ahmston, VA 20022  
703-777-0974 - mulhern@mk.com



Mulhern+Kulp project number:  
**256-21006**

project mgr: **SMK**  
drawn by: **MJF**  
issue date: **10-21-2021**

REVISIONS:



| date     | initial |
|----------|---------|
| 12/10/21 | JFP     |
| 12/20/22 | JFP     |

SMITH DOUGLAS  
HOMES

FRAMING DETAILS  
COLEMAN MODEL  
120 MPH WIND ZONE  
NORTH CAROLINA

Sheet:  
**SD2.0**

Harrington  
Lot 5




**1 GARAGE PORTAL FRAME BRACING ELEVATION**  
SCALE: N.T.S.

**2 COVERED PORCH CONNECTION DETAIL**  
SCALE: 1 1/2"=1'-0"

BOTH SIDES OF GARAGE DOOR  
120 MPH WIND SPEED (ULT)





© copyright: MULHERN + KULP  
Structural Engineering, Inc.

**MULHERN+KULP**  
RESIDENTIAL STRUCTURAL ENGINEERING  
3025 Southside Parkway, Suite 105 - Ahlsville, GA 30022  
770-777-0974 - mulhern+kulp.com

NC License # C-3825



Mulhern+Kulp project number:  
**256-2 1006**

project mgr: **SMK**  
drawn by: **MJF**  
issue date: **10-21-2021**




REVISIONS:  
date: **12/10/21** initial: **JFP**  
description: **REVISIONS ADDED**

**SMITH DOUGLAS**  
HOMES

**FRAMING DETAILS**  
**COLEMAN MODEL**  
120 MPH WIND ZONE  
NORTH CAROLINA


Sheet:  
**SD2.1**

**Harrington**  
**Lot 5**




**(B) TYPICAL GABLE END BRACING DETAIL**  
SCALE: NONE  
ROOF & GABLE END TRUSSES  
HEIGHT BETWEEN 4'-0" TO 14'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT EXCEEDS 4'-0". L BRACES NOT REQUIRED.



**(A) TYPICAL GABLE END BRACING DETAIL**  
SCALE: NONE  
ROOF & GABLE END TRUSSES  
HEIGHT UP TO 4'-0"

BRACE GABLE END TRUSSES PER ABOVE DETAIL WHEN GABLE HEIGHT IS LESS THAN 4'-0". L BRACES REQUIRED WHERE NOTED BY TRUSS MANUFACTURER.




**(C) DETAIL @ PENT ROOF**  
SCALE: 3/4"=1'-0"

LETTERED DETAILS ARE TYPICAL FOR THIS HOME & SHALL BE IMPLEMENTED IN ALL APPLICABLE AREAS. THESE DETAILS ARE NOT "CUT" ON THE PLANS.

NUMBERED DETAILS ARE PLAN SPECIFIC AND ARE ONLY REQUIRED WHERE SPECIFICALLY INDICATED ("CUT") ON THE PLANS.

THIS IS A TRUSS/COMPONENT PLACEMENT DIAGRAM (TPD) ONLY. NOT AN ENGINEERED DOCUMENT. Trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual truss design drawings (TDDs) for each truss design identified on the TPD. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the support structure including but not limited to headers, beams, walls, and columns is also the responsibility of the building designer. For general guidance regarding installation and bracing, consult "Building Component Safety Information" (BCSI) available from the SBC Association (www.sbcassociation.com). It is the responsibility of the General Contractor to verify that the provided component layout matches the final intended construction plans, loading conditions, and use. If they do not, it is the responsibility of the General Contractor to notify UFP and provide plans containing the latest specifications and designs. UFP will not be responsible for plan changes by others after final approval of shop drawings, or for errors or modifications made on-site during construction. DO NOT CUT, NOTCH, DRILL, OR OTHERWISE "REPAIR" MANUFACTURED TRUSSES IN ANY WAY WITHOUT PRIOR WRITTEN AUTHORIZATION BY A LICENSED PROFESSIONAL DESIGNATED BY UFP. The Framing is responsible to verify all dimensions, including adjusting member spacing within tolerances to allow for the drop and rise of plumbing/HVAC, unless noted otherwise. Truss-to-wall connections, if shown, are for uplift only and do not consider lateral loads. All connectors on this project are to be installed per the connector manufacturer's specifications. All connectors shown that are not truss-to-truss are suggestions only and are to be verified by the Building Designer or Engineer of Record for suitability to this particular project. UFP accepts no responsibility for the specific application or suitability of any connector that is not truss-to-truss as they apply to this specific structure.

**PLACEMENT PLAN**



| Roof Hanger List |         |                   |     |
|------------------|---------|-------------------|-----|
| MARK             | TYPE    | DESCRIPTION       | QTY |
| (A)              | HUS26   | FACE MOUNT HANGER | 8   |
| (D)              | THD26-2 | FACE MOUNT HANGER | 1   |

**COLEMAN CFI**

SCALE: N.T.S.

ROOF AREA: 1764.04 ft<sup>2</sup> RIDGE LINE: 15 ft VALLEY LINES: 40.26 HIP LINES: 140.08 **△** Indicates Left End of Truss

| REVISIONS |             | DSN |
|-----------|-------------|-----|
| DATE      | DESCRIPTION |     |
|           |             |     |
|           |             |     |
|           |             |     |
|           |             |     |
|           |             |     |

DESIGNER THATHCOCK  
LAYOUT DATE 02.24.2022  
ARCH DATE  
STRUC DATE

JOB #: 22022561

**SD COMMUNITIES**

**COLEMAN CFI (NO TRAY) RH**

**UFP SITE BUILT**  
A UFP INDUSTRIES COMPANY

Burlington, NC  
Chesapeake, VA  
Clinton, NC  
Conway, SC  
Jefferson, GA

Locust, NC  
Liberty, NC  
Ooltewah, TN  
Pearisburg, VA  
Stanfield, NC

Customer Service (800) 476-9356



This drawing is property of UFP Site Built, LLC. Any unauthorized use of this document without written permission is prohibited. UFP relinquishes ownership of delivered product upon delivery. Owner of product must obtain UFP's authorization prior to any alteration or modification of product. UFP will not be held responsible for any unauthorized modifications done or costs incurred without prior written authorization from UFP.

