DATE 08/18/23 PAGE 1 **Job Estimate** 11 **REQ. QUOTE DATE** ORDER # J0823-4373 ORDER DATE 08/15/23 **QUOTE #** 9999999999 DELIVERY DATE 11 CUSTOMER ACCT # **ROOF & FLOOR** 11 DATE OF INVOICE CUSTOMER PO # ComTech || TRUSSES & BEAMS ORDERED BY Kevin Martin **INVOICE #** Kevin Martin SALES REP Johnnie Baggett SUPERINTENDANT Reilly Road Industrial Park P.O. Box 40408 (919) 255-8130 JOBSITE PHONE # Fayetteville, N.C. 28309 (910) 864-TRUS JRB TRACKING Johnnie Baggett DESIGNER PBS JOB NAME: Lot 9 Duncan's Creek LOT # 9 SUBDIV: Duncan's Creek SOHD TAG: Hanover MODEL: Roof - Cafe/Office JOB CATEGORY: WCall - Will Call **DELIVERY INSTRUCTIONS:** то SHIP New Home Inc. SPECIAL INSTRUCTIONS: 67 Beacon Hill Road т Lillington, NC PLAN SEAL DATE:

## **ROOF TRUSSES**

PROFILE	QTY	PIT	СН		SPAN	LUN	MBER	OVER	RHANG	CANTI	LEVER	NOTES
PROFILE	PLY	TOP	BOT	ID	FT-IN-16	TOP		LEFT	RIGHT	LEFT	RIGHT	NOTES
	1	6.00	3.00	A01GE	40-07-08	2 X 6	2 X 6		00-11-00			
	5	6.00	3.00	A02	40-07-08	2 X 6	2 X 6		00-11-00			
	4	6.00	3.00	A03	40-11-00	2 X 6	2 X 6	00-11-00	00-11-00			
	4	6.00	3.00	A04	40-07-08	2 X 6	2 X 6	00-11-00				
	6	6.00	3.00	A05	40-04-00	2 X 6	2 X 6					
	1	6.00	3.00	A06GE	40-04-00	2 X 6	2 X 6					
	1	12.00	0.00	B01GE	19-11-00	2 X 6	2 X 6	00-11-00	00-11-00	05-03-08		
	1	12.00	0.00	B02	19-11-00	2 X 6	2 X 6	00-11-00	00-11-00	05-01-12		
	1 3 Ply	12.00	0.00	B03-GR	19-11-00	2 X 6	2 X 8					
	1	8.00	0.00	C01GE	10-05-00	2 X 6	2 X 6	00-11-00	00-11-00			
	5	8.00	0.00	C02	10-05-00	2 X 6	2 X 6	00-11-00	00-11-00			
	1 2 Ply	8.00	0.00	C03-GR	10-05-00	2 X 6	2 X 6					
	1	12.00	0.00	D01GE	14-11-00	2 X 6	2 X 6	00-11-00	00-11-00			
	1	8.00	0.00	G01GE	11-11-00	2 X 6	2 X 6	00-11-00	00-11-00			
$\bigwedge$	6	8.00	0.00	G02	11-11-00	2 X 6	2 X 6	00-11-00	00-11-00			
	1 2 Ply	8.00	0.00	G03-GR	11-11-00	2 X 6	2 X 6					
	2	12.00	0.00	H01GE	03-00-00	2 X 6	2 X 6	00-05-08	00-05-08			
	6	12.00	0.00	H02	03-00-00	2 X 6	2 X 6	00-05-08	00-05-08			
	1	12.00	0.00	VB1	18-09-12	2 X 4	2 X 4					
	1	12.00	0.00	VB2	16-09-12	2 X 4	2 X 4					
	1	12.00	0.00	VB3	14-09-12	2 X 4	2 X 4					
	1	12.00	0.00	VB4	12-09-12	2 X 4	2 X 4					
	1	12.00	0.00	VB5	10-09-12	2 X 4	2 X 4					
	1	12.00	0.00	VB6	08-09-12	2 X 4	2 X 4					
	1	12.00		VB7	06-09-12	2 X 4	2 X 4					
	1	12.00		VB8	04-09-12							

								DAT	E08/18/23	PAGE 2		
Jo	ob Estimate			REQ. QUOTE	DATE	11		ORDER #	J0823-43	J0823-4373		
	$\wedge$			ORDER DATE	(	08/15/23		QUOTE #				
				DELIVERY DA	TE	//		CUSTOMER ACCT #	9999999	9999		
4		OOF &	FLOOR	DATE OF INVO	DICE	11		CUSTOMER PO #				
	ComTech    TRI	USSES 8	BEAMS	SUPERINTENDANT		Kevin Martin		INVOICE #				
L						Kevin Martin		SALES REP	Johnnie	Johnnie Baggett		
	eilly Road Industrial Parl			JOBSITE PHO	NE# (	919) 255-8130						
Fo	ayetteville, N.C. 28309	9 (910) 8	64-TRUS	DESIGNER		IRB		TRACKING	Johnnie I	Baggett		
	PBS		JOB NAME:	_ot 9 Duncan's C	Creek		LOT #	LOT # 9 SUBDIV: Duncan's Creek				
SOLD			MODEL: Roo	f - Cafe/Office	ATEGORY: WCall - W	ll Call						
D HO			DELIVERY INSTRUCTIONS:									
s	New Home Inc.											
HIP FO	67 Beacon Hill Road Lillington, NC	•	SPECIAL INSTRUCTIONS: PLAN SEAL DATE:									
								I LAN O				
R	OOF TRUSSES											
P	PROFILE QTY PITCH	ID	SPAN	LUMBER	OVERHAN	G CANTILEVER		NOTES				

PROFILE	PLY	TOP	BOT	שו	FT-IN-16	TOP	BOT	LEFT	RIGHT	LEFT	RIGHT	NOTES
	1	12.00	0.00	VB9	02-09-12	2 X 4	2 X 4					
	1	8.00	0.00	VC1	08-01-03	2 X 4	2 X 4					
$\bigtriangleup$	1	8.00	0.00	VC2	05-01-03	2 X 4	2 X 4					
	1	8.00	0.00	VC3	02-01-03	2 X 4	2 X 4					
	1	8.00	0.00	VG1	09-01-15	2 X 4	2 X 4					
	1	8.00	0.00	VG2	06-01-15	2 X 4	2 X 4					
	1	8.00	0.00	VG3	03-01-15	2 X 4	2 X 4					
	2	12.00	0.00	VH1	03-11-00	2 X 4	2 X 4					
	2	12.00	0.00	VH2	02-03-14	2 X 4	2 X 4					
	1	Truss Drawings With B-1 and B-3 Bracing And Handling Instructions (Included in truss price)										

## ITEMS

## QTY ITEM TYPE SIZE LENGTH FT-IN-16 PART NUMBER NOTES 20 Hangers, USP HUS 26 SIMPSON (HUS26) ITEMS SUB-TOTAL: \$ 54.40

Please examine this quote, as we agree to furnish at the Prices quoted are valid for jobs released for production w Additional design time made necessary by incorrect found This estimate includes sealed engineering of individual tr will be billed in quarter hour increments as costs are included	SUB-TOTAL	\$8,191.78		
ACCEPTED BY SELLER				
BY:	PURCHASER:		SALES TAX 7.00%	\$573.42
TITLE:	BY:		GRAND TOTAL	\$8765.20
DATE OF ACCEPTANCE:	ADDRESS:			
	PHONE:	DATE:		

**WARNING:**As part of this proposal, we warn that trusses can be dangerous and cause property damage or personal injury if improperly installed and / or braced. Customer acceptance hereof shall constitute his affirmative representation to us that he is trained in the proper and safe methods of truss installation and bracing, and will use such methods. Customer acknowledges receipt of instructional pamphlet entitle: 'Bracing Wood Trusses: Commentary and recommendations', HIB-91, as published by the Truss Plate Institute, Inc., and also the engineering drawings showing the required lateral bracing. By his acceptance, Customer agrees, for himself, his agents and employees, to hold Comtech Inc. harmless from any and all actions for property damage, personal injury, or wrongful death resulting from improper installation and / or bracing during erection of the trusses comprehended hereby.

ROOF SUB-TOTAL: \$ 8,137.38