


Project: Address: 9/21/2023

Input by: Curtis Quick Job Name: Holly Beams Page 1 of 6

Project #:

1.750" X 14.000" 2-Ply - PASSED **Kerto-S LVL GDH** 

Level: Level



Member Infor	mation			Rea	ctions UNP	ATTERN	NED IL	(Uplift)			
Type:	Girder	Application:	Floor	Brg	Direction	Live	;	Dead	Snow	Wind	Const
Plies:	2	Design Method:	ASD	1	Vertical	0	)	2457	0	0	0
Moisture Conditio	n: Dry	Building Code:	IRC 2018	2	Vertical	0	)	2457	0	0	0
Deflection LL:	480	Load Sharing:	No								
Deflection TL:	360	Deck:	Not Checked								
Importance:	Normal - II										
Temperature:	Temp <= 100°F										
				Bea	rings						
				Bea	aring Length	Dir.	Сар.	React D/L lb	Total	Ld. Case	Ld. Comb.
				1 -	SPF 3.500"	Vert	47%	2457 / 0	2457	Uniform	D
				2 -	SPF 3.500"	Vert	47%	2457 / 0	2457	Uniform	D

### Analysis Results

_						
Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	11011 ft-lb	9'5"	24299 ft-lb	0.453 (45%)	D	Uniform
Unbraced	11011 ft-lb	9'5"	11036 ft-lb	0.998 (100%)	D	Uniform
Shear	2089 lb	1'5 1/2"	9408 lb	0.222 (22%)	D	Uniform
LL Defl inch	0.000 (L/999)	0	999.000 (L/0)	0.000 (0%)		
TL Defl inch	0.444 (L/497)	9'5 1/16"	0.612 (L/360)	0.725 (72%)	D	Uniform

### **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 9'7 7/16" o.c.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	250 PLF	0 PLF	0 PLF	0 PLF	0 PLF	
	Self Weight				11 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- LVL beams must not be cut or drilled
  Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
  2 Damaged Beams must not be used

Handling & Installation

- Danaged Beams must not be used
  Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

•	
isDesign	

Project: Address: Date: 9/21/2023 Input by: Curtis Quick

Job Name: Holly Beams

Level: Level


Page 2 of 6

Project #:

Kerto-S LVL **GDH** 

1.750" X 14.000"

2-Ply - PASSED



# Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

1 3		
Capacity	0.0 %	
Load	0.0 PLF	
Yield Limit per Foot	245.6 PLF	
Yield Limit per Fastener	81.9 lb.	
Yield Mode	IV	
Edge Distance	1 1/2"	
Min. End Distance	3"	
Load Combination		
Duration Factor	1.00	

# Notes

NOtes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

# Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851

Manufacturer Info

(800) 622-5850 www.metsawood.com/us



Project: Address: Date: 9/21/2023

Input by: Curtis Quick Job Name: Holly Beams

Project #:

1.750" X 9.250" 2-Ply - PASSED Kerto-S LVL BM1

Application:

Design Method:

**Building Code:** 

Load Sharing:

Deck:


ASD


No

IRC 2018

Not Checked

Level: Level





Page 3 of 6

### **Member Information**

Type: Plies: Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II

Temperature: Temp <= 100°F

# Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	0	1791	1768	0	0
2	Vertical	0	1791	1768	0	0

# **Bearings**

Bearing	Length	Dir.	Сар.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	3.500"	Vert	68%	1791 / 1768	3559	L	D+S
2 - SPF	3.500"	Vert	68%	1791 / 1768	3559	L	D+S

### **Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	5070 ft-lb	3'3 1/2"	14423 ft-lb	0.352 (35%)	D+S	L
Unbraced	5070 ft-lb	3'3 1/2"	10451 ft-lb	0.485 (49%)	D+S	L
Shear	2416 lb	1' 3/4"	7943 lb	0.304 (30%)	D+S	L
LL Defl inch	0.046 (L/1605)	3'3 1/2"	0.153 (L/480)	0.299 (30%)	S	L
TL Defl inch	0.092 (L/797)	3'3 1/2"	0.204 (L/360)	0.452 (45%)	D+S	L

# **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	537 PLF	0 PLF	537 PLF	0 PLF	0 PLF	A2
	Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used
- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

ersion.	21.80.417	Powered	hν	iStruct™	Dataset:	2308210	)1.	1447

۷		
1	isDesign	

Project: Address: Date: 9/21/2023 Input by: Curtis Quick

Job Name: Holly Beams


Project #:


Kerto-S LVL BM<sub>1</sub>

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 4 of 6

# Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

### Notes

NOtes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation
- - - This design is valid until 11/3/2024

6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850

Manufacturer Info

www.metsawood.com/us



Project: Address: Date: 9/21/2023 Input by: Curtis Quick

Job Name: Holly Beams


Project #:


Kerto-S LVL BM<sub>2</sub>

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 5 of 6

### **Member Information**

Type: Plies: Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal - II Temperature:

Application: Design Method: ASD **Building Code:** IRC 2018 Load Sharing: No

Deck: Not Checked

## Reactions UNPATTERNED Ib (Uplift)

Brg	Direction	Live	Dead	Snow	Wind	Const
1	Vertical	46	1604	1563	0	0
2	Vertical	114	682	615	0	0

# **Bearings**

Bearing	Length	Dir.	Cap. F	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	3.500"	Vert	61%	1604 / 1563	3167	L	D+S
2 - SPF	3.500"	Vert	25%	682 / 615	1297	L	D+S

### **Analysis Results**

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4864 ft-lb	2'6 1/2"	14423 ft-lb	0.337 (34%)	D+S	L
Unbraced	4864 ft-lb	2'6 1/2"	10370 ft-lb	0.469 (47%)	D+S	L
Shear	2417 lb	1' 3/4"	7943 lb	0.304 (30%)	D+S	L
LL Defl inch	0.036 (L/2054)	2'9 7/8"	0.155 (L/480)	0.234 (23%)	S	L
TL Defl inch	0.074 (L/1007)	2'10 1/16"	0.207 (L/360)	0.358 (36%)	D+S	L

# **Design Notes**

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.

Temp <= 100°F

- 6 Top must be laterally braced at end bearings.
- 7 Bottom must be laterally braced at end bearings.
- 8 Lateral slenderness ratio based on single ply width.

o Eateral sichaerness ratio based on single pry wath.										
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Point	0-7-4		Тор	629 lb	0 lb	629 lb	0 lb	0 lb	B2
	Bearing Length	0-3-8								
2	Point	2-6-8		Тор	1549 lb	0 lb	1549 lb	0 lb	0 lb	B2A
	Bearing Length	0-3-8								
3	Part. Uniform	2-8-0 to 6-8-0		Тор	15 PLF	40 PLF	0 PLF	0 PLF	0 PLF	Floor
	Self Weight				7 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used

Handling & Installation

- Design assumes top edge is laterally restrained
  Provide lateral support at bearing points to avoid
  lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Manufacturer Info Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Version 21.80.417 Powered by iStruct™ Dataset: 23082101.1447



٩	
1	isDesign

Project: Address:

Date: 9/21/2023

Input by: Curtis Quick Job Name: Holly Beams


Project #:


Kerto-S LVL BM<sub>2</sub>

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 6 of 6

# Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6".

Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

### Notes

NOtes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
   LVL not to be treated with fire retardant or corrosive

# Handling & Installation

- Handling & Installation

  1. UVI beams must not be cut or drilled

  2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

  3. Damaged Beams must not be used

  4. Design assumes top edge is laterally restrained

  5. Provide lateral support at bearing points to avoid lateral displacement and rotation

- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851

(800) 622-5850 www.metsawood.com/us

Manufacturer Info