

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 2301282-05935
178 BIRCHWOOD GROVE

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by 84 Components - #2383.

Pages or sheets covered by this seal: I62336986 thru I62336986

My license renewal date for the state of North Carolina is December 31, 2023.

North Carolina COA: C-0844



December 4, 2023

Gilbert, Eric


IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job 2301282-05935	Truss A1G	Truss Type Hip Girder	Qty 1	Ply 4	178 BIRCHWOOD GROVE Job Reference (optional)	162336986
----------------------	--------------	--------------------------	----------	----------	---	-----------

84 Components (Dunn, NC), Dunn, NC - 28334,

Run: 8.73 S Nov 13 2023 Print: 8.730 S Nov 13 2023 MiTek Industries, Inc. Mon Dec 04 08:16:41
ID:g_Cc8ZRDxQ?JgR7?yPykz_yuVXn-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWRcDoi7J4zJC?f

Page: 1




Scale = 1:77.2

Plate Offsets (X, Y): [6:0-5-4,0-3-4], [10:0-7-0,0-2-12], [16:0-3-8,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI	DEFL	in (loc)	l/defl	L/d	PLATES	GRIP		
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.38	Vert(LL)	-0.46	18-19	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.94	Vert(CT)	-0.84	18-19	>615	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.79	Horz(CT)	0.10	12	n/a	n/a		
BCLL	0.0*	Code	IRC2021/TPI2014	Matrix-MS								
BCDL	10.0											
											Weight: 1137 lb FT = 20%	

- LUMBER**
- TOP CHORD 2x6 SP No.2 2) n/a
- BOT CHORD 2x6 SP No.2 3) n/a
- WEBS 2x4 SP No.3 *Except* 22-3:2x4 SP No.2 4) 4-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Web connected as follows: 2x4 - 1 rows staggered at 0-9-0 oc., Except member 7-18 2x4 - 2 rows staggered at 0-4-0 oc.
Attach BC w/ 1/2" diam. bolts (ASTM A-307) in the center of the member w/washers at 4-0-0 oc.
- BRACING**
- TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 6-10.
- BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
- REACTIONS** (size) 2=0-3-8, 12=0-3-8
Max Horiz 2=76 (LC 20)
Max Uplift 2=-321 (LC 12), 12=-597 (LC 13)
Max Grav 2=2564 (LC 45), 12=3713 (LC 24)
- FORCES** (lb) - Maximum Compression/Maximum Tension
- TOP CHORD 1-2=0/19, 2-3=-6350/1130, 3-4=-6082/1120, 4-5=-6064/1123, 5-6=-9809/1730, 6-7=-18500/3011, 7-9=-18500/3011, 9-10=-15331/2469, 10-11=-9615/1575, 11-12=-7994/1344, 12-13=0/19
- BOT CHORD 2-23=-1006/5936, 22-23=-1006/5936, 20-22=-1524/9298, 19-20=-2709/16457, 18-19=-2704/16459, 16-18=-2377/15331, 15-16=-1427/9210, 14-15=-1204/7403, 12-14=-1204/7403
- WEBS 6-19=0/138, 6-18=-549/2393, 7-18=-594/180, 9-18=-612/3451, 9-16=-2029/495, 10-16=-1010/6512, 10-15=0/173, 3-23=-101/117, 3-22=-446/270, 4-22=-559/3422, 5-22=-4836/850, 5-20=-620/4152, 6-20=-8419/1356, 11-15=-247/1955, 11-14=-633/111
- NOTES**
- 1) n/a
- 10) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
- 11) Provide adequate drainage to prevent water ponding.
- 12) All plates are 4x6 MT20 unless otherwise indicated.
- 13) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 14) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 1-00-00 wide will fit between the bottom chord and any other members.
- 15) All bearings are assumed to be SP No.2 .
- 16) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 321 lb uplift at joint 2 and 597 lb uplift at joint 12.
- 17) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 18) Use Simpson Strong-Tie HHUS26-2 (14-10d Girder, 4-10d Truss) or equivalent at 26-1-8 from the left end to connect truss(es) to back face of bottom chord.



December 4, 2023

Continued on page 2

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPHI Quality Criteria and DSB-22 available from Truss Plate Institute (www.tpinst.org) and BCSI Building Component Safety Information available from the Structural Building Component Association (www.sbcacomponents.com)

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job 2301282-05935	Truss A1G	Truss Type Hip Girder	Qty 1	Ply 4	178 BIRCHWOOD GROVE Job Reference (optional)	I62336986
----------------------	--------------	--------------------------	----------	-----------------	---	-----------

84 Components (Dunn, NC), Dunn, NC - 28334,

Run: 8.73 S Nov 13 2023 Print: 8.730 S Nov 13 2023 MiTek Industries, Inc. Mon Dec 04 08:16:41
ID:gC_c8ZRDxQ?JgR7?xPykz_yuVXn-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrcDoi7J4zJC?f

Page: 2

- 19) Use Simpson Strong-Tie LUS24 (4-10d Girder, 2-10d Truss, Single Ply Girder) or equivalent at 38-2-4 from the left end to connect truss(es) to back face of bottom chord, skewed 0.0 deg.to the right, sloping 0.0 deg. down.
- 20) Fill all nail holes where hanger is in contact with lumber.
- 21) "NAILED" indicates 3-10d (0.148"x3") or 3-12d (0.148"x3.25") toe-nails per NDS guidelines.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-4=-60, 4-6=-60, 6-10=-60, 10-13=-60, 24-27=-20
Concentrated Loads (lb)
Vert: 18=-1261 (B), 11=-67 (B), 14=-154 (B), 33=-144 (B), 36=-144 (B), 38=-144 (B), 39=-144 (B), 40=-144 (B), 43=-62 (B), 44=-62 (B), 45=-62 (B), 46=-62 (B), 47=-62 (B), 48=-232 (B)

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 1/2/2023 BEFORE USE.


Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TP1 Quality Criteria and DSB-22** available from Truss Plate Institute (www.tpinst.org) and **BCSI Building Component Safety Information** available from the Structural Building Component Association (www.sbcacomponents.com)




818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.


* Plate location details available in MITek software or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number/letter where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TP1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-22: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing, Restraining & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8 dimensions shown in ft-in-sixteenths (Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

Product Code Approvals

ICC-ES Reports:

ESR-1988, ESR-2362, ESR-2685, ESR-3282
ESR-4722, ESL-1388

Design General Notes

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TP1 section 6.3. These truss designs rely on lumber values established by others.

© 2023 MITek® All Rights Reserved

MITek

ENGINEERING BY
TRENGO
A MITek Affiliate

MITek Engineering Reference Sheet: MIL-7473 rev. 1/2/2023

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability/bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TP1 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TP1 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TP1 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.