

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BLAKE POND

LOT 91

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR: APPROVED 25% REDUCTION  
*pump to*

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION PC 90/91

NO. BEDROOMS: 4

LTAR 0.3 GPD/FT<sup>2</sup>

SEPTIC TANK SIZE: 1000

PUMP TANK SIZE:

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

INITIAL SYSTEM

1	P	103.00	100'
2	Y	102.92	100'
3	P	102.75	100'
4	Y	102.58	100'
			<u>400'</u>

5	P	100.67	100'
6	Y	100.58	100'
7	P	100.50	100'
8	Y	100.42	100'
			<u>400'</u>

BY: M EAKER

DATE 12/2022

TYPICAL PROFILE

0-12 US (VF<sub>r</sub>, wa<sub>r</sub>)  
12-48 SCL (F<sub>i</sub>, sh<sub>k</sub>)  
cr > 48"  
INSTALL AT 18-24"

**THERE SHALL BE NO GRADING,  
 CUTTING, LOGGING OR OTHER SOIL  
 DISTURBANCE IN SEPTIC AREA**

HEALTH DEPARTMENT USE ONLY.  
 DESIGNS DO NOT GUARANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email mike@southeasternsoil.com

