

Client: Project: Address:

9/13/2023 Input by: Neal Baggett

Job Name: 57 LIBERTY MEADOWS

Page 1 of 6

Wind

Total Ld. Case

5376 L

8765 L

0

0

Const

Ld. Comb. D+0.75(L+S)

D+0.75(L+S)

0

0

Dead

3202

5170

3202 / 2173

5170 / 3596

Snow


1984

3282

Project #:

1.750" X 24.000" 2-Ply - PASSED **Kerto-S LVL BM2**

Level: Level



Member Information Reactions UNPATTERNED Ib (Uplift) Type: Application: Floor Brg Direction Live Plies: 2 Design Method: ASD Vertical 914 1 Moisture Condition: Dry **Building Code: IBC/IRC 2015** 2 Vertical 1512 Deflection LL: 480 Load Sharing: No Deflection TL: 360 Deck: Not Checked Importance: Normal - II Temp <= 100°F Temperature: **Bearings** Bearing Length Dir. Cap. React D/L lb 1 - SPF 3.500" Vert

Analysis R	esults
------------	--------

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	41750 ft-lb	11'1"	84163 ft-lb	0.496 (50%)	D+0.75(L+S)	L
Unbraced	41750 ft-lb	11'1"	42041 ft-lb	0.993 (99%)	D+0.75(L+S)	L
Shear	6786 lb	18'9"	20608 lb	0.329 (33%)	D+0.75(L+S)	L
LL Defl inch	0.182 (L/1360)	10'9 1/8"	0.515 (L/480)	0.353 (35%)	0.75(L+S)	L
TL Defl inch	0.444 (L/557)	10'9"	0.687 (L/360)	0.647 (65%)	D+0.75(L+S)	L

Design Notes

- 1 Provide support to prevent lateral movement and rotation at the end bearings. Lateral support may also be required at the interior bearings by the building code.
- 2 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 3 Refer to last page of calculations for fasteners required for specified loads.
- 4 Girders are designed to be supported on the bottom edge only.
- 5 Top loads must be supported equally by all plies.
- 6 Top must be laterally braced at a maximum of 4'2 1/4" o.c.
- 7 Bottom must be laterally braced at end bearings.

8 Lateral slenderness ratio based on single ply width.											
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments	
1	Part. Uniform	5-1-0 to 21-0-8		Near Face	50 PLF	152 PLF	0 PLF	0 PLF	0 PLF	F1	
2	Part. Uniform	5-1-0 to 21-0-8		Тор	330 PLF	0 PLF	330 PLF	0 PLF	0 PLF	ATRUSSES	
3	Part. Uniform	5-1-0 to 21-0-8		Тор	120 PLF	0 PLF	0 PLF	0 PLF	0 PLF	WALL	
	Self Weight				19 PLF						

End Grain

End Grain

2 - SPF 3.500"

Vert

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- approvals

 Damaged Beams must not be used
- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 11/3/2024

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS





isDesign

Client: Project: Address: Date: 9/13/2023 Input by: Neal Baggett

Job Name: 57 LIBERTY MEADOWS

Page 2 of 6


Project #:

Kerto-S LVL BM₂

1.750" X 24.000"

2-Ply - PASSED

Level: Level



Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c., Maximum end distance not to exceed 6".

		,	,
Capacity	41.1 %		
Load	101.0 PLF		
Yield Limit per Foot	245.6 PLF		
Yield Limit per Fastener	81.9 lb.		
Yield Mode	IV		
Edge Distance	1 1/2"		
Min. End Distance	3"		
Load Combination	D+L		
Duration Factor	1.00		

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

Handling & Installation

1. UVI beams must not be cut or drilled

2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

3. Damaged Beams must not be used

4. Design assumes top edge is laterally restrained

5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



