

### Central Carolina Soil Consulting, PLLC

1900 South Main Street, Suite 110, Wake Forest, NC 27587 Office Number: 919-569-6704

Acknowledgment of Subsurface wastewater evaluation and septic design by Central Carolina Soil Consulting, PLLC. for Cotton Farms, Lot 10 (PIN: 0643-35-5902), for issuance of an IP and CA.

For Improvement Permit (IP) issuance:

"The LSS/LG evaluation(s) attached to this application is to be used to issue an Improvement Permit in accordance with G.S. 130A-335(a2) and (a3)."

For Construction Authorization (CA) issuance:

"The plans or evaluations attached to this application are to be used to issue a Construction Authorization in accordance with G.S. 130A-335(a2), (a5) and (a6)."

The LSS evaluation attached to this application was used to produce and design a subsurface wastewater septic system for permitting to obtain an IP and CA in accordance G.S. 130A-335(a2), (a3), (a5) and (a6).

Owner: Ken Harrey Homes, LLC
Owner's representative: Andy Beair D

Date:

Permit #:	



**ROY COOPER • Governor** 

KODY H. KINSLEY • Secretary

MARK BENTON • Deputy Secretary for Health

**SUSAN KANSAGRA** • Assistant Secretary for Public Health

Division of Public Health

Submittal Includes:	(a2) Improvement Permit	(a2) Construction Authorization	Fee \$	
	IMPROVEM	ENT PERMIT FOR G.S. 130A-33	5(a2)	
County:		<u> </u>		
PIN/Lot Identifier:				
Issued To:				
Property Location:				
Subdivision (if applical	ole)	Lot #:	Block:	Section:
LSS Report Provided:	Yes No No			
If yes, name and licens	se number of LSS:			
New	Expansion	System Relocation	Change of Use	
Proposed Structure: _				
Number of bedrooms:	Number of Occupants:	Other:		
Design Wastewater St	rength:  domestic	high strength industr	ial process	
Proposed Design Daily	Flow: GPD	Proposed LTAR (Initial): P	roposed LTAR (Repair):	,
Proposed Wastewater	System Type*:	(Initial) Pump Re	quired: Yes No	☐ May be required
Proposed Wastewater	System Type*:	(Repair) Pump Re	quired: Yes No	May be required
*Please include systen	n classification for proposed wastew	ater system types in accordance with 15A	NCAC 18A .1961 Table V	((a)
Saprolite System (initia	al):  Yes  No Saprolite	e System (repair): 🔲 Yes 🔲 No		
Fill System (Initial):	Yes No If yes, specify: Ne	w   Existing (when adding more than	6 inches of fill to system	area provide a fill plan)
Fill System (repair):	Yes No If yes, specify: Ne	w Existing (when adding more than	6 inches of fill to system	n area provide a fill plan
Usable Soil Depth (Init	ial): Usable S	oil Depth (Repair):		
Max. Trench Depth (In	itial)‡: Max. Tre	nch Depth (Repair)‡:	‡ Measured on the dow	nhill side of the trench
Artificial Drainage Req	uired: Yes No If yes, pleas	e specify details:		
Type of Water Supply:	Private well Public well	Shared well Municipal Supply	Spring Othe	r:
Drainfield location me	ets requirements of Rule .1945: Yes	No Drainfield location meets	requirements of Rule .1	950: Yes No No
Permit valid for: 🔲 Fi	ve years [site plan submitted pursua	nt to GS 130A-334(13a)] No expiration	on [plat submitted pursu	ant to GS 130A-334(7a)
Permit conditions:				
		100 May		
		SOIL		
		16 AND	CAR	
Licensed Soil Scientist		W R SWIE		
Licensed Soil Scientist			Pate:	
	The LSS evaluation is being submit	ted pursuant to and meets the requirement	nts of 6.5. 130A 335(a2	2).

NC DEPARTMENT OF HEALTH AND HUMAN SERVICES DIVISION OF PUBLIC HEALTH

\*See attached site sketch

LOCATION: 5605 Six Forks Road, Building 3, Raleigh, NC 27609
MAILING ADDRESS: 1632 Mail Service Center, Raleigh, NC 27699-1632
www.ncdhhs.gov • TEL: 919-707-5854 FAX: 919-845-3972

AN EQUAL OPPORTUNITY / AFFIRMATIVE ACTION EMPLOYER



## This Section for Local Health Department Use Only

Initial submittal received:	 Date	by Initials	
G.S. 130A-335(a3) states the following:			
When an applicant for an Improvement Permit submits to a local health department department, the common form developed by the Department, and a soil evaluation within five business days of receiving the application, conduct a completeness review for mithin five business days of receiving the application, conduct a completeness review for mithin includes all of the required components. If the local health department detected the improvement of the improvement department to cure the deficiencies in the Improvement Permit. The local health described the second set out in this subsection, the applicant may treat the failure common form for use as the Improvement Permit.	n pursuant to subsection  on of the submittal. A content of the submittal in the Improvite of the submittal in the Improvite of the submitter	on (a2) of this section, the local had termination of completeness me vement Permit is incomplete, the may submit additional information as to whether from the applicant. If the local	nealth department shall, neans that the Improvement to local health department tion to the local health the the Improvement Permit health department fails to
The review for completeness of this Improvement Permit was con Permit is determined to be:	iducted in accorda	nce with G.S. 130A-335(a3	3). This Improvement
☐ Incomplete (If box is checked, information in this section is re-	quired.)		
The following items are missing:			
	2		
Copies of this were sent to the LSS and the Applicant on	Date		
State Authorized Agent:		Date:	
☐ Complete			
State Authorized Agent:	1	Date:	
This Improvement Permit is issued pursuant to G.S. 130A-335 (as attached here. The issuance of this permit by the Health Depart permit holder is responsible for checking with appropriate gover to revocation if the site plan, plat, or the intended use changes. Downership of the site. This permit is subject to compliance with Disposal and to the conditions of this permit.  The Department, the Department's authorized agents, and the locations of the site of the	ment in no way gu ning bodies in me The Improvement the provisions of ocal health depart	uarantees the issuance of eting their requirements. t Permit shall not be affec the Laws and Rules for Se ments shall be discharged	other permits. The This permit is subject cted by a change in wage Treatment and
any liabilities, duties, and responsibilities imposed by statute or evaluations, submittals, or actions from a licensed soil scientist of the second scientist scientists.	or licensed geolog	-	
mprovement Permit Expiration Date:			

\*See attached site sketch\*



Permit #:	

## **Re-submittal of Improvement Permit**

ſ				
	LHD USE ONLY: This IP resubmittal received: _		by	
		Date	Initials	
The following it	tems are being resubmitted pursuant to G.S. 130A-3	35(a3) for issuance	of the Improvement Permit:	
	, ST	ATE	dh.	
is accurate and o	hereby attest the complete to the best of my knowledge and that the laws, regulations, rules, and ordinances.		required to be included with ment Permit meets all applic	
Signature	e of Licensed Soil Scientist		Date	
	The section below is for Local Health Department (	use after submittal of	items noted as missing above.	
LHD Follow-u	up Completeness Review of Improvement	Permit		
	completeness of this Improvement Permit re-subm ermit is determined to be:	ittal was conducted	in accordance with G.S. 130	4-335(a3). This
☐ Incomplete	(If box is checked, information in this section is req	quired.)		
The following ite	ems are missing:			
		UVI V		
Copies of this w	ere sent to the LSS and the Applicant on	ate		
State Authorized	d Agent:		Date:	
☐ Complete				
State Authorized	d Agent:		Date:	



### Central Carolina Soil Consulting, PLLC

1900 South Main Street, Suite 110, Wake Forest, NC 27587 Office Number: 919-569-6704

> July 12, 2023 Job #4610

Ken Harvey Homes
Attention: Andy Beaird
4909 Unicon Drive, Suite 107
Wake Forest, NC 27587

RE: Preliminary soil/site evaluation for single family wastewater approval at Cotton Farms Subdivision, Lot 10 (4-bedroom) in Harnett County pursuant to and meets the requirements of G.S. 130A-335(a2)."

Dear Mr. Beaird:

Central Carolina Soil Consulting, PLLC conducted a preliminary soil evaluation on the aforementioned lot to determine the areas of provisionally suitable soils that are suitable for subsurface wastewater disposal systems (conventional, Accepted & Innovative). "The LSS evaluation is being submitted pursuant to and meets the requirements of G.S. 130A-335(a2)." The soil/site evaluation was performed using a hand auger in June 2023, under moist soil conditions, based on the criteria found in the State Subsurface Rules, 15ANCAC 18A .1900 "Laws and Rules for Sewage Treatment and Disposal Systems". From this evaluation, CCSC laid out and located the septic layout and gps'd for site plan drawing purposes. Please note that the lot lines must be clearly marked by your surveyor prior to system installation by your installer to verify all setbacks before digging.

The lot is proposed to have a 4-bedroom system for the house, per an Engineered Flow-Reduction. A septic system field layout was completed based on the house location and property lines surveyed in the field.

The proposed Initial system for the house is a Pressure Manifold distribution using lines 3-5 totaling 345 feet of accepted product (EZ-Flow). The repair field is a Pressure Manifold distribution using lines 1-2 & 6-7 totaling 205 feet of T&J Panel Block product (horizontal). The septic and pump tanks for the house should be minimum 1,000 gallons each with risers. The septic and pump tanks should also have pressed in rubber boots on both the inlets and the outlets of the tanks.

Based on the findings during the field evaluation, the area on the attached map has at least 44 inches (initial) and 32 inches (repair) of provisionally suitable soils for a modified conventional septic system. The assigned LTAR for the site is 0.3 gal/day/ft² with a maximum depth of 24 inches for the initial system installation of the drain lines due to slope correction. The assigned LTAR for the site is 0.35 gal/day/ft² with a maximum depth of 16 inches with 6" of additional cover for the repair system installation of the drain lines due to slope correction.

#### Septic Installation:

The septic system for the lot should be installed during dry soil conditions (no rain events within 72 hours). The septic system should be installed on contour while maintaining all required setbacks.

Setbacks: (see septic design page for locations)

- Septic and Pump Tanks (see septic design)
  - o 10' minimum from property lines
  - o 5' minimum from house
- Septic Lines (see septic design)
  - o 10' minimum from property lines
  - o 5' minimum from house
- Manifold's and D-Box's (see septic design)
  - o 10' minimum from property lines
- Supply Lines (see septic design)
  - o 5' minimum from property lines

#### Grading:

No grading should be completed within the initial and repair septic areas that change the natural grade of the area. There should be no cutting or filling within the septic areas as well. When grading the lot, no cuts of 2' or greater should be within 15' of the septic areas. If a cut is required near the septic area, keep the cut around 6-8 inches in depth.

#### HOUSE:

- Initial System: Pressure Manifold, lines 3-5 totaling 345' (see layout)
- Repair System: Pressure Manifold, lines 1-2 & 6-7 totaling 205' (see layout)
- 360 gal/day flow rate (4-bedroom)
- 1,000 gallon septic and pump tanks with risers and pressed in rubber boots on both the inlet and outlet ends
- 24" maximum trench depth (Initial)
- 16" maximum trench depth with 6" of additional cover (Repair)
- 0.3 LTAR for Initial, 0.35 LTAR for Repair
- No grading/filling septic areas
- No cuts >2' within 15' of septic areas
- Keep tanks and drain lines 10' from property lines
- Keep supply line >5' property lines
- Install in dry soil conditions (No rain events within 72 hours)
- Maintain natural contours when clearing the lot

This letter discusses the location of provisionally suitable soils for subsurface wastewater disposal systems and does not guarantee the future function of any wastewater system on sites. Central Carolina Soil Consulting, PLLC is a professional consulting firm specializing in soil delineations and design for on-site wastewater disposal systems.

If you have any questions regarding the findings on the attached map or in this report, please feel free to contact me at any time. Thank you for allowing Central Carolina Soil Consulting to perform this site evaluation for you.

Sincerely.

Jason Hall

NC Licensed Soil Scientist #1248 AOWE certification number 10004E

Encl: Soil Map & septic layout

Sheet:

Property ID: 0643-35-5902

Lot #: 10 File #: AppID:

## CCSC SOIL/SITE EVALUATION for ON-SITE WASTEWATER SYSTEM

Owner: Ken Harvey Homes LLC Applicant:

Address: 4909 Unicon Drive, Suite 107, Wake Forest, NC 27587

Proposed Facility: 4-Bedroom

Design Flow (.1949): 360 gal/day per engineered flow-red.

Property Size: 0.58 acres

Location of Site: Cotton Farms, Lot 10 (218 Hook Drive, Fuquay-Varina, NC)

Property Recorded:

Water Supply: [X] Public [1] Individual [1] Well [1] Spring [1] Other

Evaluation Method: [X] Auger Boring [] Pit [] Cut

Type of Wastewater: [X] Sewage [] Industrial Process [] Mixed

P R O F			SOIL	MORPHOLOGY .1941		b E FACTO	RS		
L E #	.1940 Landscape Position/ Slope%	Horizon Depth (IN.)	.1941 Texture/ Structure	.1941 Consistence Mineralogy	.1942 Soil Wetness/ Color	.1943 Soil Depth (IN.)	.1956 Sapro Class	.1944 Restr Horiz	Profile Class & LTAR
1	~10%	A, 0-4	SL, GR	VFR, NS, NP					
		Bt1, 4-10	SCL, SBK	FR, SS, SP, SEXP					
		Bt2, 10-36	C, SBK	FI, SS, SP, SEXP		PS			PS, 0.3
		BC, 36-45	CL, SBK	FR, SS, SP, SEXP		PS			PS, 0.3
		C, 45-48	L, GR	FR, NS, NP		UN			UN
2	~5%	A, 0-5	SL, GR	VFR, NS, NP					
		B, 5-22	SL, GR	VFR, NS, NP		PS			PS, 0.4
		Bt, 22-45	SCL, SBK	FR, SS, SP, SEXP		PS			PS, 0.35
					auger restrictive @ 45"				
3	~10%	A, 0-9	SL, GR	VFR, NS, NP					
		B, 9-27	SL, GR	VFR, NS, NP		PS			PS, 0.4
		Bt1, 27-44	SCL, SBK	FR, SS, SP, SEXP		PS			PS, 0.35
		Bt2, 44-48	SCL, SBK	FR, SS, SP, SEXP	10YR 7/2	UN			UN
4	~10%	A, 0-9	SL, GR	VFR, NS, NP					
		B, 9-24	SL, GR	FR, NS, NP		PS			PS, 0.4
		Bt, 24-30	SCL, SBK	FR, SS, SP, SEXP		PS			PS, 0.35
					auger restrictive @ 30"				

Description	Initial System	Repair System
Available Space (.1945)	Yes	Yes
System Type(s)	Accepted	T&J Panel Block
Site LTAR	0.3	0.3

Other Factors (.1946):

Soil Evaluation By: Jason Hall

Others Present: James Rice

Site Classification (.1948): Provisionally Suitable


Site Evaluation By: Others Present:

COMMENTS: Sheet: FILE #:

Landscape Position	Group	<u>Texture</u>	.1955 LTAR	Structure
R-Ridge	1	S-Sand	1.2 - 0.8	SG-Single Grain
SS-Shoulder Slope		LS-Loamy Sand		M-Massive
LS-Linear Slope				CR-Crumb
FS-Foot Slope	II	SL-Sandy Loam	0.8 - 0.6	GR-Granular
NS-Nose Slope		L-Loam		SBK-Subangular Blocky
HS-Head Slope				ABK-Angular Blocky
CC-Concave Slope	III	SI-Silt	0.6 - 0.3	PL-Platy
CV-Convex Slope		SICL-Silty Clay		PR-Prismatic
T-Terrace		Loam		
FP-Flood Plain		CL-Clay Loam		
		SCL-Sandy Clay		
		Loam		
	IV	SC-Sandy Clay	0.4 - 0.1	
		SIC-Silty Clay		
		C-Clay		

Consistence	Consistence	<u>Mineralogy</u>
Moist	Wet	SEXP-Slightly Expansive
VFR-Very Friable	NS-Non-Sticky	EXP-Expansive
FR-Friable	SS-Slightly Sticky	
FI-Firm	S-Sticky	
VFI-Very Firm	VS-Very Sticky	
EFI-Extremely Firm	NP-Non-Plastic	
	SP-Slightly Plastic	
	P-Plastic	
	VP-Very Plastic	

**Sketch of Soil Evaluation Locations** 



# **HOOK DRIVE**


50' PUBLIC R/W & UTILITY



- \*Keep tanks and drain lines 10' from property lines.
- \*Not a survey.
- \*Not a guarantee of a septic permit.
- \*Keep supply lines >5' from property lines.
- \*Some lines are flagged longer in the field than lengths indicate.
- \*No grading septic area.
- \*No adding soil within septic area
- \*No rutting—up septic area
- \*No cuts of >2' within 15' of septic areas

System and Repair Area:

- $\sim 7,000 \text{ ft}^2$
- 0.3 soil LTAR
- 4-bedroom: Accepted Product Primary and T&J Panel Repair (per Engineered Flow-Reduction)





Central Carolina Soil Consulting, PLLC 1900 South Main Street, Suite 110 Wake Forest, North Carolina 27587 Phone (919)569-6704 Fax (919)569-6703

Soils Map Lot 10, Cotton Farms Subdivision Harnett County, North Carolina Job#: 4609

Drawn By: JR

Date: 06/14/2023

Revision: