

Rear Covered Patio, Left Rear 6x6 Patio Post
1 piece(s) 6 x 6 SP No.1

Post Height: 11' 6"



Design Results	Actual	Allowed	Result	LDF	Load: Combination
Slenderness	25	50	Passed (50%)	--	--
Compression (lbs)	3050	16891	Passed (18%)	1.15	1.0 D + 1.0 S
Base Bearing (lbs)	3050	12856	Passed (24%)	--	1.0 D + 1.0 S
Bending/Compression	0.11	1	Passed (11%)	1.15	1.0 D + 1.0 S

- Input axial load eccentricity for this design is 16.67% of applicable member side dimension.
- Applicable calculations are based on NDS.

Supports	Type	Material
Base	Beam	Spruce-Pine-Fir

Member Type : Free Standing Post
Building Code : IBC 2015
Design Methodology : ASD

Max Unbraced Length	Comments
Full Member Length	No bracing assumed.

Drawing is Conceptual

Vertical Load	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Point (lb)	1196	80	1854	Default Load

Member Notes
Left Rear 6x6 Covered Patio Post Calculation

Weyerhaeuser Notes
Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library .
The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes
Johnathan Hall H Squared Home Design (919) 207-1403 jhall6473@gmail.com	

